



Sidewalk Inventory

Draft Report

Borough of,
Naugatuck

April 2014

Borough of Naugatuck, Connecticut



Sidewalk Inventory

DRAFT

Inventory and Inspection Reports Table of Contents

1. Repair Bands & Backlog

- Sidewalk Repair Methods and Unit Pricing Asphalt
- Sidewalk Repair Methods and Unit Pricing Concrete
- Backlog Summary Asphalt
- Backlog Summary Concrete
- Backlog Summary Mix Materials

2. Inventory & Condition

- Sidewalk Location Summary
- Sidewalk Condition Summary
- Sidewalk Condition Summary With Detailed Description

3. Capital Planning

- Sidewalk Condition and Estimated Costs Asphalt
- Sidewalk Condition and Estimated Costs Concrete
- Sidewalk Condition and Estimated Costs Mix Materials

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Repair Methods - Asphalt

Repair Method	Condition	Unit Cost Sq.Yrd.
Defer Maintenance	Excellent	\$0.00
10% Replacement	Good	\$15.00
25% Replacement	Fair	\$25.00
50% Replacement	Poor	\$50.00
100% Replacement	Replace	\$75.00

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Repair Methods - Concrete

Repair Method	Condition	Unit Cost Sq.Yrd.
Defer Maintenance	Excellent	\$0.00
10% Replacement	Good	\$15.00
25% Replacement	Fair	\$50.00
50% Replacement	Poor	\$75.00
100% Replacement	Replace	\$150.00

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Summary - Asphalt

Repair Method	Length (Miles)	Estimated Cost
Replace	0.46	\$61,316.67
Poor	0.37	\$37,705.56
Fair	1.18	\$59,972.22
Good	1.86	\$63,165.00
Excellent	0.58	\$0.00
Total	4.46	\$222,159.44

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Summary - Concrete

Repair Method	Length (Miles)	Estimated Cost
Replace	1.19	\$367,800.00
Poor	6.25	\$1,074,258.33
Fair	13.34	\$1,531,755.56
Good	8.35	\$288,740.00
Excellent	14.93	\$0.00
Total	44.05	\$3,262,553.89

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Summary - Mix

Repair Method	Length (Miles)	Estimated Cost
Replace	1.36	\$240,133.33
Poor	2.45	\$279,905.56
Fair	4.53	\$262,311.11
Good	2.98	\$100,315.00
Excellent	0.51	\$0.00
Total	11.84	\$882,665.00

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Location and Length Summary

Sidewalk Location	Length (Miles)
Even	3.77
Odd	5.30
Odd/Even	51.27

Total: 60.34

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Condition Summary

	From	To	Side	Length	Width	Material	Repair Method	Condition
ACUSHNET STREET								
ACUSHNET ST-01	GOLDEN HILL ST	STANLEY ST	Odd	95	2	Concrete	100% Replacement	Replace
				Total Length: 95				
ADRIATIC LANE								
ADRIATIC LN-01	VILLAGE CIR	D'ARCANGELO DR	Even	147	4	Concrete	Defer Maintenance	Excellent
ADRIATIC LN-01	VILLAGE CIR	D'ARCANGELO DR	Odd	147	4	Concrete	Defer Maintenance	Excellent
ADRIATIC LN-02	D'ARCANGELO DR	WISTERIA DR	Even	149	4	Concrete	Defer Maintenance	Excellent
ADRIATIC LN-02	D'ARCANGELO DR	WISTERIA DR	Odd	149	4	Concrete	Defer Maintenance	Excellent
				Total Length: 592				
AETNA STREET								
AETNA ST-02	GALPIN ST	BEEBE ST	Even	21	2	Concrete	25% Replacement	Fair
AETNA ST-02	GALPIN ST	BEEBE ST	Odd	31	4	Asphalt	Defer Maintenance	Excellent
AETNA ST-03	BEEBE ST	EDWARD ST	Even	18	4	Concrete	Defer Maintenance	Excellent
AETNA ST-04	EDWARD ST	GOODYEAR AVE	Even	120	4	Concrete	10% Replacement	Good
AETNA ST-05	GOODYEAR AVE	NETTLETON AVE	Even	260	4	Concrete	25% Replacement	Fair
AETNA ST-05	GOODYEAR AVE	NETTLETON AVE	Odd	260	4	Concrete	25% Replacement	Fair
AETNA ST-06	NETTLETON AVE	CLIFF ST	Even	629	4	Concrete	25% Replacement	Fair
AETNA ST-06	NETTLETON AVE	CLIFF ST	Odd	629	4	Concrete	50% Replacement	Poor
AETNA ST-07	CLIFF ST	AETNA PL	Even	216	4	Concrete	50% Replacement	Poor
AETNA ST-07	CLIFF ST	AETNA PL	Odd	216	4	Concrete	50% Replacement	Poor
AETNA ST-08	AETNA PL	RUBBER AVE	Even	243	4	Concrete	50% Replacement	Poor
AETNA ST-08	AETNA PL	RUBBER AVE	Odd	243	4	Concrete	100% Replacement	Replace
				Total Length: 2,886				
ANDERSON STREET								
ANDERSON ST	SCHOOL ST	SPRING ST	Even	739	4	Asphalt	10% Replacement	Good
ANDERSON ST	SCHOOL ST	SPRING ST	Odd	739	4	Asphalt	10% Replacement	Good
				Total Length: 1,478				
ANDREW AVENUE								
ANDREW AVE-01	RUBBER AVE	SCOTT ST	Even	38	4	Concrete	Defer Maintenance	Excellent
ANDREW AVE-01	RUBBER AVE	SCOTT ST	Odd	76	4	Concrete	Defer Maintenance	Excellent
ANDREW AVE-03	MANNERS AVE	MELBOURNE ST	Even	959	4	Mix	10% Replacement	Good
				Total Length: 1,073				
APPLE BLOSSOM DRIVE								

	From	To	Side	Length	Width	Material	Repair Method	Condition
APPLE BLOSSOM DR	FAWN MEADOW DR	CUL DE SAC	Even	641	4	Concrete	Defer Maintenance	Excellent
APPLE BLOSSOM DR	FAWN MEADOW DR	CUL DE SAC	Odd	641	4	Concrete	Defer Maintenance	Excellent
Total Length: 1,282								
APPLEWOOD LANE								
APPLEWOOD LN-01	WOOSTER ST	TYLER HILL RD	Even	1039	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-01	WOOSTER ST	TYLER HILL RD	Odd	1039	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-02	TYLER HILL RD	SKYVIEW DR	Even	1147	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-02	TYLER HILL RD	SKYVIEW DR	Odd	1147	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-03	SKYVIEW DR	DONOVAN RD	Even	521	4	Concrete	10% Replacement	Good
APPLEWOOD LN-03	SKYVIEW DR	DONOVAN RD	Odd	695	4	Concrete	10% Replacement	Good
APPLEWOOD LN-04	DONOVAN RD	ROSEWOOD CT	Even	350	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-04	DONOVAN RD	ROSEWOOD CT	Odd	350	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-05	ROSEWOOD CT	COUNTRY HOLLOW RD	Even	537	4	Concrete	Defer Maintenance	Excellent
APPLEWOOD LN-05	ROSEWOOD CT	COUNTRY HOLLOW RD	Odd	537	4	Concrete	10% Replacement	Good
Total Length: 7,362								
ARBOR AVENUE								
ARBOR AVE-01	MAPLE HILL RD	KENT ST	Even	304	4	Asphalt	25% Replacement	Fair
ARBOR AVE-02	KENT ST	RUSTLING REED RD	Even	297	4	Asphalt	10% Replacement	Good
Total Length: 601								
ARCH STREET								
ARCH ST	SCOTT ST	RUBBER AVE	Even	737	4	Mix	25% Replacement	Fair
ARCH ST	SCOTT ST	RUBBER AVE	Odd	184	4	Concrete	Defer Maintenance	Excellent
Total Length: 921								
AUBURN STREET								
AUBURN ST-07	ALBION ST	CUL DE SAC	Even	508	4	Concrete	Defer Maintenance	Excellent
AUBURN ST-07	ALBION ST	CUL DE SAC	Odd	305	4	Concrete	Defer Maintenance	Excellent
Total Length: 813								
BARNUM COURT								
BARNUM CT	CHURCH ST	DEAD END	Even	60	2	Mix	10% Replacement	Good
Total Length: 60								
BEARDSLEY AVENUE								
BEARDSLEY AVE-01	PLATTS MILLS RD	RADNOR AVE	Even	288	4	Concrete	25% Replacement	Fair
BEARDSLEY AVE-01	PLATTS MILLS RD	RADNOR AVE	Odd	288	4	Concrete	10% Replacement	Good
BEARDSLEY AVE-02	RADNOR AVE	WATERBURY TL	Even	649	4	Concrete	50% Replacement	Poor
BEARDSLEY AVE-02	RADNOR AVE	WATERBURY TL	Odd	584	4	Concrete	25% Replacement	Fair
Total Length: 1,809								
BEEBE STREET								
BEEBE ST	AETNA ST	HIGHLAND AVE	Even	986	4	Concrete	50% Replacement	Poor

	From	To	Side	Length	Width	Material	Repair Method	Condition
BEEBE ST	AETNA ST	HIGHLAND AVE	Odd	986	4	Mix	25% Replacement	Fair
				Total Length: 1,972				
BEECHER STREET								
BEECHER ST	BUCKINGHAM ST	SHERMAN ST	Even	573	4	Concrete	10% Replacement	Good
BEECHER ST	BUCKINGHAM ST	SHERMAN ST	Odd	573	4	Concrete	25% Replacement	Fair
				Total Length: 1,146				
BRADLEY STREET								
BRADLEY ST	OAK ST	HILL ST	Even	555	4	Concrete	50% Replacement	Poor
BRADLEY ST	OAK ST	HILL ST	Odd	555	4	Mix	25% Replacement	Fair
				Total Length: 1,110				
BRENNAN STREET								
BRENNAN ST-01	BRIDGE ST	CROWN ST	Even	21	4	Concrete	Defer Maintenance	Excellent
BRENNAN ST-01	BRIDGE ST	CROWN ST	Odd	429	4	Concrete	Defer Maintenance	Excellent
BRENNAN ST-02	CROWN ST	SPRING ST	Odd	28	4	Concrete	Defer Maintenance	Excellent
				Total Length: 478				
BROOKSIDE AVENUE								
BROOKSIDE AVE-01	RUBBER AVE	NORTH CIR	Even	555	4	Concrete	10% Replacement	Good
BROOKSIDE AVE-01	RUBBER AVE	NORTH CIR	Odd	555	4	Concrete	50% Replacement	Poor
BROOKSIDE AVE-02	NORTH CIR	SOUTH CIR	Even	288	4	Concrete	25% Replacement	Fair
BROOKSIDE AVE-02	NORTH CIR	SOUTH CIR	Odd	288	4	Mix	50% Replacement	Poor
BROOKSIDE AVE-03	SOUTH CIR	MELBOURNE CT	Even	373	4	Mix	25% Replacement	Fair
BROOKSIDE AVE-03	SOUTH CIR	MELBOURNE CT	Odd	280	4	Concrete	50% Replacement	Poor
				Total Length: 2,339				
BUCKINGHAM STREET								
BUCKINGHAM ST-01	HILLSIDE AVE	BEECHER ST	Even	389	4	Concrete	10% Replacement	Good
BUCKINGHAM ST-01	HILLSIDE AVE	BEECHER ST	Odd	389	4	Concrete	10% Replacement	Good
BUCKINGHAM ST-02	BEECHER ST	JUDD ST	Even	373	4	Concrete	25% Replacement	Fair
BUCKINGHAM ST-02	BEECHER ST	JUDD ST	Odd	373	4	Concrete	25% Replacement	Fair
BUCKINGHAM ST-03	JUDD ST	NORTH CHURCH ST	Even	279	4	Concrete	10% Replacement	Good
BUCKINGHAM ST-03	JUDD ST	NORTH CHURCH ST	Odd	279	4	Concrete	10% Replacement	Good
				Total Length: 2,082				
CALVIN STREET								
CALVIN ST	N MAIN ST	HIGH ST	Odd	659	4	Concrete	Defer Maintenance	Excellent
				Total Length: 659				
CAROLYN CIRCLE								
CAROLYN CIR	PICTURE LN	PICTURE LN	Even	364	3	Concrete	25% Replacement	Fair
CAROLYN CIR	PICTURE LN	PICTURE LN	Odd	364	3	Concrete	25% Replacement	Fair
				Total Length: 728				

	From	To	Side	Length	Width	Material	Repair Method	Condition
CARROLL COURT								
CARROLL CT	CARROLL ST	DEAD END	Even	338	3	Concrete	25% Replacement	Fair
CARROLL CT	CARROLL ST	DEAD END	Odd	338	4	Concrete	25% Replacement	Fair
				Total Length: 676				
CARROLL STREET								
CARROLL ST-01	MAPLE ST	CENTRAL AVE	Even	790	4	Concrete	Defer Maintenance	Excellent
CARROLL ST-01	MAPLE ST	CENTRAL AVE	Odd	790	4	Concrete	Defer Maintenance	Excellent
CARROLL ST-02	CENTRAL AVE	CARROLL CT	Even	261	4	Concrete	Defer Maintenance	Excellent
CARROLL ST-02	CENTRAL AVE	CARROLL CT	Odd	261	4	Concrete	Defer Maintenance	Excellent
CARROLL ST-03	CARROLL CT	HIGH ST	Even	181	4	Concrete	50% Replacement	Poor
CARROLL ST-03	CARROLL CT	HIGH ST	Odd	181	4	Concrete	25% Replacement	Fair
				Total Length: 2,464				
CEDAR STREET								
CEDAR ST	CHURCH ST	WATER ST	Even	289	5	Concrete	10% Replacement	Good
CEDAR ST	CHURCH ST	WATER ST	Odd	578	5	Mix	10% Replacement	Good
				Total Length: 867				
CENTRAL AVENUE								
CENTRAL AVE	MAPLE ST	CARROLL ST	Odd	210	4	Concrete	100% Replacement	Replace
				Total Length: 210				
CHARLES STREET								
CHARLES ST-02	CHARLES CT	ANN ST	Odd	209	4	Concrete	Defer Maintenance	Excellent
				Total Length: 209				
CHERRY STREET								
CHERRY ST-01	SPENCER ST	OLIVE ST	Even	1103	5	Concrete	Defer Maintenance	Excellent
CHERRY ST-01	SPENCER ST	OLIVE ST	Odd	1103	4	Concrete	Defer Maintenance	Excellent
CHERRY ST-02	OLIVE ST	ROUTE 63	Even	1287	4	Concrete	Defer Maintenance	Excellent
CHERRY ST-02	OLIVE ST	ROUTE 63	Odd	1287	4	Concrete	Defer Maintenance	Excellent
				Total Length: 4,780				
CHERRY STREET EXTENSION								
CHERRY ST EXT-01	SPENCER ST	CHARLES ST	Even	447	4	Concrete	Defer Maintenance	Excellent
CHERRY ST EXT-01	SPENCER ST	CHARLES ST	Odd	447	4	Concrete	Defer Maintenance	Excellent
CHERRY ST EXT-02	CHARLES ST	ANN ST	Even	141	4	Concrete	Defer Maintenance	Excellent
CHERRY ST EXT-02	CHARLES ST	ANN ST	Odd	401	4	Concrete	10% Replacement	Good
CHERRY ST EXT-03	ANN ST	DEAD END	Even	141	4	Asphalt	100% Replacement	Replace
CHERRY ST EXT-03	ANN ST	DEAD END	Odd	70	4	Asphalt	100% Replacement	Replace
				Total Length: 1,647				
CHESTNUT STREET								
CHESTNUT ST-01	N HOADLEY ST	FERN ST	Odd	277	4	Mix	100% Replacement	Replace

	From	To	Side	Length	Width	Material	Repair Method	Condition
CHESTNUT ST-02	FERN ST	QUINN ST	Odd	261	4	Asphalt	25% Replacement	Fair
CHESTNUT ST-03	QUINN ST	PARK AVE	Even	86	4	Concrete	Defer Maintenance	Excellent
CHESTNUT ST-03	QUINN ST	PARK AVE	Odd	143	3	Mix	10% Replacement	Good

Total Length: 767

CHURCH STREET

CHURCH ST-01	RUBBER AVE	BARNUM CT	Even	527	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-01	RUBBER AVE	BARNUM CT	Odd	527	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-02	BARNUM CT	PARK PL	Even	262	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-02	BARNUM CT	PARK PL	Odd	262	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-03	PARK PL	MAPLE ST	Even	428	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-03	PARK PL	MAPLE ST	Odd	428	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-04	MAPLE ST	DIVISION ST	Even	150	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-04	MAPLE ST	DIVISION ST	Odd	150	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-05	DIVISION ST	CEDAR ST	Even	547	6	Concrete	Defer Maintenance	Excellent
CHURCH ST-05	DIVISION ST	CEDAR ST	Odd	547	6	Concrete	25% Replacement	Fair
CHURCH ST-06	CEDAR ST	MEADOW CT	Even	448	4	Concrete	25% Replacement	Fair
CHURCH ST-06	CEDAR ST	MEADOW CT	Odd	448	4	Concrete	25% Replacement	Fair
CHURCH ST-07	MEADOW CT	WATER ST	Even	677	4	Concrete	10% Replacement	Good
CHURCH ST-07	MEADOW CT	WATER ST	Odd	677	4	Concrete	10% Replacement	Good

Total Length: 6,078

CITY BROOK ROAD

CITY BROOK RD-01	CITY HILL ST	SKYVIEW DR	Even	641	4	Concrete	10% Replacement	Good
CITY BROOK RD-01	CITY HILL ST	SKYVIEW DR	Odd	675	4	Concrete	10% Replacement	Good
CITY BROOK RD-02	SKYVIEW DR	DONOVAN RD	Even	460	4	Concrete	10% Replacement	Good
CITY BROOK RD-02	SKYVIEW DR	DONOVAN RD	Odd	460	4	Concrete	25% Replacement	Fair

Total Length: 2,236

CITY HILL STREET

CITY HILL ST-01	N MIAN ST	CITY HILL CT	Even	641	4	Concrete	50% Replacement	Poor
CITY HILL ST-01	N MIAN ST	CITY HILL CT	Odd	641	4	Mix	25% Replacement	Fair
CITY HILL ST-02	CITY HILL CT	HIGH ST	Even	406	4	Concrete	50% Replacement	Poor
CITY HILL ST-02	CITY HILL CT	HIGH ST	Odd	406	4	Concrete	25% Replacement	Fair
CITY HILL ST-03	HIGH ST	JOHN ST	Even	491	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-04	JOHN ST	WOOSTER ST	Even	473	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-04	JOHN ST	WOOSTER ST	Odd	118	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-05	WOOSTER ST	COEN LN	Even	1012	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-05	WOOSTER ST	COEN LN	Odd	202	4	Concrete	10% Replacement	Good
CITY HILL ST-06	COEN LN	MORRIS ST	Odd	263	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-07	MORRIS ST	CITY BROOK RD	Odd	920	4	Concrete	Defer Maintenance	Excellent
CITY HILL ST-08	CITY BROOK RD	DONOVAN RD	Odd	196	2	Asphalt	100% Replacement	Replace

	From	To	Side	Length	Width	Material	Repair Method	Condition
Total Length: 5,769								
CLARK ROAD								
CLARK RD-01	NEW HAVEN RD	VALLEY MOBILE HOME PARK	Even	643	2	Asphalt	100% Replacement	Replace
Total Length: 643								
CLEARVIEW CIRCLE								
CLEARVIEW CIR	MILLVILLE AVE	MILLVILLE AVE	Even	1017	4	Concrete	25% Replacement	Fair
CLEARVIEW CIR	MILLVILLE AVE	MILLVILLE AVE	Odd	1272	4	Concrete	10% Replacement	Good
Total Length: 2,289								
CLIFF STREET								
CLIFF ST-01	AETNA ST	LE CLAIR CT	Even	258	4	Concrete	10% Replacement	Good
CLIFF ST-01	AETNA ST	LE CLAIR CT	Odd	13	4	Asphalt	Defer Maintenance	Excellent
CLIFF ST-02	LE CLAIR CT	PLEASANT VIEW ST	Even	467	4	Concrete	25% Replacement	Fair
CLIFF ST-02	LE CLAIR CT	PLEASANT VIEW ST	Odd	467	4	Mix	10% Replacement	Good
CLIFF ST-03	PLEASANT VIEW ST	GEORGE ST	Even	423	4	Concrete	25% Replacement	Fair
CLIFF ST-03	PLEASANT VIEW ST	GEORGE ST	Odd	423	4	Concrete	25% Replacement	Fair
CLIFF ST-04	GEORGE ST	FREDRICK ST	Even	241	4	Concrete	10% Replacement	Good
CLIFF ST-04	GEORGE ST	FREDRICK ST	Odd	241	4	Concrete	25% Replacement	Fair
CLIFF ST-05	FREDRICK ST	WALNUT ST	Even	321	4	Concrete	50% Replacement	Poor
CLIFF ST-05	FREDRICK ST	WALNUT ST	Odd	321	4	Concrete	25% Replacement	Fair
CLIFF ST-06	WALNUT ST	FAIRVIEW AVE	Even	314	4	Concrete	25% Replacement	Fair
CLIFF ST-06	WALNUT ST	FAIRVIEW AVE	Odd	314	4	Concrete	100% Replacement	Replace
Total Length: 3,803								
COBBLE STREETONE COURT								
COBBLE STONE CT	PEMBROOK RD	CUL DE SAC	Even	419	4	Concrete	Defer Maintenance	Excellent
COBBLE STONE CT	PEMBROOK RD	CUL DE SAC	Odd	375	4	Concrete	Defer Maintenance	Excellent
Total Length: 794								
COEN STREET								
COEN ST	OAK ST	DEAD END	Even	956	4	Concrete	25% Replacement	Fair
COEN ST	OAK ST	DEAD END	Odd	956	4	Concrete	25% Replacement	Fair
Total Length: 1,912								
COLD SPRING CIRCLE								
COLD SPRING CIR-01	BROOK ST	CUL DE SAC	Even	223	3	Concrete	50% Replacement	Poor
COLD SPRING CIR-01	BROOK ST	CUL DE SAC	Odd	223	3	Concrete	10% Replacement	Good
COLD SPRING CIR-02	CUL DE SAC	COLD SPRING CIR	Even	1137	3	Concrete	25% Replacement	Fair
COLD SPRING CIR-02	CUL DE SAC	COLD SPRING CIR	Odd	1137	3	Concrete	25% Replacement	Fair
Total Length: 2,720								
CROFUT ROAD								
CROFUT RD	WEBB RD	RUBBER AVE EXT	Odd	581	3	Concrete	10% Replacement	Good

	From	To	Side	Length	Width	Material	Repair Method	Condition	
Total Length: 581									
CROSSING NORTH									
	PINEWOOD CROSSING NORTH SILVER BEECH DR	CUL DE SAC	Even	411	4	Concrete	Defer Maintenance	Excellent	
	PINEWOOD CROSSING NORTH SILVER BEECH DR	CUL DE SAC	Odd	411	4	Concrete	Defer Maintenance	Excellent	
Total Length: 822									
CULVER STREET									
	CULVER ST-01	HILL ST	HILLCREST AVE	Even	279	4	Concrete	25% Replacement	Fair
	CULVER ST-02	HILLCREST AVE	HOMESTEAD AVE	Even	261	3	Concrete	50% Replacement	Poor
	CULVER ST-02	HILLCREST AVE	HOMESTEAD AVE	Odd	234	4	Concrete	10% Replacement	Good
Total Length: 774									
CURTISS STREET									
	CURTISS ST-01	N MAIN ST	LINDEN ST	Even	537	5	Concrete	50% Replacement	Poor
	CURTISS ST-01	N MAIN ST	LINDEN ST	Odd	269	4	Concrete	25% Replacement	Fair
	CURTISS ST-02	LINDEN ST	GRIFFIN ST	Even	708	4	Asphalt	50% Replacement	Poor
	CURTISS ST-02	LINDEN ST	GRIFFIN ST	Odd	106	4	Mix	Defer Maintenance	Excellent
	CURTISS ST-03	GRIFFINS ST	ROUTE 8	Even	305	4	Concrete	100% Replacement	Replace
	CURTISS ST-03	GRIFFINS ST	ROUTE 8	Odd	305	4	Concrete	50% Replacement	Poor
Total Length: 2,230									
DAMSON LANE									
	DAMSON LN-01	N HOADLEY ST	BIRCH LN	Even	188	4	Mix	10% Replacement	Good
	DAMSON LN-01	N HOADLEY ST	BIRCH LN	Odd	188	4	Concrete	10% Replacement	Good
	DAMSON LN-02	BIRCH LN	N HOADLEY ST	Even	866	4	Mix	100% Replacement	Replace
	DAMSON LN-02	BIRCH LN	N HOADLEY ST	Odd	866	4	Concrete	50% Replacement	Poor
Total Length: 2,108									
DEERING LANE									
	DEERING LN	N HOADLEY ST	DEAD END	Even	588	4	Mix	10% Replacement	Good
	DEERING LN	N HOADLEY ST	DEAD END	Odd	588	4	Mix	25% Replacement	Fair
Total Length: 1,176									
DIAMOND STREET									
	DIAMOND ST	SPRING ST	BRENNAN ST	Even	395	4	Concrete	10% Replacement	Good
	DIAMOND ST	SPRING ST	BRENNAN ST	Odd	395	4	Concrete	10% Replacement	Good
Total Length: 790									
DIVISION STREET									
	DIVISION ST	CHURCH ST	MEADOW ST	Even	349	4	Concrete	25% Replacement	Fair
	DIVISION ST	CHURCH ST	MEADOW ST	Odd	349	4	Concrete	10% Replacement	Good
Total Length: 698									
DONOVAN ROAD									

	From	To	Side	Length	Width	Material	Repair Method	Condition
DONOVAN RD-01	MAY ST	CITY HILL ST	Even	252	4	Concrete	Defer Maintenance	Excellent
DONOVAN RD-02	CITY HILL ST	CITY BROOK RD	Even	475	4	Concrete	Defer Maintenance	Excellent
DONOVAN RD-03	CITY BROOK RD	APPLEWOOD LN	Even	328	4	Concrete	10% Replacement	Good
DONOVAN RD-04	APPLEWOOD LN	SIRRA RIDGE RD	Even	436	4	Concrete	10% Replacement	Good
DONOVAN RD-04	APPLEWOOD LN	SIRRA RIDGE RD	Odd	872	4	Concrete	10% Replacement	Good
DONOVAN RD-05	SIERRA RIDGE RD	DONOVAN CT	Odd	590	4	Concrete	10% Replacement	Good
DONOVAN RD-06	DONOVAN CT	WOOSTER ST	Odd	468	4	Asphalt	Defer Maintenance	Excellent

Total Length: 3,421

EAGLE STREET

EAGLE ST-01	PROSPECT ST	ENDOGEN ST	Even	31	3	Asphalt	10% Replacement	Good
-------------	-------------	------------	------	----	---	---------	-----------------	------

Total Length: 31

EAST DRIVE

EAST DR	PARK AVE	QUINN ST	Even	206	4	Asphalt	25% Replacement	Fair
EAST DR	PARK AVE	QUINN ST	Odd	41	4	Concrete	100% Replacement	Replace

Total Length: 247

ELM STREET

ELM ST-01	RUBBER AVE	SCOTT ST	Odd	826	4	Mix	25% Replacement	Fair
ELM ST-02	SCOTT ST	CHERRY ST	Odd	292	4	Concrete	Defer Maintenance	Excellent
ELM ST-03	CHERRY ST	SPENCER ST	Odd	321	4	Mix	100% Replacement	Replace

Total Length: 1,439

ELMWOOD STREET

ELMWOOD ST-01	WALNUT ST	ELMHURST ST	Even	239	4	Concrete	25% Replacement	Fair
ELMWOOD ST-01	WALNUT ST	ELMHURST ST	Odd	239	4	Concrete	25% Replacement	Fair
ELMWOOD ST-02	ELMHURST ST	HILLSIDE AVE	Even	208	4	Concrete	Defer Maintenance	Excellent
ELMWOOD ST-02	ELMHURST ST	HILLSIDE AVE	Odd	208	4	Concrete	10% Replacement	Good

Total Length: 894

FAIRCHILD STREET

FAIRCHILD ST-01	LEWIS ST	MALGARI CT	Even	321	4	Concrete	10% Replacement	Good
FAIRCHILD ST-01	LEWIS ST	MALGARI CT	Odd	429	4	Mix	25% Replacement	Fair
FAIRCHILD ST-02	MALGARI CT	HARD ST	Odd	234	4	Mix	10% Replacement	Good
FAIRCHILD ST-03	HARD ST	GORMAN ST	Even	106	4	Concrete	10% Replacement	Good

Total Length: 1,090

FAIRFIELD COURT

FAIRFIELD CT	FIELD ST	CUL DE SAC	Odd	20	4	Concrete	Defer Maintenance	Excellent
--------------	----------	------------	-----	----	---	----------	-------------------	-----------

Total Length: 20

FAIRLAWN STREET

FAIRLAWN ST	HILL ST	HILLCREST AVE	Even	237	4	Concrete	25% Replacement	Fair
FAIRLAWN ST	HILL ST	HILLCREST AVE	Odd	237	4	Concrete	25% Replacement	Fair

	From	To	Side	Length	Width	Material	Repair Method	Condition
Total Length: 474								
FAIRVIEW AVENUE								
FAIRVIEW AVE-01	POND ST	PLEASANT VIEW ST	Even	277	4	Concrete	50% Replacement	Poor
FAIRVIEW AVE-01	POND ST	PLEASANT VIEW ST	Odd	277	5	Mix	10% Replacement	Good
FAIRVIEW AVE-02	PLEASANT VIEW ST	GEORGE ST	Even	748	0	Concrete	100% Replacement	Replace
FAIRVIEW AVE-02	PLEASANT VIEW ST	GEORGE ST	Odd	748	0	Mix	10% Replacement	Good
FAIRVIEW AVE-03	GEORGE ST	FREDRICK ST	Even	242	4	Concrete	25% Replacement	Fair
FAIRVIEW AVE-03	GEORGE ST	FREDRICK ST	Odd	242	6	Concrete	Defer Maintenance	Excellent
FAIRVIEW AVE-04	FREDRICK ST	CLIFF ST	Even	203	4	Concrete	50% Replacement	Poor
FAIRVIEW AVE-04	FREDRICK ST	CLIFF ST	Odd	203	5	Concrete	25% Replacement	Fair
FAIRVIEW AVE-05	CLIFF ST	HILLSIDE AVE	Even	271	4	Concrete	50% Replacement	Poor
FAIRVIEW AVE-05	CLIFF ST	HILLSIDE AVE	Odd	271	5	Concrete	10% Replacement	Good
Total Length: 3,482								
FARMSTEAD LANE								
FARMSTEAD LN	GRAHAM RIDGE RD	CUL DE SAC	Odd	691	4	Concrete	Defer Maintenance	Excellent
Total Length: 691								
FAWN MEADOW DRIVE								
FAWN MEADOW DR-01	MULBERRY ST	WILD CHERRY DR	Even	948	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-01	MULBERRY ST	WILD CHERRY DR	Odd	948	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-02	WILD CHERRY DR	APPLE BLOSSOM DR	Even	1065	4	Concrete	10% Replacement	Good
FAWN MEADOW DR-02	WILD CHERRY DR	APPLE BLOSSOM DR	Odd	1065	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-03	APPLE BLOSSOM DR	PEAR TREE DR	Even	337	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-03	APPLE BLOSSOM DR	PEAR TREE DR	Odd	337	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-04	PEAR TREE DR	SWIFT LN	Even	329	4	Concrete	Defer Maintenance	Excellent
FAWN MEADOW DR-04	PEAR TREE DR	SWIFT LN	Odd	329	4	Concrete	Defer Maintenance	Excellent
Total Length: 5,358								
FERN STREET								
FERN ST-01	CHESTNUT ST	COTTAGE ST	Even	166	4	Asphalt	Defer Maintenance	Excellent
FERN ST-02	COTTAGE ST	MILLVILLE AVE	Even	654	4	Mix	100% Replacement	Replace
FERN ST-02	COTTAGE ST	MILLVILLE AVE	Odd	588	4	Mix	25% Replacement	Fair
Total Length: 1,408								
FIELD STREET								
FIELD ST-14	HILLSIDE AVE	NORTH CHURCH ST	Odd	262	4	Concrete	Defer Maintenance	Excellent
Total Length: 262								
FREDRICK STREET								
FREDRICK ST	FAIRVIEW AVE	CLIFF ST	Even	417	4	Concrete	25% Replacement	Fair
FREDRICK ST	FAIRVIEW AVE	CLIFF ST	Odd	417	4	Concrete	100% Replacement	Replace
Total Length: 834								

	From	To	Side	Length	Width	Material	Repair Method	Condition
GALPIN STREET								
GALPIN ST-01	AETNA ST	MARSHALL AVE	Even	587	4	Concrete	50% Replacement	Poor
GALPIN ST-01	AETNA ST	MARSHALL AVE	Odd	587	4	Concrete	25% Replacement	Fair
GALPIN ST-02	MARSHALL AVE	WEST ST	Even	238	4	Concrete	25% Replacement	Fair
GALPIN ST-02	MARSHALL AVE	WEST ST	Odd	238	4	Concrete	50% Replacement	Poor
GALPIN ST-03	WEST ST	HIGHLAND AVE	Even	225	4	Mix	25% Replacement	Fair
GALPIN ST-03	WEST ST	HIGHLAND AVE	Odd	225	4	Mix	25% Replacement	Fair
				Total Length: 2,100				
GENERAL DALTON DRIVE								
GENERAL DALTON DR-01	MARJORIE ST	GENERAL DALTON DR	Even	610	4	Concrete	10% Replacement	Good
GENERAL DALTON DR-01	MARJORIE ST	GENERAL DALTON DR	Odd	610	4	Concrete	25% Replacement	Fair
GENERAL DALTON DR-02	GENERAL DALTON DR	DEAD END	Even	75	4	Concrete	10% Replacement	Good
GENERAL DALTON DR-02	GENERAL DALTON DR	DEAD END	Odd	135	4	Concrete	10% Replacement	Good
				Total Length: 1,430				
GENERAL PATTON DRIVE								
GENERAL PATTON DR-01	MARJORIE ST	GENERAL DALTON DR	Even	762	4	Concrete	25% Replacement	Fair
GENERAL PATTON DR-01	MARJORIE ST	GENERAL DALTON DR	Odd	802	4	Concrete	25% Replacement	Fair
GENERAL PATTON DR-02	GENERAL DALTON DR	GLENDALE CT	Even	684	4	Concrete	25% Replacement	Fair
GENERAL PATTON DR-02	GENERAL DALTON DR	GLENDALE CT	Odd	513	4	Concrete	10% Replacement	Good
GENERAL PATTON DR-03	GLENDALE CT	DEAD END	Even	155	4	Concrete	10% Replacement	Good
				Total Length: 2,916				
GENERAL PULASKI WALK								
GENERAL PULASKI WALK	BRIDGE ST	DEAD END	Even	500	4	Concrete	50% Replacement	Poor
GENERAL PULASKI WALK	BRIDGE ST	DEAD END	Odd	300	4	Concrete	10% Replacement	Good
				Total Length: 800				
GEORGE STREET								
GEORGE ST	FAIRVIEW AVE	CLIFF ST	Even	402	4	Concrete	25% Replacement	Fair
GEORGE ST	FAIRVIEW AVE	CLIFF ST	Odd	402	4	Concrete	25% Replacement	Fair
				Total Length: 804				
GOLDEN HILL STREET								
GOLDEN HILL ST-01	PROSPECT ST	ACUSHNET ST	Even	584	4	Concrete	25% Replacement	Fair
GOLDEN HILL ST-01	PROSPECT ST	ACUSHNET ST	Odd	584	3	Concrete	50% Replacement	Poor
GOLDEN HILL ST-02	ACUSHNET ST	WOODBINE ST	Even	428	3	Concrete	50% Replacement	Poor
GOLDEN HILL ST-02	ACUSHNET ST	WOODBINE ST	Odd	428	3	Concrete	50% Replacement	Poor
				Total Length: 2,024				
GOODYEAR AVENUE								
GOODYEAR AVE-01	AETNA ST	TROWBRIDGE PL	Even	732	4	Concrete	50% Replacement	Poor
GOODYEAR AVE-01	AETNA ST	TROWBRIDGE PL	Odd	732	4	Concrete	25% Replacement	Fair

	From	To	Side	Length	Width	Material	Repair Method	Condition
GOODYEAR AVE-02	TROWBRIDGE PL	HIGHLAND AVE	Even	307	4	Concrete	50% Replacement	Poor
GOODYEAR AVE-02	TROWBRIDGE PL	HIGHLAND AVE	Odd	307	4	Concrete	25% Replacement	Fair

Total Length: 2,078

GORMAN STREET

GORMAN ST-01	LEWIS ST	OLIVE ST	Even	694	4	Concrete	25% Replacement	Fair
GORMAN ST-01	LEWIS ST	OLIVE ST	Odd	298	4	Concrete	25% Replacement	Fair
GORMAN ST-02	OLIVE ST	VAGNINI DR	Even	328	6	Mix	25% Replacement	Fair
GORMAN ST-02	OLIVE ST	VAGNINI DR	Odd	328	6	Mix	25% Replacement	Fair
GORMAN ST-03	VAGNINI DR	FAIRCHILD ST	Even	253	4	Concrete	10% Replacement	Good
GORMAN ST-03	VAGNINI DR	FAIRCHILD ST	Odd	253	4	Concrete	25% Replacement	Fair
GORMAN ST-04	FAIRCHILD ST	SPENCER ST	Even	562	4	Concrete	25% Replacement	Fair
GORMAN ST-04	FAIRCHILD ST	SPENCER ST	Odd	281	4	Mix	25% Replacement	Fair

Total Length: 2,997

GRAHAM RIDGE ROAD

GRAHAM RIDGE RD-01	WESTOVER DR	FARMSTEAD LN	Even	1341	4	Concrete	25% Replacement	Fair
GRAHAM RIDGE RD-01	WESTOVER DR	FARMSTEAD LN	Odd	1341	4	Concrete	10% Replacement	Good
GRAHAM RIDGE RD-02	FARMSTEAD LN	WESTOVER DR	Even	2050	4	Concrete	25% Replacement	Fair

Total Length: 4,732

GREENWOOD STREET

GREENWOOD ST-01	SCHOOL ST	BRIDGE ST	Even	466	4	Concrete	25% Replacement	Fair
GREENWOOD ST-01	SCHOOL ST	BRIDGE ST	Odd	23	4	Concrete	Defer Maintenance	Excellent
GREENWOOD ST-02	BRIDGE ST	DEAD END	Even	348	4	Concrete	25% Replacement	Fair
GREENWOOD ST-02	BRIDGE ST	DEAD END	Odd	25	4	Concrete	10% Replacement	Good

Total Length: 862

GRIFFIN STREET

GRIFFIN ST	N MAIN ST	CURTISS ST	Odd	235	4	Concrete	10% Replacement	Good
------------	-----------	------------	-----	-----	---	----------	-----------------	------

Total Length: 235

GROVE STREET

GROVE ST-01	PARK AVE	MAY AVE	Even	355	4	Concrete	25% Replacement	Fair
GROVE ST-01	PARK AVE	MAY AVE	Odd	355	4	Mix	25% Replacement	Fair
GROVE ST-02	MAY AVE	WALNUT ST	Even	289	4	Concrete	Defer Maintenance	Excellent
GROVE ST-02	MAY AVE	WALNUT ST	Odd	217	4	Concrete	100% Replacement	Replace
GROVE ST-03	WALNUT ST	WOODLAWN AVE	Even	327	4	Concrete	50% Replacement	Poor
GROVE ST-03	WALNUT ST	WOODLAWN AVE	Odd	327	4	Concrete	50% Replacement	Poor
GROVE ST-04	WOODLAWN AVE	HILLSIDE AVE	Even	371	4	Mix	10% Replacement	Good
GROVE ST-04	WOODLAWN AVE	HILLSIDE AVE	Odd	371	4	Concrete	25% Replacement	Fair

Total Length: 2,612

HARD STREET

	From	To	Side	Length	Width	Material	Repair Method	Condition
HARD ST	FAIRCHILD ST	SPENCER ST	Even	582	4	Concrete	25% Replacement	Fair
HARD ST	FAIRCHILD ST	SPENCER ST	Odd	349	4	Concrete	10% Replacement	Good

Total Length: 931

HICKORY ROAD

HICKORY RD-01	HIGH ST	BURITT PL	Even	63	4	Concrete	Defer Maintenance	Excellent
---------------	---------	-----------	------	----	---	----------	-------------------	-----------

Total Length: 63

HIGH STREET

HIGH ST-06	CALVINST	OAK ST	Even	844	4	Concrete	Defer Maintenance	Excellent
HIGH ST-07	OAK ST	HILL ST	Even	508	4	Concrete	Defer Maintenance	Excellent
HIGH ST-07	OAK ST	HILL ST	Odd	508	4	Mix	100% Replacement	Replace
HIGH ST-08	HILL ST	MAPLE TER	Odd	325	4	Concrete	25% Replacement	Fair
HIGH ST-09	MAY ST	CARROLL ST	Even	833	4	Mix	50% Replacement	Poor
HIGH ST-10	CARROLL ST	HILL ST	Even	169	4	Concrete	10% Replacement	Good
HIGH ST-11	HILL ST	HICKORY RD	Even	352	4	Mix	Defer Maintenance	Excellent
HIGH ST-11	HILL ST	HICKORY RD	Odd	352	4	Concrete	50% Replacement	Poor
HIGH ST-12	HICKORY RD	WOODLAND ST	Even	383	4	Concrete	10% Replacement	Good
HIGH ST-12	HICKORY RD	WOODLAND ST	Odd	383	4	Concrete	50% Replacement	Poor
HIGH ST-13	WOODLAND ST	S MAIN ST	Even	1502	4	Mix	25% Replacement	Fair
HIGH ST-13	WOODLAND ST	S MAIN ST	Odd	1502	4	Concrete	25% Replacement	Fair

Total Length: 7,661

HIGHLAND AVENUE

HIGHLAND AVE-01	HOADLEY ST	GALPIN ST	Even	451	4	Concrete	50% Replacement	Poor
HIGHLAND AVE-01	HOADLEY ST	GALPIN ST	Odd	451	4	Concrete	100% Replacement	Replace
HIGHLAND AVE-02	GALPIN ST	BEEBE ST	Even	250	4	Mix	50% Replacement	Poor
HIGHLAND AVE-02	GALPIN ST	BEEBE ST	Odd	250	4	Mix	25% Replacement	Fair
HIGHLAND AVE-03	BEEBE ST	DUNN AVE	Even	343	5	Mix	50% Replacement	Poor
HIGHLAND AVE-03	BEEBE ST	DUNN AVE	Odd	343	5	Mix	25% Replacement	Fair
HIGHLAND AVE-04	DUNN AVE	HIGHLAND CIR	Even	551	4	Mix	25% Replacement	Fair
HIGHLAND AVE-04	DUNN AVE	HIGHLAND CIR	Odd	551	4	Mix	50% Replacement	Poor
HIGHLAND AVE-05	HIGHLAND CIR	WALNUT ST	Even	121	4	Concrete	50% Replacement	Poor
HIGHLAND AVE-05	HIGHLAND CIR	WALNUT ST	Odd	121	4	Concrete	50% Replacement	Poor

Total Length: 3,432

HILL STREET

HILL ST-02	FAIRLAWN ST	CULVER ST	Even	274	4	Mix	25% Replacement	Fair
HILL ST-02	FAIRLAWN ST	CULVER ST	Odd	110	4	Concrete	50% Replacement	Poor
HILL ST-03	MAY ST	FAIRLAWN ST	Even	296	4	Concrete	25% Replacement	Fair
HILL ST-03	MAY ST	FAIRLAWN ST	Odd	237	4	Mix	25% Replacement	Fair

Total Length: 917

	From	To	Side	Length	Width	Material	Repair Method	Condition
HILLCREST AVENUE								
HILLCREST AVE-01	FAIRLAWN ST	MAY ST	Even	288	4	Concrete	10% Replacement	Good
HILLCREST AVE-01	FAIRLAWN ST	MAY ST	Odd	288	4	Concrete	10% Replacement	Good
HILLCREST AVE-02	CULVER ST	FAIRLAWN ST	Even	234	4	Concrete	Defer Maintenance	Excellent
HILLCREST AVE-02	CULVER ST	FAIRLAWN ST	Odd	234	4	Concrete	10% Replacement	Good
				Total Length: 1,044				

HILLSIDE AVENUE								
HILLSIDE AVE-01	FIELD ST	PARK AVE	Even	233	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-01	FIELD ST	PARK AVE	Odd	388	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-02	PARK AVE	BUCKINGHAM ST	Even	530	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-02	PARK AVE	BUCKINGHAM ST	Odd	530	4	Concrete	10% Replacement	Good
HILLSIDE AVE-03	BUCKINGHAM ST	JUDD ST	Even	989	3	Concrete	25% Replacement	Fair
HILLSIDE AVE-03	BUCKINGHAM ST	JUDD ST	Odd	989	3	Concrete	10% Replacement	Good
HILLSIDE AVE-04	JUDD ST	BRADBURY ST	Even	406	3	Concrete	10% Replacement	Good
HILLSIDE AVE-04	JUDD ST	BRADBURY ST	Odd	385	3	Concrete	10% Replacement	Good
HILLSIDE AVE-05	BRADBURY ST	SALEM ST	Even	257	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-05	BRADBURY ST	SALEM ST	Odd	257	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-06	SALEM ST	GROVE ST	Even	647	4	Mix	50% Replacement	Poor
HILLSIDE AVE-06	SALEM ST	GROVE ST	Odd	647	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-07	GROVE ST	ROCKWELL AVE	Even	217	4	Concrete	10% Replacement	Good
HILLSIDE AVE-07	GROVE ST	ROCKWELL AVE	Odd	217	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-08	ROCKWELL AVE	MILLVILLE AVE	Even	585	4	Concrete	100% Replacement	Replace
HILLSIDE AVE-08	ROCKWELL AVE	MILLVILLE AVE	Odd	585	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-09	MILLVILLE AVE	SWEENEY ST	Even	364	4	Mix	10% Replacement	Good
HILLSIDE AVE-09	MILLVILLE AVE	SWEENEY ST	Odd	364	4	Concrete	10% Replacement	Good
HILLSIDE AVE-10	SWEENEY ST	ELMWOOD ST	Even	395	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-10	SWEENEY ST	ELMWOOD ST	Odd	395	4	Concrete	50% Replacement	Poor
HILLSIDE AVE-11	ELMWOOD ST	TERRACE AVE	Even	196	4	Concrete	Defer Maintenance	Excellent
HILLSIDE AVE-11	ELMWOOD ST	TERRACE AVE	Odd	196	4	Concrete	50% Replacement	Poor
HILLSIDE AVE-12	MEADOW ST	PAVEMENT CHANGE	Even	184	4	Concrete	25% Replacement	Fair
HILLSIDE AVE-13	PAVEMENT CHANGE	FAIRVIEW AVE	Even	250	4	Concrete	Defer Maintenance	Excellent
HILLSIDE AVE-13	PAVEMENT CHANGE	FAIRVIEW AVE	Odd	250	4	Mix	25% Replacement	Fair
				Total Length: 10,456				

HOADLEY STREET								
HOADLEY ST-01	RUBBER AVE	AETNA ST	Even	310	4	Asphalt	10% Replacement	Good
HOADLEY ST-02	AETNA ST	HOADLEY TER	Odd	397	4	Concrete	Defer Maintenance	Excellent
HOADLEY ST-03	HOADLEY TER	MARSHALL AVE	Odd	348	4	Concrete	Defer Maintenance	Excellent
HOADLEY ST-04	MARSHALL AVE	WEST ST	Odd	234	4	Concrete	Defer Maintenance	Excellent
HOADLEY ST-05	WEST ST	HIGHLAND AVE	Odd	236	4	Concrete	Defer Maintenance	Excellent

	From	To	Side	Length	Width	Material	Repair Method	Condition
HOADLEY ST-06	HIGHLAND AVE	SUMMIT RD	Odd	498	4	Concrete	Defer Maintenance	Excellent
HOADLEY ST-07	SUMMIT RD	MILLVILLE AVE	Odd	228	4	Concrete	10% Replacement	Good
				Total Length: 2,251				
HOMESTEAD AVENUE								
HOMESTEAD AVE-01	HIGH ST	CULVER CT	Odd	193	4	Concrete	25% Replacement	Fair
HOMESTEAD AVE-02	CULVER CT	CULVER ST	Odd	501	4	Concrete	25% Replacement	Fair
HOMESTEAD AVE-03	CULVER ST	DEAD END	Odd	112	4	Concrete	50% Replacement	Poor
				Total Length: 806				
HOPKINS HILL ROAD								
HOPKINS HILL RD	MULBERRY ST	CUL DE SAC	Even	778	4	Concrete	25% Replacement	Fair
HOPKINS HILL RD	MULBERRY ST	CUL DE SAC	Odd	778	4	Concrete	10% Replacement	Good
				Total Length: 1,556				
HOTCHKISS STREET								
HOTCHKISS ST	S MAIN ST	DEAD END	Even	643	4	Mix	25% Replacement	Fair
HOTCHKISS ST	S MAIN ST	DEAD END	Odd	482	4	Mix	25% Replacement	Fair
				Total Length: 1,125				
IDA STREET								
IDA ST	SPENCER ST	IRVING ST	Even	298	4	Concrete	Defer Maintenance	Excellent
IDA ST	SPENCER ST	IRVING ST	Odd	298	4	Concrete	25% Replacement	Fair
				Total Length: 596				
IRVING STREET								
IRVING ST-01	SPENCER ST	IDA ST	Even	696	3	Asphalt	25% Replacement	Fair
IRVING ST-01	SPENCER ST	IDA ST	Odd	696	3	Asphalt	25% Replacement	Fair
IRVING ST-02	IDA ST	SPENCER ST	Even	856	4	Concrete	25% Replacement	Fair
IRVING ST-02	IDA ST	SPENCER ST	Odd	856	4	Concrete	50% Replacement	Poor
				Total Length: 3,104				
JONES ROAD								
JONES RD-02	WEBB RD	STONE FENCE RD	Odd	386	4	Concrete	Defer Maintenance	Excellent
				Total Length: 386				
JUDD STREET								
JUDD ST	HILLSIDE AVE	BUCKINGHAM ST	Even	352	4	Concrete	10% Replacement	Good
JUDD ST	HILLSIDE AVE	BUCKINGHAM ST	Odd	352	4	Concrete	10% Replacement	Good
				Total Length: 704				
LAUREL AVENUE								
LAUREL AVE	NEW HAVEN RD	MARJORIE ST	Even	452	4	Concrete	10% Replacement	Good
LAUREL AVE	NEW HAVEN RD	MARJORIE ST	Odd	301	4	Concrete	25% Replacement	Fair
				Total Length: 753				

	From	To	Side	Length	Width	Material	Repair Method	Condition
LEWIS CIRCLE								
LEWIS CIR	SPENCER ST	CUL DE SAC	Even	691	4	Concrete	Defer Maintenance	Excellent
LEWIS CIR	SPENCER ST	CUL DE SAC	Odd	691	4	Concrete	25% Replacement	Fair
				Total Length: 1,382				
LEWIS STREET								
LEWIS ST-01	SCOTT ST	NIXON AVE	Even	247	4	Concrete	50% Replacement	Poor
LEWIS ST-01	SCOTT ST	NIXON AVE	Odd	247	4	Mix	50% Replacement	Poor
LEWIS ST-02	NIXON AVE	MANNERS AVE	Even	191	4	Mix	25% Replacement	Fair
LEWIS ST-02	NIXON AVE	MANNERS AVE	Odd	191	4	Concrete	100% Replacement	Replace
LEWIS ST-03	MANNERS AVE	OLIVE ST	Even	482	4	Concrete	50% Replacement	Poor
LEWIS ST-03	MANNERS AVE	OLIVE ST	Odd	482	4	Concrete	50% Replacement	Poor
LEWIS ST-04	OLIVE ST	FAIRCHILD ST	Even	506	4	Asphalt	10% Replacement	Good
LEWIS ST-04	OLIVE ST	FAIRCHILD ST	Odd	51	4	Concrete	Defer Maintenance	Excellent
LEWIS ST-05	FAIRCHILD ST	SPENCER ST	Even	258	4	Asphalt	10% Replacement	Good
LEWIS ST-06	SPENCERS ST	SHARON AVE	Odd	352	3	Asphalt	25% Replacement	Fair
				Total Length: 3,007				
LINDEN STREET								
LINDEN ST-01	N MAIN ST	CURTISS ST	Even	91	3	Concrete	Defer Maintenance	Excellent
LINDEN ST-01	N MAIN ST	CURTISS ST	Odd	227	4	Mix	Defer Maintenance	Excellent
				Total Length: 318				
LONGWOOD DRIVE								
LONGWOOD DR-02	WARM EARTH RD	CUL DE SAC	Even	76	4	Asphalt	50% Replacement	Poor
				Total Length: 76				
LYNN CIRCLE								
LYNN CIR	DEERLING LN	CUL DE SAC	Even	153	4	Concrete	25% Replacement	Fair
LYNN CIR	DEERLING LN	CUL DE SAC	Odd	153	4	Asphalt	50% Replacement	Poor
				Total Length: 306				
LYNN ROAD								
LYNN RD	MOORE AVE	DEAD END	Odd	124	4	Concrete	25% Replacement	Fair
				Total Length: 124				
MALGARI COURT								
MALGARI CT	FAIRCHILD ST	DEAD END	Even	143	4	Concrete	25% Replacement	Fair
MALGARI CT	FAIRCHILD ST	DEAD END	Odd	238	3	Concrete	25% Replacement	Fair
				Total Length: 381				
MANNERS AVENUE								
MANNERS AVE-02	RUSSELL ST	THERESA ST	Even	339	4	Mix	25% Replacement	Fair
MANNERS AVE-02	RUSSELL ST	THERESA ST	Odd	282	4	Asphalt	25% Replacement	Fair

	From	To	Side	Length	Width	Material	Repair Method	Condition
Total Length: 621								
MAPLE HILL ROAD								
MAPLE HILL RD-09	INWOOD DR	OLDE FARM LN	Even	257	4	Concrete	Defer Maintenance	Excellent
MAPLE HILL RD-12	MULBERRY ST	VICTORIA LN	Even	847	4	Concrete	Defer Maintenance	Excellent
Total Length: 1,104								
MAPLE STREET								
MAPLE ST-01	CHURCH ST	OLD FIREHOUSE RD	Even	250	6	Concrete	Defer Maintenance	Excellent
MAPLE ST-01	CHURCH ST	OLD FIREHOUSE RD	Odd	250	6	Concrete	10% Replacement	Good
MAPLE ST-02	OLD FIREHOUSE RD	WATER ST	Even	400	5	Concrete	100% Replacement	Replace
MAPLE ST-02	OLD FIREHOUSE RD	WATER ST	Odd	400	6	Concrete	Defer Maintenance	Excellent
MAPLE ST-03	WATER ST	OAK ST	Even	391	6	Concrete	Defer Maintenance	Excellent
MAPLE ST-03	WATER ST	OAK ST	Odd	391	6	Concrete	Defer Maintenance	Excellent
MAPLE ST-04	OAK ST	CENTRAL AVE	Even	62	4	Concrete	Defer Maintenance	Excellent
MAPLE ST-04	OAK ST	CENTRAL AVE	Odd	155	4	Concrete	Defer Maintenance	Excellent
MAPLE ST-05	CENTRAL AVE	CARROLL ST	Even	231	6	Concrete	Defer Maintenance	Excellent
MAPLE ST-05	CENTRAL AVE	CARROLL ST	Odd	231	4	Concrete	Defer Maintenance	Excellent
MAPLE ST-06	CARROLL ST	MAPLE TER	Even	245	4	Concrete	25% Replacement	Fair
MAPLE ST-06	CARROLL ST	MAPLE TER	Odd	245	4	Concrete	25% Replacement	Fair
MAPLE ST-07	MAPLE TER	HILL ST	Even	126	4	Mix	Defer Maintenance	Excellent
Total Length: 3,377								
MAPLE TERRACE								
MAPLE TER	MAPLE ST	MAY ST	Odd	312	4	Mix	25% Replacement	Fair
Total Length: 312								
MARJORIE STREET								
MARJORIE ST-01	HAZEL AVE	GENERAL DALTON DR	Odd	130	4	Concrete	50% Replacement	Poor
MARJORIE ST-02	GENERAL DALTON DR	LAUREL AVE	Odd	188	4	Concrete	100% Replacement	Replace
MARJORIE ST-03	LAUREL AVE	GENERAL PATTON DR	Odd	125	4	Concrete	25% Replacement	Fair
Total Length: 443								
MAY AVENUE								
MAY AVE-02	NEW ST	GROVE ST	Even	346	4	Concrete	25% Replacement	Fair
MAY AVE-02	NEW ST	GROVE ST	Odd	346	4	Concrete	25% Replacement	Fair
MAY AVE-03	GROVE ST	MILLVILLE AVE	Even	816	4	Mix	100% Replacement	Replace
MAY AVE-03	GROVE ST	MILLVILLE AVE	Odd	816	4	Concrete	25% Replacement	Fair
Total Length: 2,324								
MAY STREET								
MAY ST-01	HIGH ST	HILL ST	Even	336	4	Mix	25% Replacement	Fair
MAY ST-01	HIGH ST	HILL ST	Odd	336	4	Asphalt	10% Replacement	Good
MAY ST-02	HILL ST	HILLCREST AVE	Even	161	4	Concrete	Defer Maintenance	Excellent

	From	To	Side	Length	Width	Material	Repair Method	Condition
MAY ST-02	HILL ST	HILLCREST AVE	Odd	161	4	Asphalt	10% Replacement	Good
MAY ST-03	HILLCREST AVE	PHOENIX AVE	Even	190	4	Concrete	Defer Maintenance	Excellent
MAY ST-03	HILLCREST AVE	PHOENIX AVE	Odd	190	4	Asphalt	25% Replacement	Fair
MAY ST-04	PHOENIX AVE	SPRUCE DR	Even	290	4	Concrete	Defer Maintenance	Excellent
MAY ST-04	PHOENIX AVE	SPRUCE DR	Odd	290	4	Asphalt	25% Replacement	Fair
MAY ST-16	MAPLE HILL RD	PROSPECT TL	Odd	1226	4	Concrete	Defer Maintenance	Excellent

Total Length: 3,180

MEADOW BROOK PLACE

MEADOW BROOK PL	CROSS ST	CUL DE SAC	Even	538	4	Concrete	10% Replacement	Good
-----------------	----------	------------	------	-----	---	----------	-----------------	------

Total Length: 538

MEADOW COURT

MEADOW CT	CHURCH ST	MEADOW CT	Even	347	4	Concrete	10% Replacement	Good
MEADOW CT	CHURCH ST	MEADOW CT	Odd	347	4	Concrete	10% Replacement	Good

Total Length: 694

MELBOURNE COURT

MELBOURNE CT-01	MELBOURNE ST	BROOKSIDE AVE	Odd	500	4	Asphalt	Defer Maintenance	Excellent
-----------------	--------------	---------------	-----	-----	---	---------	-------------------	-----------

Total Length: 500

MELBOURNE STREET

MELBOURNE ST-01	RUBBER AVE	MELBOURNE CT	Odd	43	4	Asphalt	Defer Maintenance	Excellent
-----------------	------------	--------------	-----	----	---	---------	-------------------	-----------

Total Length: 43

MELISSA COURT

MELISSA CT	MALLANE LN	CUL DE SAC	Even	195	4	Concrete	10% Replacement	Good
------------	------------	------------	------	-----	---	----------	-----------------	------

Total Length: 195

MILLVILLE AVENUE

MILLVILLE AVE-01	FIELD ST	WEST HILL TER	Even	115	4	Asphalt	Defer Maintenance	Excellent
MILLVILLE AVE-02	WEST HILL TER	LORANN DR	Even	1398	4	Asphalt	10% Replacement	Good
MILLVILLE AVE-03	LORANN DR	PINE ST	Even	359	4	Asphalt	Defer Maintenance	Excellent
MILLVILLE AVE-07	CLEARVIEW CIR	N HOADLEY ST	Even	398	4	Asphalt	10% Replacement	Good
MILLVILLE AVE-08	N HOADLEY ST	FERN ST	Even	281	4	Mix	25% Replacement	Fair
MILLVILLE AVE-08	N HOADLEY ST	FERN ST	Odd	281	4	Concrete	25% Replacement	Fair
MILLVILLE AVE-09	FERN ST	QUINN ST	Even	116	4	Concrete	10% Replacement	Good
MILLVILLE AVE-09	FERN ST	QUINN ST	Odd	233	4	Concrete	25% Replacement	Fair
MILLVILLE AVE-10	QUINN ST	PARK AVE	Even	213	4	Concrete	Defer Maintenance	Excellent
MILLVILLE AVE-10	QUINN ST	PARK AVE	Odd	355	4	Concrete	10% Replacement	Good
MILLVILLE AVE-11	PARK AVE	WALNUT ST	Even	430	4	Concrete	Defer Maintenance	Excellent
MILLVILLE AVE-11	PARK AVE	WALNUT ST	Odd	430	4	Mix	25% Replacement	Fair
MILLVILLE AVE-12	WALNUT ST	WOODLAWN AVE	Even	323	4	Concrete	10% Replacement	Good
MILLVILLE AVE-12	WALNUT ST	WOODLAWN AVE	Odd	323	4	Concrete	Defer Maintenance	Excellent

	From	To	Side	Length	Width	Material	Repair Method	Condition
MILLVILLE AVE-13	WOODLAWN AVE	HILLSIDE AVE	Even	364	4	Concrete	50% Replacement	Poor
MILLVILLE AVE-13	WOODLAWN AVE	HILLSIDE AVE	Odd	364	4	Concrete	Defer Maintenance	Excellent
MILLVILLE AVE-14	HILLSIDE AVE	TERRACE AVE	Even	379	4	Mix	25% Replacement	Fair
MILLVILLE AVE-14	HILLSIDE AVE	TERRACE AVE	Odd	379	4	Concrete	Defer Maintenance	Excellent

Total Length: 6,741

MOORE AVENUE

MOORE AVE-01	CLIFF ST	LYNN RD	Even	550	3	Mix	25% Replacement	Fair
MOORE AVE-01	CLIFF ST	LYNN RD	Odd	550	3	Concrete	10% Replacement	Good
MOORE AVE-02	LYNN RD	NETTLETON AVE	Even	200	4	Concrete	Defer Maintenance	Excellent
MOORE AVE-02	LYNN RD	NETTLETON AVE	Odd	200	4	Concrete	Defer Maintenance	Excellent

Total Length: 1,500

MORNING DOVE ROAD

MORNING DOVE RD-03	RAIN DANCE CIR	THISTLE DOWN LN	Odd	504	3	Asphalt	10% Replacement	Good
MORNING DOVE RD-04	THISTLE DOWN LN	DEAD END	Odd	198	4	Asphalt	10% Replacement	Good

Total Length: 702

MULBERRY STREET

MULBERRY ST-08	MAPLE HILL RD	KENT ST	Odd	304	4	Concrete	Defer Maintenance	Excellent
MULBERRY ST-09	KENT ST	RUSTLING REED RD	Odd	294	4	Concrete	Defer Maintenance	Excellent
MULBERRY ST-10	RUSTLING REED RD	DEAD END	Odd	251	4	Concrete	10% Replacement	Good

Total Length: 849

MYRTLE AVENUE

MYRTLE AVE	N MAIN ST	DEAD END	Even	275	4	Concrete	25% Replacement	Fair
MYRTLE AVE	N MAIN ST	DEAD END	Odd	275	4	Concrete	25% Replacement	Fair

Total Length: 550

N HOADLEY STREET

N HOADLEY ST-01	MILLVILLE AVE	COTTAGE ST	Even	687	4	Mix	25% Replacement	Fair
N HOADLEY ST-01	MILLVILLE AVE	COTTAGE ST	Odd	549	4	Mix	25% Replacement	Fair
N HOADLEY ST-02	COTTAGE ST	PHYLLIS DR	Even	267	4	Mix	10% Replacement	Good
N HOADLEY ST-02	COTTAGE ST	PHYLLIS DR	Odd	321	4	Concrete	50% Replacement	Poor
N HOADLEY ST-03	PHYLLIS DR	CHESTNUT ST	Even	82	4	Concrete	100% Replacement	Replace
N HOADLEY ST-04	CHESTNUT ST	DEERING LN	Even	338	4	Asphalt	10% Replacement	Good
N HOADLEY ST-04	CHESTNUT ST	DEERING LN	Odd	338	4	Mix	50% Replacement	Poor
N HOADLEY ST-05	DEERING LN	BIRCH LN	Even	390	4	Mix	50% Replacement	Poor
N HOADLEY ST-05	DEERING LN	BIRCH LN	Odd	390	4	Mix	25% Replacement	Fair
N HOADLEY ST-06	DAMSON LN	SURREY DR	Even	254	4	Mix	25% Replacement	Fair
N HOADLEY ST-06	DAMSON LN	SURREY DR	Odd	254	4	Asphalt	25% Replacement	Fair
N HOADLEY ST-07	SURREY DR	DAMSON LN	Even	815	4	Mix	50% Replacement	Poor
N HOADLEY ST-07	SURREY DR	DAMSON LN	Odd	815	4	Mix	25% Replacement	Fair

	From	To	Side	Length	Width	Material	Repair Method	Condition
N HOADLEY ST-08	DAMSON LN	QUINN ST	Even	433	4	Mix	50% Replacement	Poor
N HOADLEY ST-08	DAMSON LN	QUINN ST	Odd	433	4	Mix	25% Replacement	Fair

Total Length: 6,366

N MAIN STREET

N MAIN ST-01	CALVIN ST	CURTISS CT	Even	204	4	Concrete	Defer Maintenance	Excellent
N MAIN ST-01	CALVIN ST	CURTISS CT	Odd	41	3	Asphalt	25% Replacement	Fair
N MAIN ST-02	CURTISS CT	LINDEN ST	Even	677	5	Concrete	Defer Maintenance	Excellent
N MAIN ST-02	CURTISS CT	LINDEN ST	Odd	677	3	Asphalt	25% Replacement	Fair
N MAIN ST-03	LINDEN ST	GRIFFIN ST	Even	712	4	Concrete	Defer Maintenance	Excellent
N MAIN ST-03	LINDEN ST	GRIFFIN ST	Odd	285	3	Asphalt	10% Replacement	Good
N MAIN ST-04	GRIFFIN ST	SMITH ST	Even	399	4	Concrete	25% Replacement	Fair
N MAIN ST-04	GRIFFIN ST	SMITH ST	Odd	319	4	Mix	25% Replacement	Fair
N MAIN ST-05	SMITH ST	CITY HILL ST	Even	522	4	Concrete	25% Replacement	Fair
N MAIN ST-05	SMITH ST	CITY HILL ST	Odd	522	4	Mix	Defer Maintenance	Excellent
N MAIN ST-06	CITY HILL ST	PROSPECT ST	Even	293	4	Concrete	Defer Maintenance	Excellent
N MAIN ST-06	CITY HILL ST	PROSPECT ST	Odd	326	6	Concrete	Defer Maintenance	Excellent
N MAIN ST-07	PROSPECT ST	GOLDEN CT	Odd	206	4	Mix	10% Replacement	Good
N MAIN ST-08	GOLDEN CT	WOOD ST	Odd	235	4	Concrete	10% Replacement	Good
N MAIN ST-09	WOOD ST	MYRTLE AVE	Odd	240	0	Concrete	Defer Maintenance	Excellent
N MAIN ST-10	MYRTLE AVE	WOODBINE ST	Odd	172	0	Mix	10% Replacement	Good

Total Length: 5,830

NETTLETON AVENUE

NETTLETON AVE-01	AETNA ST	MOORE AVE	Even	367	4	Concrete	50% Replacement	Poor
NETTLETON AVE-01	AETNA ST	MOORE AVE	Odd	458	4	Concrete	50% Replacement	Poor
NETTLETON AVE-02	MOORE AVE	TROWBRIDGE PL	Even	199	4	Concrete	Defer Maintenance	Excellent
NETTLETON AVE-02	MOORE AVE	TROWBRIDGE PL	Odd	199	4	Concrete	Defer Maintenance	Excellent

Total Length: 1,223

NEW STREET

NEW ST-01	SALEM ST	HILLSIDE AVE	Even	408	4	Concrete	50% Replacement	Poor
NEW ST-01	SALEM ST	HILLSIDE AVE	Odd	408	4	Concrete	10% Replacement	Good
NEW ST-02	HILLSIDE AVE	SVEA AVE	Odd	245	4	Mix	25% Replacement	Fair
NEW ST-03	SVEA AVE	WALNUT ST	Odd	350	4	Concrete	50% Replacement	Poor
NEW ST-04	WALNUT ST	MAY AVE	Odd	393	4	Concrete	25% Replacement	Fair
NEW ST-05	MAY AVE	PARK AVE	Even	71	4	Concrete	50% Replacement	Poor
NEW ST-05	MAY AVE	PARK AVE	Odd	106	3	Concrete	10% Replacement	Good

Total Length: 1,981

NORTH CIRCLE

NORTH CIR	BROOKSIDE AVE	CUL DE SAC	Even	173	4	Concrete	25% Replacement	Fair
NORTH CIR	BROOKSIDE AVE	CUL DE SAC	Odd	173	4	Concrete	50% Replacement	Poor

	From	To	Side	Length	Width	Material	Repair Method	Condition
Total Length: 346								
OAK STREET								
OAK ST-01	MAPLE ST	HIGH ST	Even	793	4	Concrete	25% Replacement	Fair
OAK ST-01	MAPLE ST	HIGH ST	Odd	793	4	Mix	50% Replacement	Poor
OAK ST-02	HIGH ST	COEN ST	Even	307	4	Concrete	25% Replacement	Fair
OAK ST-02	HIGH ST	COEN ST	Odd	307	4	Concrete	50% Replacement	Poor
OAK ST-03	COEN ST	BRADLEY ST	Even	108	4	Mix	25% Replacement	Fair
OAK ST-03	COEN ST	BRADLEY ST	Odd	108	4	Concrete	25% Replacement	Fair
OAK ST-04	BRADLEY ST	DEAD END	Even	178	4	Mix	50% Replacement	Poor
OAK ST-04	BRADLEY ST	DEAD END	Odd	89	4	Mix	100% Replacement	Replace
Total Length: 2,683								
OLD FIREHOUSE ROAD								
OLD FIREHOUSE RD	MAPLE ST	ELM ST	Even	1196	4	Concrete	Defer Maintenance	Excellent
OLD FIREHOUSE RD	MAPLE ST	ELM ST	Odd	1196	4	Concrete	Defer Maintenance	Excellent
Total Length: 2,392								
OLDE FARM LANE								
OLDE FARM LN	MAPLE HILL RD	CUL DE SAC	Even	643	4	Concrete	Defer Maintenance	Excellent
OLDE FARM LN	MAPLE HILL RD	CUL DE SAC	Odd	643	4	Concrete	10% Replacement	Good
Total Length: 1,286								
OLIVE STREET								
OLIVE ST-01	CHERRY ST	GORMAN ST	Even	415	4	Concrete	25% Replacement	Fair
OLIVE ST-01	CHERRY ST	GORMAN ST	Odd	415	4	Concrete	25% Replacement	Fair
OLIVE ST-02	GORMENT ST	LEWIS ST	Even	692	4	Concrete	50% Replacement	Poor
OLIVE ST-02	GORMENT ST	LEWIS ST	Odd	519	4	Concrete	25% Replacement	Fair
Total Length: 2,041								
ORCHARD STREET								
ORCHARD ST-01	HIGH ST	ORCHARD TER	Even	237	4	Mix	25% Replacement	Fair
ORCHARD ST-01	HIGH ST	ORCHARD TER	Odd	237	4	Concrete	50% Replacement	Poor
ORCHARD ST-02	ORHCARD TER	N MAIN ST	Even	503	4	Mix	10% Replacement	Good
ORCHARD ST-02	ORHCARD TER	N MAIN ST	Odd	503	4	Mix	100% Replacement	Replace
Total Length: 1,480								
ORCHARD TERRACE								
ORCHARD TER	ORCHARD ST	DEAD END	Even	248	4	Mix	25% Replacement	Fair
Total Length: 248								
OSBORN ROAD								
OSBORN RD-03	D'ARCANGELO DR	DAVIN DR	Odd	372	4	Concrete	Defer Maintenance	Excellent
OSBORN RD-04	DAVIN DR	CELENTANO DR	Odd	620	4	Concrete	10% Replacement	Good
OSBORN RD-05	CELENTANO DR	CARRIAGE DR	Odd	259	4	Concrete	Defer Maintenance	Excellent

	From	To	Side	Length	Width	Material	Repair Method	Condition
OSBORN RD-06	CARRIAGE DR	WISTERIA DR	Even	356	4	Concrete	Defer Maintenance	Excellent
OSBORN RD-06	CARRIAGE DR	WISTERIA DR	Odd	594	4	Concrete	Defer Maintenance	Excellent
OSBORN RD-07	WISTERIA DR	CUL DE SAC	Even	476	4	Concrete	Defer Maintenance	Excellent

Total Length: 2,677

PARK AVENUE

PARK AVE-01	WALNUT TER	MILLVILLE AVE	Even	875	3	Concrete	25% Replacement	Fair
PARK AVE-01	WALNUT TER	MILLVILLE AVE	Odd	921	3	Concrete	25% Replacement	Fair
PARK AVE-02	MILLVILLE AVE	GROVE ST	Even	795	4	Concrete	25% Replacement	Fair
PARK AVE-02	MILLVILLE AVE	GROVE ST	Odd	795	4	Concrete	25% Replacement	Fair
PARK AVE-03	GROVE ST	NEW ST	Even	346	4	Mix	25% Replacement	Fair
PARK AVE-03	GROVE ST	NEW ST	Odd	346	4	Concrete	10% Replacement	Good
PARK AVE-04	NEW ST	CHESTNUT ST	Even	261	4	Concrete	10% Replacement	Good
PARK AVE-04	NEW ST	CHESTNUT ST	Odd	372	4	Concrete	Defer Maintenance	Excellent
PARK AVE-05	CHESTNUT ST	EAST DR	Odd	1392	3	Concrete	50% Replacement	Poor
PARK AVE-06	EAST DR	HILLSIDE AVE	Even	141	4	Concrete	Defer Maintenance	Excellent
PARK AVE-06	EAST DR	HILLSIDE AVE	Odd	353	4	Mix	10% Replacement	Good

Total Length: 6,597

PARK PLACE

PARK PL	CHURCH ST	MEADOW ST	Even	353	4	Concrete	25% Replacement	Fair
PARK PL	CHURCH ST	MEADOW ST	Odd	353	4	Concrete	25% Replacement	Fair

Total Length: 706

PEAR TREE DRIVE

PEAR TREE DR	FAWN MEADOW DR	CUL DE SAC	Even	614	4	Concrete	Defer Maintenance	Excellent
PEAR TREE DR	FAWN MEADOW DR	CUL DE SAC	Odd	614	4	Concrete	Defer Maintenance	Excellent

Total Length: 1,228

PEMBROOK ROAD

PEMBROOK RD	MAY ST	CUL DE SAC	Even	652		Concrete	Defer Maintenance	Excellent
PEMBROOK RD	MAY ST	CUL DE SAC	Odd	618		Concrete	Defer Maintenance	Excellent

Total Length: 1,270

PHOENIX AVENUE

PHOENIX AVE	MAY ST	JOHNSON ST	Even	1322	4	Asphalt	10% Replacement	Good
PHOENIX AVE	MAY ST	JOHNSON ST	Odd	378	4	Mix	50% Replacement	Poor

Total Length: 1,700

PINE STREET

PINE ST	HOADLEY ST	MILLVILLE AVE	Even	1030	5	Asphalt	Defer Maintenance	Excellent
PINE ST	HOADLEY ST	MILLVILLE AVE	Odd	858	4	Mix	10% Replacement	Good

Total Length: 1,888

PINEWOOD CROSSING SOUTH

	From	To	Side	Length	Width	Material	Repair Method	Condition
PINEWOOD CROSSING SOUTH	SILVER BEECH DR	CUL DE SAC	Even	313	4	Concrete	Defer Maintenance	Excellent
PINEWOOD CROSSING SOUTH	SILVER BEECH DR	CUL DE SAC	Odd	313	4	Concrete	Defer Maintenance	Excellent
Total Length: 626								
PLEASANT VIEW STREET								
PLEASANT VIEW ST	FAIRVIEW AVE	CLIFF ST	Even	585	4	Concrete	25% Replacement	Fair
PLEASANT VIEW ST	FAIRVIEW AVE	CLIFF ST	Odd	585	4	Concrete	25% Replacement	Fair
Total Length: 1,170								
POND STREET								
POND ST-01	RUBBER AVE	SOUTHVIEW ST	Odd	285	4	Concrete	50% Replacement	Poor
POND ST-02	SOUTHVIEW ST	FAIRVIEW AVE	Even	46	2	Concrete	Defer Maintenance	Excellent
POND ST-02	SOUTHVIEW ST	FAIRVIEW AVE	Odd	277	5	Mix	10% Replacement	Good
Total Length: 608								
POND VALLEY ROAD								
POND VALLEY RD	SILVER BEECH DR	CUL DE SAC	Even	271	4	Concrete	Defer Maintenance	Excellent
POND VALLEY RD	SILVER BEECH DR	CUL DE SAC	Odd	271	4	Concrete	Defer Maintenance	Excellent
Total Length: 542								
QUINN STREET								
QUINN ST-01	FIELD ST	NO HOADLEY ST	Even	338	3	Concrete	50% Replacement	Poor
QUINN ST-01	FIELD ST	NO HOADLEY ST	Odd	376	3	Concrete	10% Replacement	Good
QUINN ST-02	N HOADLEY ST	QUINN ST-03	Even	529	3	Concrete	25% Replacement	Fair
QUINN ST-02	N HOADLEY ST	QUINN ST-03	Odd	529	3	Mix	25% Replacement	Fair
QUINN ST-03	QUINN ST-02	SURREY DR	Even	857	3	Mix	25% Replacement	Fair
QUINN ST-03	QUINN ST-02	SURREY DR	Odd	86	1	Concrete	100% Replacement	Replace
QUINN ST-04	SURREY DR	EAST DR	Odd	356	3	Asphalt	100% Replacement	Replace
QUINN ST-05	EAST DR	QUINN ST-02	Odd	649	3	Mix	50% Replacement	Poor
QUINN ST-06	SURREY DR	CHESTNUT ST	Even	1035	3	Mix	25% Replacement	Fair
QUINN ST-06	SURREY DR	CHESTNUT ST	Odd	1035	3	Mix	50% Replacement	Poor
QUINN ST-07	CHESTNUT ST	MILLVILLE AVE	Even	1495	3	Concrete	25% Replacement	Fair
QUINN ST-07	CHESTNUT ST	MILLVILLE AVE	Odd	1495	4	Concrete	25% Replacement	Fair
Total Length: 8,780								
RADNOR AVENUE								
RADNOR AVE-02	WILLOW LN	BEARDSLEY AVE	Even	234	4	Concrete	50% Replacement	Poor
RADNOR AVE-02	WILLOW LN	BEARDSLEY AVE	Odd	273	4	Concrete	25% Replacement	Fair
RADNOR AVE-03	BEARDSLEY AVE	SANDE AVE	Even	336	4	Concrete	25% Replacement	Fair
RADNOR AVE-03	BEARDSLEY AVE	SANDE AVE	Odd	336	4	Concrete	25% Replacement	Fair
RADNOR AVE-04	SANDE AVE	WATERBURY TL	Even	279	4	Concrete	25% Replacement	Fair
RADNOR AVE-04	SANDE AVE	WATERBURY TL	Odd	279	4	Mix	Defer Maintenance	Excellent
Total Length: 1,737								

	From	To	Side	Length	Width	Material	Repair Method	Condition
RAIN DANCE CIRCLE								
RAIN DANCE CIR	MORNING DOVE CIR	CUL DE SAC	Odd	196	4	Asphalt	10% Replacement	Good
				Total Length: 196				
ROCKWELL AVENUE								
ROCKWELL AVE	HILLSIDE AVE	SALEM ST	Even	1052	4	Concrete	50% Replacement	Poor
ROCKWELL AVE	HILLSIDE AVE	SALEM ST	Odd	1052	4	Concrete	25% Replacement	Fair
				Total Length: 2,104				
ROSEWOOD COURT								
ROSEWOOD CT	APPLEWOOD LN	CUL DE SAC	Even	129	4	Concrete	10% Replacement	Good
ROSEWOOD CT	APPLEWOOD LN	CUL DE SAC	Odd	129	4	Concrete	Defer Maintenance	Excellent
				Total Length: 258				
RUBBER AVENUE								
RUBBER AVE-01	NEUMANN ST	WOODRUFF AVE	Even	179	4	Concrete	Defer Maintenance	Excellent
RUBBER AVE-01	NEUMANN ST	WOODRUFF AVE	Odd	1434	4	Mix	10% Replacement	Good
RUBBER AVE-02	WOODRUFF AVE	KOCZAK CT	Odd	474	3	Asphalt	10% Replacement	Good
RUBBER AVE-03	ZOCZAK CT	BROOKSIDE AVE	Even	97	4	Mix	10% Replacement	Good
RUBBER AVE-03	ZOCZAK CT	BROOKSIDE AVE	Odd	645	4	Mix	10% Replacement	Good
RUBBER AVE-04	BROOKSIDE AVE	MELBOURNE ST	Odd	1117	4	Mix	10% Replacement	Good
RUBBER AVE-05	MELBOURNE ST	EDWARD ST	Even	113	4	Mix	10% Replacement	Good
RUBBER AVE-05	MELBOURNE ST	EDWARD ST	Odd	1131	4	Mix	10% Replacement	Good
RUBBER AVE-06	EDWARD ST	ANDREW AVE	Even	342	4	Mix	10% Replacement	Good
RUBBER AVE-06	EDWARD ST	ANDREW AVE	Odd	489	4	Mix	10% Replacement	Good
RUBBER AVE-07	ANDREW AVE	AETNA ST	Even	23	4	Concrete	Defer Maintenance	Excellent
RUBBER AVE-07	ANDREW AVE	AETNA ST	Odd	459	4	Asphalt	10% Replacement	Good
RUBBER AVE-08	AETNA ST	SOUTHVIEW ST	Even	64	4	Mix	25% Replacement	Fair
RUBBER AVE-08	AETNA ST	SOUTHVIEW ST	Odd	425	4	Concrete	25% Replacement	Fair
RUBBER AVE-09	SOUTHVIEW ST	MEADOW ST	Even	452	4	Concrete	10% Replacement	Good
RUBBER AVE-09	SOUTHVIEW ST	MEADOW ST	Odd	452	4	Concrete	10% Replacement	Good
RUBBER AVE-10	MEADOW ST	ELM ST	Even	622	4	Concrete	25% Replacement	Fair
RUBBER AVE-10	MEADOW ST	ELM ST	Odd	622	4	Concrete	10% Replacement	Good
				Total Length: 9,140				
RUBBER AVENUE EXTENSION								
RUBBER AVE EXT-01	NEUMANN ST	FIELD ST	Even	535	4	Concrete	Defer Maintenance	Excellent
RUBBER AVE EXT-03	SOUTHWOOD APT RD	CROFUT RD	Even	108	3	Concrete	10% Replacement	Good
RUBBER AVE EXT-04	CROFUT RD	BRIGHTON RD	Odd	431	4	Concrete	Defer Maintenance	Excellent
				Total Length: 1,074				
S MAIN STREET (ROUTE 63)								
S MAIN ST (ROUTE 63)-02	MAPLE ST	HOTCHKISS ST	Even	759	4	Asphalt	10% Replacement	Good

	From	To	Side	Length	Width	Material	Repair Method	Condition
S MAIN ST (ROUTE 63)-02	MAPLE ST	HOTCHKISS ST	Odd	759	6	Concrete	Defer Maintenance	Excellent
Total Length: 1,518								

SALEM STREET

SALEM ST-01	MILLVILLE AVE	ROCKWELL AVE	Even	151	4	Concrete	50% Replacement	Poor
SALEM ST-01	MILLVILLE AVE	ROCKWELL AVE	Odd	1009	4	Mix	100% Replacement	Replace
SALEM ST-02	ROCKWELL AVE	NEW ST	Even	372	4	Concrete	100% Replacement	Replace
SALEM ST-02	ROCKWELL AVE	NEW ST	Odd	372	4	Concrete	50% Replacement	Poor
Total Length: 1,904								

SANDE AVENUE

SANDE AVE-01	PLATTS MILLS RD	RADNOR AVE	Even	278	4	Mix	50% Replacement	Poor
SANDE AVE-01	PLATTS MILLS RD	RADNOR AVE	Odd	278	4	Mix	50% Replacement	Poor
SANDE AVE-02	RADNOR AVE	WATERBURY TL	Even	249	4	Concrete	25% Replacement	Fair
SANDE AVE-02	RADNOR AVE	WATERBURY TL	Odd	174	4	Concrete	50% Replacement	Poor
Total Length: 979								

SCHOOL STREET

SCHOOL ST-01	BRIDGE ST	ANDERSON ST	Even	20	4	Concrete	Defer Maintenance	Excellent
SCHOOL ST-01	BRIDGE ST	ANDERSON ST	Odd	405	4	Mix	10% Replacement	Good
SCHOOL ST-02	ANDERSON ST	SCHOOL ST EXT	Even	125	4	Concrete	10% Replacement	Good
SCHOOL ST-02	ANDERSON ST	SCHOOL ST EXT	Odd	836	4	Concrete	50% Replacement	Poor
SCHOOL ST-03	SCHOOL ST EXT	DEAD END	Odd	418	4	Concrete	50% Replacement	Poor
Total Length: 1,804								

SCOTT STREET

SCOTT ST-01	ELM ST	GORMAN ST	Even	794	4	Mix	Defer Maintenance	Excellent
SCOTT ST-01	ELM ST	GORMAN ST	Odd	836	4	Mix	10% Replacement	Good
SCOTT ST-02	GORMAN ST	ARCH ST	Even	231	4	Asphalt	25% Replacement	Fair
SCOTT ST-02	GORMAN ST	ARCH ST	Odd	243	4	Mix	100% Replacement	Replace
SCOTT ST-03	ARCH ST	THERESA ST	Even	684	4	Asphalt	100% Replacement	Replace
SCOTT ST-03	ARCH ST	THERESA ST	Odd	684	4	Mix	100% Replacement	Replace
SCOTT ST-04	THERESA ST	ANDREW AVE	Even	435	4	Mix	25% Replacement	Fair
SCOTT ST-04	THERESA ST	ANDREW AVE	Odd	544	4	Mix	100% Replacement	Replace
SCOTT ST-05	ANDREW AVE	MELBOURNE ST	Even	690	4	Mix	100% Replacement	Replace
SCOTT ST-05	ANDREW AVE	MELBOURNE ST	Odd	863	4	Mix	50% Replacement	Poor
Total Length: 6,004								

SETH DRIVE

SETH DR	HIGHLAND AVE	CUL DE SAC	Even	291	4	Concrete	Defer Maintenance	Excellent
SETH DR	HIGHLAND AVE	CUL DE SAC	Odd	412	4	Concrete	Defer Maintenance	Excellent
Total Length: 703								

SHARON AVENUE

	From	To	Side	Length	Width	Material	Repair Method	Condition
SHARON AVE	SPENCER ST	LEWIS ST	Even	168	4	Asphalt	Defer Maintenance	Excellent
Total Length: 168								
SHERMAN STREET								
SHERMAN ST-01	NORHT CHURCH ST	BEECHER ST	Even	662	4	Concrete	10% Replacement	Good
SHERMAN ST-01	NORHT CHURCH ST	BEECHER ST	Odd	629	4	Concrete	50% Replacement	Poor
SHERMAN ST-02	BEECHER ST	HILLSIDE AVE	Even	352	3	Concrete	10% Replacement	Good
SHERMAN ST-02	BEECHER ST	HILLSIDE AVE	Odd	352	4	Concrete	25% Replacement	Fair
Total Length: 1,995								
SIERRA RIDGE ROAD								
SIERRA RIDGE RD	DONOVAN RD	CUL DE SAC	Even	958	4	Concrete	Defer Maintenance	Excellent
SIERRA RIDGE RD	DONOVAN RD	CUL DE SAC	Odd	958	4	Concrete	10% Replacement	Good
Total Length: 1,916								
SILVER BEECH DRIVE								
SILVER BEECH DR-01	MAPLE HILL RD	POND VALLY RD	Even	381	4	Concrete	Defer Maintenance	Excellent
SILVER BEECH DR-01	MAPLE HILL RD	POND VALLY RD	Odd	381	4	Concrete	Defer Maintenance	Excellent
SILVER BEECH DR-02	POND VALLY RD	PINEWOOD CROSSING SOUTH	Even	531	4	Concrete	Defer Maintenance	Excellent
SILVER BEECH DR-02	POND VALLY RD	PINEWOOD CROSSING SOUTH	Odd	531	4	Concrete	Defer Maintenance	Excellent
SILVER BEECH DR-03	PINEWOOD CROSSING SO	CUL DE SAC	Even	386	4	Concrete	Defer Maintenance	Excellent
SILVER BEECH DR-03	PINEWOOD CROSSING SO	CUL DE SAC	Odd	386	4	Concrete	Defer Maintenance	Excellent
Total Length: 2,596								
SKYVIEW DRIVE								
SKYVIEW DR-01	CITY BROOK RD	WINDVIEW DR	Even	445	4	Concrete	Defer Maintenance	Excellent
SKYVIEW DR-01	CITY BROOK RD	WINDVIEW DR	Odd	445	4	Concrete	10% Replacement	Good
SKYVIEW DR-02	WINDVIEW DR	APPLEWOOD LN	Even	417	4	Concrete	Defer Maintenance	Excellent
SKYVIEW DR-02	WINDVIEW DR	APPLEWOOD LN	Odd	417	4	Concrete	10% Replacement	Good
Total Length: 1,724								
SMITH STREET								
SMITH ST	N MAIN ST	ROUTE 8	Even	189	4	Concrete	10% Replacement	Good
SMITH ST	N MAIN ST	ROUTE 8	Odd	9	4	Concrete	10% Replacement	Good
Total Length: 198								
SOUTH CIRCLE								
SOUTH CIR	BROOKSIDE AVE	CUL DE SAC	Even	173	4	Concrete	25% Replacement	Fair
Total Length: 173								
SPENCER STREET								
SPENCER ST-01	ELM ST	WARD ST	Even	402	4	Concrete	Defer Maintenance	Excellent
SPENCER ST-02	WARD ST	CHERRY ST	Even	414	4	Concrete	10% Replacement	Good
SPENCER ST-02	WARD ST	CHERRY ST	Odd	166	4	Mix	10% Replacement	Good
SPENCER ST-03	CHERRY ST	GORMAN ST	Odd	399	4	Concrete	25% Replacement	Fair

	From	To	Side	Length	Width	Material	Repair Method	Condition
SPENCER ST-04	GORMAN ST	HARD ST	Odd	321	3	Asphalt	25% Replacement	Fair
SPENCER ST-05	HARD ST	SHARON AVE	Odd	319	3	Asphalt	25% Replacement	Fair
SPENCER ST-06	SHARON AVE	LEWIS ST	Odd	532	3	Concrete	25% Replacement	Fair
SPENCER ST-07	LEWIS ST	IRVING ST	Even	268	3	Asphalt	50% Replacement	Poor
SPENCER ST-07	LEWIS ST	IRVING ST	Odd	268	3	Asphalt	50% Replacement	Poor
SPENCER ST-08	IRVING ST	IDA ST	Even	344	3	Asphalt	25% Replacement	Fair
SPENCER ST-08	IRVING ST	IDA ST	Odd	344	3	Asphalt	100% Replacement	Replace
SPENCER ST-09	IDA ST	IRVING ST	Even	598	4	Concrete	50% Replacement	Poor
SPENCER ST-09	IDA ST	IRVING ST	Odd	598	4	Concrete	50% Replacement	Poor
SPENCER ST-10	IRVING ST	DEAD END	Even	125	4	Concrete	10% Replacement	Good
SPENCER ST-10	IRVING ST	DEAD END	Odd	125	4	Concrete	10% Replacement	Good

Total Length: 5,223

SPRING STREET

SPRING ST-01	BRIDGE ST	DIAMOND ST	Even	491	4	Concrete	10% Replacement	Good
SPRING ST-01	BRIDGE ST	DIAMOND ST	Odd	491	4	Concrete	25% Replacement	Fair
SPRING ST-02	DIAMOND ST	ANDERSON ST	Even	206	4	Concrete	25% Replacement	Fair
SPRING ST-02	DIAMOND ST	ANDERSON ST	Odd	206	4	Concrete	25% Replacement	Fair
SPRING ST-03	ANDERSON ST	DUNN LN	Even	643	4	Concrete	25% Replacement	Fair
SPRING ST-03	ANDERSON ST	DUNN LN	Odd	643	4	Concrete	50% Replacement	Poor

Total Length: 2,680

SURREY DRIVE

SURREY DR	N HOADLEY ST	QUINN ST	Even	303	4	Mix	50% Replacement	Poor
SURREY DR	N HOADLEY ST	QUINN ST	Odd	303	4	Mix	50% Replacement	Poor

Total Length: 606

SVEA AVENUE

SVEA AVE	NEW ST	DEAD END	Even	16	4	Asphalt	10% Replacement	Good
SVEA AVE	NEW ST	DEAD END	Odd	32	4	Asphalt	25% Replacement	Fair

Total Length: 48

SWEENEY STREET

SWEENEY ST	WALNUT ST	HILLSIDE AVE	Even	237	4	Concrete	25% Replacement	Fair
SWEENEY ST	WALNUT ST	HILLSIDE AVE	Odd	237	4	Concrete	25% Replacement	Fair

Total Length: 474

SWIFT LANE

SWIFT LN	FAWN MEADOW DR	BLUEBIRD DR	Even	152	4	Concrete	10% Replacement	Good
SWIFT LN	FAWN MEADOW DR	BLUEBIRD DR	Odd	152	4	Concrete	10% Replacement	Good

Total Length: 304

TERRACE AVENUE

TERRACE AVE-01	HILLSIDE AVE	MILLVILLE AVE	Even	1130	4	Mix	50% Replacement	Poor
----------------	--------------	---------------	------	------	---	-----	-----------------	------

	From	To	Side	Length	Width	Material	Repair Method	Condition
TERRACE AVE-01	HILLSIDE AVE	MILLVILLE AVE	Odd	283	4	Mix	Defer Maintenance	Excellent
TERRACE AVE-02	MILLVILLE AVE	SALEM ST	Odd	478	4	Mix	10% Replacement	Good
TERRACE AVE-03	SALEM ST	WATER ST	Even	385	4	Concrete	10% Replacement	Good
TERRACE AVE-03	SALEM ST	WATER ST	Odd	385	4	Concrete	10% Replacement	Good

Total Length: 2,661

THISTLE DOWN LANE

THISTLE DOWN LN-03	MORNING DOVE RD	CUL DE SAC	Odd	53	3	Asphalt	10% Replacement	Good
--------------------	-----------------	------------	-----	----	---	---------	-----------------	------

Total Length: 53

TIDMOUTH LANE

TIDMOUTH LN	UNION CITY RD	CUL DE SAC	Even	323	4	Concrete	10% Replacement	Good
TIDMOUTH LN	UNION CITY RD	CUL DE SAC	Odd	538	4	Concrete	Defer Maintenance	Excellent

Total Length: 861

TROWBRIDGE PLACE

TROWBRIDGE PL-01	CLIFF ST	NETTLETON AVE	Even	688	4	Concrete	50% Replacement	Poor
TROWBRIDGE PL-01	CLIFF ST	NETTLETON AVE	Odd	688	4	Concrete	25% Replacement	Fair
TROWBRIDGE PL-02	NETTLETON AVE	GOODYEAR AVE	Even	161	4	Concrete	Defer Maintenance	Excellent
TROWBRIDGE PL-02	NETTLETON AVE	GOODYEAR AVE	Odd	161	4	Concrete	Defer Maintenance	Excellent

Total Length: 1,698

TYLER HILL ROAD

TYLER HILL RD	APPLEWOOD LN	CUL DE SAC	Even	976	4	Concrete	Defer Maintenance	Excellent
TYLER HILL RD	APPLEWOOD LN	CUL DE SAC	Odd	925	4	Concrete	Defer Maintenance	Excellent

Total Length: 1,901

UNION CITY ROAD

UNION CITY RD-03	TIDMOUTH LN	GAIL DR	Even	372	4	Concrete	10% Replacement	Good
------------------	-------------	---------	------	-----	---	----------	-----------------	------

Total Length: 372

WALNUT STREET

WALNUT ST-01	NEW ST	GROVE ST	Even	214	4	Concrete	10% Replacement	Good
WALNUT ST-01	NEW ST	GROVE ST	Odd	429	4	Concrete	50% Replacement	Poor
WALNUT ST-02	GROVE ST	MILLVILLE AVE	Even	795	4	Concrete	100% Replacement	Replace
WALNUT ST-02	GROVE ST	MILLVILLE AVE	Odd	795	4	Concrete	50% Replacement	Poor
WALNUT ST-03	MILLVILLE AVE	SWEENEY ST	Even	279	4	Concrete	50% Replacement	Poor
WALNUT ST-03	MILLVILLE AVE	SWEENEY ST	Odd	279	4	Concrete	25% Replacement	Fair
WALNUT ST-04	SWEENEY ST	ELMWOOD ST	Even	537	4	Concrete	25% Replacement	Fair
WALNUT ST-04	SWEENEY ST	ELMWOOD ST	Odd	537	4	Concrete	25% Replacement	Fair
WALNUT ST-05	ELMWOOD ST	WALNUT TER	Even	113	4	Concrete	25% Replacement	Fair
WALNUT ST-05	ELMWOOD ST	WALNUT TER	Odd	113	4	Concrete	25% Replacement	Fair
WALNUT ST-06	WALNUT TER	HIGHLAND CIR	Even	161	4	Concrete	25% Replacement	Fair
WALNUT ST-07	HIGHLAND CIR	HIGHLAND AVE	Even	121	4	Concrete	10% Replacement	Good

	From	To	Side	Length	Width	Material	Repair Method	Condition
WALNUT ST-07	HIGHLAND CIR	HIGHLAND AVE	Odd	121	4	Concrete	25% Replacement	Fair
WALNUT ST-08	HIGHLAND AVE	CLIFF ST	Even	109	4	Asphalt	25% Replacement	Fair
WALNUT ST-08	HIGHLAND AVE	CLIFF ST	Odd	109	4	Concrete	Defer Maintenance	Excellent
Total Length: 4,712								
WALNUT TERRACE								
WALNUT TER	WALNUT ST	PARK AVE	Even	415	3	Concrete	25% Replacement	Fair
WALNUT TER	WALNUT ST	PARK AVE	Odd	415	3	Concrete	25% Replacement	Fair
Total Length: 830								
WARD STREET								
WARD ST-01	ELM ST	NEVILLE ST	Even	537	4	Concrete	100% Replacement	Replace
WARD ST-01	ELM ST	NEVILLE ST	Odd	537	4	Mix	10% Replacement	Good
WARD ST-02	NEVILLE ST	SPENCER ST	Even	1408	4	Mix	50% Replacement	Poor
WARD ST-02	NEVILLE ST	SPENCER ST	Odd	1408	4	Concrete	50% Replacement	Poor
Total Length: 3,890								
WATER STREET								
WATER ST-01	NORTH CHURCH ST	MILLVILLE AVE	Odd	347	4	Mix	10% Replacement	Good
WATER ST-02	MILLVILLE AVE	CEDAR ST	Even	1279	6	Concrete	25% Replacement	Fair
WATER ST-03	CEDAR ST	MAPLE ST	Even	776	4	Mix	25% Replacement	Fair
Total Length: 2,402								
WEST STREET								
WEST ST	GALPIN ST	HOADLEY ST	Even	477	3	Asphalt	50% Replacement	Poor
Total Length: 477								
WESTOVER DRIVE								
WESTOVER DR-01	KRODEL RD	GRAHAM RIDGE RD	Even	243	4	Concrete	Defer Maintenance	Excellent
WESTOVER DR-01	KRODEL RD	GRAHAM RIDGE RD	Odd	243	4	Concrete	10% Replacement	Good
WESTOVER DR-02	GRAHAM RIDGE RD	GRAHAM RIDGE RD	Even	538	4	Concrete	25% Replacement	Fair
WESTOVER DR-02	GRAHAM RIDGE RD	GRAHAM RIDGE RD	Odd	538	4	Concrete	Defer Maintenance	Excellent
WESTOVER DR-03	GRAHAM RIDGE RD	WEBB RD	Even	421	4	Concrete	Defer Maintenance	Excellent
Total Length: 1,983								
WILD CHERRY DRIVE								
WILD CHERRY DR	FAWN MEADOW DR	CUL DE SAC	Even	284	4	Concrete	Defer Maintenance	Excellent
WILD CHERRY DR	FAWN MEADOW DR	CUL DE SAC	Odd	284	4	Concrete	Defer Maintenance	Excellent
Total Length: 568								
WILLOW LANE								
WILLOW LN	RADNOR AVE	CUL DE SAC	Even	235	6	Asphalt	25% Replacement	Fair
WILLOW LN	RADNOR AVE	CUL DE SAC	Odd	148	6	Asphalt	Defer Maintenance	Excellent
Total Length: 383								

	From	To	Side	Length	Width	Material	Repair Method	Condition
WINDVIEW DRIVE								
WINDVIEW DR	SKYVIEW DR	CUL DE SAC	Even	527	4	Concrete	10% Replacement	Good
WINDVIEW DR	SKYVIEW DR	CUL DE SAC	Odd	527	4	Concrete	10% Replacement	Good
				Total Length: 1,054				
WINSLOW COURT								
WINSLOW CT	MEADOW ST	DEAD END	Even	69	2	Concrete	Defer Maintenance	Excellent
WINSLOW CT	MEADOW ST	DEAD END	Odd	69	2	Asphalt	10% Replacement	Good
				Total Length: 138				
WISTERIA DRIVE								
WISTERIA DR-01	OSBORN RD	ROLLINGWOOD DR	Even	482	4	Concrete	10% Replacement	Good
WISTERIA DR-01	OSBORN RD	ROLLINGWOOD DR	Odd	482	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-02	ROLLINGWOOD DR	ADRIATIC LN	Even	1672	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-02	ROLLINGWOOD DR	ADRIATIC LN	Odd	1672	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-03	ADRIATIC LN	ROLLINGWOOD DR	Even	981	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-03	ADRIATIC LN	ROLLINGWOOD DR	Odd	981	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-04	ROLLINGWOOD DR	CUL DE SAC	Even	759	4	Concrete	Defer Maintenance	Excellent
WISTERIA DR-04	ROLLINGWOOD DR	CUL DE SAC	Odd	759	4	Concrete	Defer Maintenance	Excellent
				Total Length: 7,788				
WOOD STREET								
WOOD ST	N MAIN ST	DEAD END	Even	200	4	Mix	50% Replacement	Poor
WOOD ST	N MAIN ST	DEAD END	Odd	223	4	Concrete	50% Replacement	Poor
				Total Length: 423				
WOODBINE STREET								
WOODBINE ST-02	GEN HILL ST	STANLEY ST	Odd	20	3	Asphalt	Defer Maintenance	Excellent
				Total Length: 20				
WOODLAWN AVENUE								
WOODLAWN AVE	GROVE ST	MILLVILLE AVE	Odd	795	4	Mix	25% Replacement	Fair
				Total Length: 795				
WOODSIDE DRIVE								
WOODSIDE DR	MULBERRY ST	CUL DE SAC	Even	402	3	Asphalt	25% Replacement	Fair
				Total Length: 402				
WOOSTER STREET								
WOOSTER ST-04	DONOVAN RD	KOSKO LN	Odd	454	4	Concrete	10% Replacement	Good
WOOSTER ST-05	KOSKO LN	WHITNEY PL	Odd	417	4	Concrete	Defer Maintenance	Excellent
WOOSTER ST-07	APPLEWOOD LN	GLEN HOLLOW RD	Even	321	4	Concrete	Defer Maintenance	Excellent
				Total Length: 1,192				

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Condition Summary With Detailed Description

	Exists	Length	Width	Material	Condition	Major Issues		
Street : ACUSHNET STREET								
Segment: ACUSHNET ST-01								
From:GOLDEN HILL ST		To: STANLEY ST						
Odd Side:	Odd	95	2	Concrete	Replace	Patching	Linear Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0
Street : ADRIATIC LANE								
Segment: ADRIATIC LN-01								
From:VILLAGE CIR		To: D'ARCANGELO DR						
Odd Side:	Odd	147	4	Concrete	Excellent	0	0	0
Even Side:	Even	147	4	Concrete	Excellent	0	0	0
Segment: ADRIATIC LN-02								
From:D'ARCANGELO DR		To: WISTERIA DR						
Odd Side:	Odd	149	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	149	4	Concrete	Excellent	Grass	0	0
Street : AETNA STREET								
Segment: AETNA ST-02								
From:GALPIN ST		To: BEEBE ST						
Odd Side:	Odd	31	4	Asphalt	Excellent	0	0	0
Even Side:	Even	21	2	Concrete	Fair	Patching	Linear Cracking	0
Segment: AETNA ST-03								
From:BEEBE ST		To: EDWARD ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	18	4	Concrete	Excellent	0	0	0
Segment: AETNA ST-04								

	Exists	Length	Width	Material	Condition	Major Issues				
From:EDWARD ST		To: GOODYEAR AVE								
Odd Side:	None	0	0	None	0	0	0	0		
Even Side:	Even	120	4	Concrete	Good	Linear Cracking	Grass	0		
Segment: AETNA ST-05										
From:GOODYEAR AVE		To: NETTLETON AVE								
Odd Side:	Odd	260	4	Concrete	Fair	Linear Cracking	Lifting	Depressions		
Even Side:	Even	260	4	Concrete	Fair	Grass	Linear Cracking	Lifting		
Segment: AETNA ST-06										
From:NETTLETON AVE		To: CLIFF ST								
Odd Side:	Odd	629	4	Concrete	Poor	Depressions	Linear Cracking	0		
Even Side:	Even	629	4	Concrete	Fair	Lifting	Linear Cracking	Alligator Cracking		
Segment: AETNA ST-07										
From:CLIFF ST		To: AETNA PL								
Odd Side:	Odd	216	4	Concrete	Poor	Depressions	Patching	Lifting		
Even Side:	Even	216	4	Concrete	Poor	Depressions	Patching	Linear Cracking		
Segment: AETNA ST-08										
From:AETNA PL		To: RUBBER AVE								
Odd Side:	Odd	243	4	Concrete	Replace	Depressions	Patching	Linear Cracking		
Even Side:	Even	243	4	Concrete	Poor	Depressions	Patching	Lifting		
Street : ANDERSON STREET										
Segment: ANDERSON ST										
From:SCHOOL ST		To: SPRING ST								
Odd Side:	Odd	739	4	Asphalt	Good	Linear Cracking	Grass	0		
Even Side:	Even	739	4	Asphalt	Good	Grass	Linear Cracking	0		
Street : ANDREW AVENUE										
Segment: ANDREW AVE-01										
From:RUBBER AVE		To: SCOTT ST								
Odd Side:	Odd	76	4	Concrete	Excellent	0	0	0		
Even Side:	Even	38	4	Concrete	Excellent	0	0	0		
Segment: ANDREW AVE-03										

	Exists	Length	Width	Material	Condition		Major Issues	
From: MANNERS AVE								
To: MELBOURNE ST								
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	959	4	Mix	Good	Linear Cracking	Grass	0

Segment: ANDREW AVE-04

From: MELBOURNE ST								
To: OLD DERBY TPKE								
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	674	0	Mix	0	0	0	0

Street : APPLE BLOSSOM DRIVE

Segment: APPLE BLOSSOM DR

From: FAWN MEADOW DR								
To: CUL DE SAC								
Odd Side:	Odd	641	4	Concrete	Excellent	Patching	0	0
Even Side:	Even	641	4	Concrete	Excellent	Patching	0	0

Street : APPLEWOOD LANE

Segment: APPLEWOOD LN-01

From: WOOSTER ST								
To: TYLER HILL RD								
Odd Side:	Odd	1,039	4	Concrete	Excellent	Grass	Lifting	0
Even Side:	Even	1,039	4	Concrete	Excellent	Grass	Lifting	0

Segment: APPLEWOOD LN-02

From: TYLER HILL RD								
To: SKYVIEW DR								
Odd Side:	Odd	1,147	4	Concrete	Excellent	Grass	Lifting	0
Even Side:	Even	1,147	4	Concrete	Excellent	Grass	0	0

Segment: APPLEWOOD LN-03

From: SKYVIEW DR								
To: DONOVAN RD								
Odd Side:	Odd	695	4	Concrete	Good	Grass	Lifting	Patching
Even Side:	Even	521	4	Concrete	Good	Grass	Lifting	0

Segment: APPLEWOOD LN-04

From: DONOVAN RD								
To: ROSEWOOD CT								
Odd Side:	Odd	350	4	Concrete	Excellent	Linear Cracking	Grass	0
Even Side:	Even	350	4	Concrete	Excellent	0	0	0

Segment: APPLEWOOD LN-05

	Exists	Length	Width	Material	Condition	Major Issues		
From:ROSEWOOD CT	To: COUNTRY HOLLOW RD							
Odd Side:	Odd	537	4	Concrete	Good	Lifting	Grass	Linear Cracking
Even Side:	Even	537	4	Concrete	Excellent	Grass	Linear Cracking	0

Street : ARBOR AVENUE

Segment: ARBOR AVE-01

From:MAPLE HILL RD	To: KENT ST							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	304	4	Asphalt	Fair	Grass	Linear Cracking	Depressions

Segment: ARBOR AVE-02

From:KENT ST	To: RUSTLING REED RD							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	297	4	Asphalt	Good	Grass	Linear Cracking	Depressions

Street : ARCH STREET

Segment: ARCH ST

From:SCOTT ST	To: RUBBER AVE							
Odd Side:	Odd	184	4	Concrete	Excellent	0	0	0
Even Side:	Even	737	4	Mix	Fair	Patching	Linear Cracking	Depressions

Street : AUBURN STREET

Segment: AUBURN ST-07

From:ALBION ST	To: CUL DE SAC							
Odd Side:	Odd	305	4	Concrete	Excellent	0	0	0
Even Side:	Even	508	4	Concrete	Excellent	Grass	0	0

Street : BARNUM COURT

Segment: BARNUM CT

From:CHURCH ST	To: DEAD END							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	60	2	Mix	Good	Patching	Depressions	0

Street : BEARDSLEY AVENUE

Segment: BEARDSLEY AVE-01

	Exists	Length	Width	Material	Condition	Major Issues		
From:PLATTS MILLS RD	To: RADNOR AVE							
Odd Side:	Odd	288	4	Concrete	Good	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	288	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions

Segment: BEARDSLEY AVE-02

From:RADNOR AVE	To: WATERBURY TL							
Odd Side:	Odd	584	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	649	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Tree Roots

Street : BEEBE STREET

Segment: BEEBE ST

From:AETNA ST	To: HIGHLAND AVE							
Odd Side:	Odd	986	4	Mix	Fair	Depressions	Patching	Lifting
Even Side:	Even	986	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Patching

Street : BEECHER STREET

Segment: BEECHER ST

From:BUCKINGHAM ST	To: SHERMAN ST							
Odd Side:	Odd	573	4	Concrete	Fair	Lifting	Over Hanging Tree	0
Even Side:	Even	573	4	Concrete	Good	Linear Cracking	Lifting	0

Street : BRADLEY STREET

Segment: BRADLEY ST

From:OAK ST	To: HILL ST							
Odd Side:	Odd	555	4	Mix	Fair	Linear Cracking	Grass	Patching
Even Side:	Even	555	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions

Street : BRENNAN STREET

Segment: BRENNAN ST-01

From:BRIDGE ST	To: CROWN ST							
Odd Side:	Odd	429	4	Concrete	Excellent	0	0	0
Even Side:	Even	21	4	Concrete	Excellent	0	0	0

Segment: BRENNAN ST-02

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: CALVIN ST								
From:N MAIN ST		To: HIGH ST						
Odd Side:	Odd	659	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : CAROLYN CIRCLE

Segment: CAROLYN CIR

From:PICTURE LN		To: PICTURE LN						
Odd Side:	Odd	364	3	Concrete	Fair	Linear Cracking	Grass	Depressions
Even Side:	Even	364	3	Concrete	Fair	Grass	Depressions	Alligator Cracking

Street : CARROLL COURT

Segment: CARROLL CT

From:CARROLL ST		To: DEAD END						
Odd Side:	Odd	338	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching
Even Side:	Even	338	3	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions

Street : CARROLL STREET

Segment: CARROLL ST-01

From:MAPLE ST		To: CENTRAL AVE						
Odd Side:	Odd	790	4	Concrete	Excellent	Grass	Linear Cracking	0
Even Side:	Even	790	4	Concrete	Excellent	Grass	0	0

Segment: CARROLL ST-02

From:CENTRAL AVE		To: CARROLL CT						
Odd Side:	Odd	261	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	261	4	Concrete	Excellent	Grass	0	0

Segment: CARROLL ST-03

From:CARROLL CT		To: HIGH ST						
Odd Side:	Odd	181	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Grass
Even Side:	Even	181	4	Concrete	Poor	Lifting	Linear Cracking	Alligator Cracking

Street : CEDAR STREET

Segment: CEDAR ST

	Exists	Length	Width	Material	Condition	Major Issues		
From:CHURCH ST	To: WATER ST							
Odd Side:	Odd	578	5	Mix	Good	Lifting	Depressions	0
Even Side:	Even	289	5	Concrete	Good	Lifting	Linear Cracking	0

Street : CENTRAL AVENUE

Segment: CENTRAL AVE

From:MAPLE ST	To: CARROLL ST							
Odd Side:	Odd	210	4	Concrete	Replace	Depressions	Alligator Cracking	Linear Cracking
Even Side:	Even	1,049	4	Concrete	0	Linear Cracking	Grass	Alligator Cracking

Street : CHARLES STREET

Segment: CHARLES ST-02

From:CHARLES CT	To: ANN ST							
Odd Side:	Odd	209	4	Concrete	Excellent	Grass	Lifting	0
Even Side:	None	0	0	None	0	0	0	0

Street : CHERRY STREET

Segment: CHERRY ST-01

From:SPENCER ST	To: OLIVE ST							
Odd Side:	Odd	1,103	4	Concrete	Excellent	0	0	0
Even Side:	Even	1,103	5	Concrete	Excellent	Grass	0	0

Segment: CHERRY ST-02

From:OLIVE ST	To: ROUTE 63							
Odd Side:	Odd	1,287	4	Concrete	Excellent	0	0	0
Even Side:	Even	1,287	4	Concrete	Excellent	0	0	0

Street : CHERRY STREET EXTENSION

Segment: CHERRY ST EXT-01

From:SPENCER ST	To: CHARLES ST							
Odd Side:	Odd	447	4	Concrete	Excellent	0	0	0
Even Side:	Even	447	4	Concrete	Excellent	0	0	0

Segment: CHERRY ST EXT-02

	Exists	Length	Width	Material	Condition	Major Issues		
From:CHARLES ST	To: ANN ST							
Odd Side:	Odd	401	4	Concrete	Good	Linear Cracking	Alligator Cracking	0
Even Side:	Even	141	4	Concrete	Excellent	0	0	0

Segment: CHERRY ST EXT-03

From:ANN ST	To: DEAD END							
Odd Side:	Odd	70	4	Asphalt	Replace	Depressions	Linear Cracking	0
Even Side:	Even	141	4	Asphalt	Replace	Depressions	Linear Cracking	0

Street : CHESTNUT STREET

Segment: CHESTNUT ST-01

From:N HOADLEY ST	To: FERN ST							
Odd Side:	Odd	277	4	Mix	Replace	Alligator Cracking	Linear Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0

Segment: CHESTNUT ST-02

From:FERN ST	To: QUINN ST							
Odd Side:	Odd	261	4	Asphalt	Fair	Grass	Linear Cracking	Patching
Even Side:	None	0	0	None	0	0	0	0

Segment: CHESTNUT ST-03

From:QUINN ST	To: PARK AVE							
Odd Side:	Odd	143	3	Mix	Good	Depressions	Linear Cracking	0
Even Side:	Even	86	4	Concrete	Excellent	Linear Cracking	0	0

Street : CHURCH STREET

Segment: CHURCH ST-01

From:RUBBER AVE	To: BARNUM CT							
Odd Side:	Odd	527	6	Concrete	Excellent	0	0	0
Even Side:	Even	527	6	Concrete	Excellent	0	0	0

Segment: CHURCH ST-02

From:BARNUM CT	To: PARK PL							
Odd Side:	Odd	262	6	Concrete	Excellent	Linear Cracking	0	0
Even Side:	Even	262	6	Concrete	Excellent	Lifting	0	0

Segment: CHURCH ST-03

	Exists	Length	Width	Material	Condition	Major Issues		
From: PARK PL	To: MAPLE ST							
Odd Side:	Odd	428	6	Concrete	Excellent	0	0	0
Even Side:	Even	428	6	Concrete	Excellent	0	0	0

Segment: CHURCH ST-04

From: MAPLE ST	To: DIVISION ST							
Odd Side:	Odd	150	6	Concrete	Excellent	0	0	0
Even Side:	Even	150	6	Concrete	Excellent	0	0	0

Segment: CHURCH ST-05

From: DIVISION ST	To: CEDAR ST							
Odd Side:	Odd	547	6	Concrete	Fair	Patching	Depressions	0
Even Side:	Even	547	6	Concrete	Excellent	0	0	0

Segment: CHURCH ST-06

From: CEDAR ST	To: MEADOW CT							
Odd Side:	Odd	448	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	448	4	Concrete	Fair	Linear Cracking	Patching	Depressions

Segment: CHURCH ST-07

From: MEADOW CT	To: WATER ST							
Odd Side:	Odd	677	4	Concrete	Good	Alligator Cracking	Linear Cracking	Lifting
Even Side:	Even	677	4	Concrete	Good	Alligator Cracking	Linear Cracking	Depressions

Street : CITY BROOK ROAD

Segment: CITY BROOK RD-01

From: CITY HILL ST	To: SKYVIEW DR							
Odd Side:	Odd	675	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	641	4	Concrete	Good	Linear Cracking	Lifting	0

Segment: CITY BROOK RD-02

From: SKYVIEW DR	To: DONOVAN RD							
Odd Side:	Odd	460	4	Concrete	Fair	Grass	Depressions	Lifting
Even Side:	Even	460	4	Concrete	Good	Grass	Linear Cracking	Linear Cracking

Street : CITY HILL STREET

Segment: CITY HILL ST-01

	Exists	Length	Width	Material	Condition	Major Issues			
From:N MIAN ST		To: CITY HILL CT							
Odd Side:	Odd	641	4	Mix	Fair	Patching	Grass	Linear Cracking	
Even Side:	Even	641	4	Concrete	Poor	Depressions	Alligator Cracking	Patching	
Segment: CITY HILL ST-02									
From:CITY HILL CT		To: HIGH ST							
Odd Side:	Odd	406	4	Concrete	Fair	Grass	Depressions	0	
Even Side:	Even	406	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions	
Segment: CITY HILL ST-03									
From:HIGH ST		To: JOHN ST							
Odd Side:	None	0	0	None	0	0	0	0	
Even Side:	Even	491	4	Concrete	Excellent	Grass	0	0	
Segment: CITY HILL ST-04									
From:JOHN ST		To: WOOSTER ST							
Odd Side:	Odd	118	4	Concrete	Excellent	Grass	0	0	
Even Side:	Even	473	4	Concrete	Excellent	Grass	0	0	
Segment: CITY HILL ST-05									
From:WOOSTER ST		To: COEN LN							
Odd Side:	Odd	202	4	Concrete	Good	Grass	Linear Cracking	Lifting	
Even Side:	Even	1,012	4	Concrete	Excellent	Grass	0	0	
Segment: CITY HILL ST-06									
From:COEN LN		To: MORRIS ST							
Odd Side:	Odd	263	4	Concrete	Excellent	Grass	0	0	
Even Side:	None	0	0	None	0	0	0	0	
Segment: CITY HILL ST-07									
From:MORRIS ST		To: CITY BROOK RD							
Odd Side:	Odd	920	4	Concrete	Excellent	Linear Cracking	Grass	0	
Even Side:	None	0	0	None	0	0	0	0	
Segment: CITY HILL ST-08									
From:CITY BROOK RD		To: DONOVAN RD							
Odd Side:	Odd	196	2	Asphalt	Replace	Linear Cracking	Grass	Depressions	
Even Side:	None	0	0	None	0	0	0	0	

	Exists	Length	Width	Material	Condition	Major Issues		
Street : CLARK ROAD								
Segment: CLARK RD-01								
From:NEW HAVEN RD								
To: VALLEY MOBILE HOME PARK								
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	643	2	Asphalt	Replace	Linear Cracking	Depressions	0
Street : CLEARVIEW CIRCLE								
Segment: CLEARVIEW CIR								
From:MILLVILLE AVE								
To: MILLVILLE AVE								
Odd Side:	Odd	1,272	4	Concrete	Good	Linear Cracking	Over Hanging Tree	0
Even Side:	Even	1,017	4	Concrete	Fair	Patching	Depressions	Linear Cracking
Street : CLIFF STREET								
Segment: CLIFF ST-01								
From:AETNA ST								
To: LE CLAIR CT								
Odd Side:	Odd	13	4	Asphalt	Excellent	0	0	0
Even Side:	Even	258	4	Concrete	Good	Grass	Linear Cracking	0
Segment: CLIFF ST-02								
From:LE CLAIR CT								
To: PLEASANT VIEW ST								
Odd Side:	Odd	467	4	Mix	Good	Depressions	Linear Cracking	Grass
Even Side:	Even	467	4	Concrete	Fair	Depressions	Lifting	Linear Cracking
Segment: CLIFF ST-03								
From:PLEASANT VIEW ST								
To: GEORGE ST								
Odd Side:	Odd	423	4	Concrete	Fair	Patching	Grass	0
Even Side:	Even	423	4	Concrete	Fair	Depressions	Linear Cracking	Lifting
Segment: CLIFF ST-04								
From:GEORGE ST								
To: FREDRICK ST								
Odd Side:	Odd	241	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	241	4	Concrete	Good	Linear Cracking	Grass	0
Segment: CLIFF ST-05								

	Exists	Length	Width	Material	Condition	Major Issues		
From: FREDRICK ST	To: WALNUT ST							
Odd Side:	Odd	321	4	Concrete	Fair	Patching	Depressions	Lifting
Even Side:	Even	321	4	Concrete	Poor	Linear Cracking	Depressions	Lifting

Segment: CLIFF ST-06

From: WALNUT ST	To: FAIRVIEW AVE							
Odd Side:	Odd	314	4	Concrete	Replace	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	314	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Depressions

Street : COBBLE STREETONE COURT

Segment: COBBLE STONE CT

From: PEMBROOK RD	To: CUL DE SAC							
Odd Side:	Odd	375	4	Concrete	Excellent	0	0	0
Even Side:	Even	419	4	Concrete	Excellent	0	0	0

Street : COEN STREET

Segment: COEN ST

From: OAK ST	To: DEAD END							
Odd Side:	Odd	956	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	956	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching

Street : COLD SPRING CIRCLE

Segment: COLD SPRING CIR-01

From: BROOK ST	To: CUL DE SAC							
Odd Side:	Odd	223	3	Concrete	Good	Linear Cracking	Alligator Cracking	Grass
Even Side:	Even	223	3	Concrete	Poor	Depressions	0	0

Segment: COLD SPRING CIR-02

From: CUL DE SAC	To: COLD SPRING CIR							
Odd Side:	Odd	1,137	3	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching
Even Side:	Even	1,137	3	Concrete	Fair	Lifting	Linear Cracking	Depressions

Street : CROFUT ROAD

Segment: CROFUT RD

	Exists	Length	Width	Material	Condition	Major Issues		
From:WEBB RD	To: RUBBER AVE EXT							
Odd Side:	Odd	581	3	Concrete	Good	Grass	Depressions	Linear Cracking
Even Side:	None	0	0	None	0	0	0	0

Street : CROSSING NORTH

Segment: PINWOOD CROSSING NORTH

From:SILVER BEECH DR	To: CUL DE SAC							
Odd Side:	Odd	411	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	411	4	Concrete	Excellent	Grass	0	0

Street : CULVER STREET

Segment: CULVER ST-01

From:HILL ST	To: HILLCREST AVE							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	279	4	Concrete	Fair	Linear Cracking	Lifting	Grass

Segment: CULVER ST-02

From:HILLCREST AVE	To: HOMESTEAD AVE							
Odd Side:	Odd	234	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	261	3	Concrete	Poor	Patching	Depressions	Linear Cracking

Street : CURTISS STREET

Segment: CURTISS ST-01

From:N MAIN ST	To: LINDEN ST							
Odd Side:	Odd	269	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	537	5	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions

Segment: CURTISS ST-02

From:LINDEN ST	To: GRIFFIN ST							
Odd Side:	Odd	106	4	Mix	Excellent	0	0	0
Even Side:	Even	708	4	Asphalt	Poor	Alligator Cracking	Patching	Grass

Segment: CURTISS ST-03

From:GRIFFINS ST	To: ROUTE 8							
Odd Side:	Odd	305	4	Concrete	Poor	Linear Cracking	Depressions	Grass
Even Side:	Even	305	4	Concrete	Replace	Linear Cracking	Depressions	Grass

	Exists	Length	Width	Material	Condition	Major Issues		
Street : DAMSON LANE								
Segment: DAMSON LN-01								
From:N HOADLEY ST		To: BIRCH LN						
Odd Side:	Odd	188	4	Concrete	Good	Lifting	0	0
Even Side:	Even	188	4	Mix	Good	Lifting	0	0
Segment: DAMSON LN-02								
From:BIRCH LN		To: N HOADLEY ST						
Odd Side:	Odd	866	4	Concrete	Poor	Tree Roots	Depressions	Lifting
Even Side:	Even	866	4	Mix	Replace	Depressions	Lifting	Linear Cracking
Street : DEERING LANE								
Segment: DEERING LN								
From:N HOADLEY ST		To: DEAD END						
Odd Side:	Odd	588	4	Mix	Fair	Alligator Cracking	Tree Roots	Linear Cracking
Even Side:	Even	588	4	Mix	Good	Lifting	Depressions	0
Street : DIAMOND STREET								
Segment: DIAMOND ST								
From:SPRING ST		To: BRENNAN ST						
Odd Side:	Odd	395	4	Concrete	Good	Grass	Linear Cracking	Patching
Even Side:	Even	395	4	Concrete	Good	Grass	Linear Cracking	Patching
Street : DIVISION STREET								
Segment: DIVISION ST								
From:CHURCH ST		To: MEADOW ST						
Odd Side:	Odd	349	4	Concrete	Good	Linear Cracking	Grass	0
Even Side:	Even	349	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching
Street : DONOVAN ROAD								
Segment: DONOVAN RD-01								
From:MAY ST		To: CITY HILL ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	252	4	Concrete	Excellent	Lifting	Grass	0
Segment: DONOVAN RD-02								

	Exists	Length	Width	Material	Condition	Major Issues		
From: CITY HILL ST	To: CITY BROOK RD							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	475	4	Concrete	Excellent	0	0	0

Segment: DONOVAN RD-03

From: CITY BROOK RD	To: APPLEWOOD LN							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	328	4	Concrete	Good	Grass	Linear Cracking	0

Segment: DONOVAN RD-04

From: APPLEWOOD LN	To: SIRRA RIDGE RD							
Odd Side:	Odd	872	4	Concrete	Good	Lifting	Linear Cracking	0
Even Side:	Even	436	4	Concrete	Good	Grass	Linear Cracking	0

Segment: DONOVAN RD-05

From: SIERRA RIDGE RD	To: DONOVAN CT							
Odd Side:	Odd	590	4	Concrete	Good	Linear Cracking	Alligator Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0

Segment: DONOVAN RD-06

From: DONOVAN CT	To: WOOSTER ST							
Odd Side:	Odd	468	4	Asphalt	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : EAGLE STREET

Segment: EAGLE ST-01

From: PROSPECT ST	To: ENDOGEN ST							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	31	3	Asphalt	Good	Linear Cracking	0	0

Street : EAST DRIVE

Segment: EAST DR

From: PARK AVE	To: QUINN ST							
Odd Side:	Odd	41	4	Concrete	Replace	Lifting	Alligator Cracking	Depressions
Even Side:	Even	206	4	Asphalt	Fair	Linear Cracking	Alligator Cracking	Depressions

Street : ELM STREET

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: ELM ST-01								
From: RUBBER AVE								
		To: SCOTT ST						
Odd Side:	Odd	826	4	Mix	Fair	Linear Cracking	Alligator Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0
Segment: ELM ST-02								
From: SCOTT ST								
		To: CHERRY ST						
Odd Side:	Odd	292	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0
Segment: ELM ST-03								
From: CHERRY ST								
		To: SPENCER ST						
Odd Side:	Odd	321	4	Mix	Replace	Linear Cracking	Patching	0
Even Side:	None	0	0	None	0	0	0	0
Street : ELMWOOD STREET								
Segment: ELMWOOD ST-01								
From: WALNUT ST								
		To: ELMHURST ST						
Odd Side:	Odd	239	4	Concrete	Fair	Alligator Cracking	Depressions	Lifting
Even Side:	Even	239	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Lifting
Segment: ELMWOOD ST-02								
From: ELMHURST ST								
		To: HILLSIDE AVE						
Odd Side:	Odd	208	4	Concrete	Good	Grass	0	0
Even Side:	Even	208	4	Concrete	Excellent	0	0	0
Street : FAIRCHILD STREET								
Segment: FAIRCHILD ST-01								
From: LEWIS ST								
		To: MALGARI CT						
Odd Side:	Odd	429	4	Mix	Fair	Linear Cracking	Grass	Depressions
Even Side:	Even	321	4	Concrete	Good	Linear Cracking	Grass	Depressions
Segment: FAIRCHILD ST-02								
From: MALGARI CT								
		To: HARD ST						
Odd Side:	Odd	234	4	Mix	Good	Linear Cracking	Grass	0
Even Side:	None	0	0	None	0	0	0	0

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: FAIRCHILD ST-03								
From:HARD ST		To: GORMAN ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	106	4	Concrete	Good	Linear Cracking	Alligator Cracking	Grass
Street : FAIRFIELD COURT								
Segment: FAIRFIELD CT								
From:FIELD ST		To: CUL DE SAC						
Odd Side:	Odd	20	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0
Street : FAIRLAWN STREET								
Segment: FAIRLAWN ST								
From:HILL ST		To: HILLCREST AVE						
Odd Side:	Odd	237	4	Concrete	Fair	Linear Cracking	Grass	Depressions
Even Side:	Even	237	4	Concrete	Fair	Linear Cracking	Grass	Depressions
Street : FAIRVIEW AVENUE								
Segment: FAIRVIEW AVE-01								
From:POND ST		To: PLEASANT VIEW ST						
Odd Side:	Odd	277	5	Mix	Good	Linear Cracking	Depressions	0
Even Side:	Even	277	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Segment: FAIRVIEW AVE-02								
From:PLEASANT VIEW ST		To: GEORGE ST						
Odd Side:	Odd	748	0	Mix	Good	Patching	Linear Cracking	0
Even Side:	Even	748	0	Concrete	Replace	Linear Cracking	Depressions	Lifting
Segment: FAIRVIEW AVE-03								
From:GEORGE ST		To: FREDRICK ST						
Odd Side:	Odd	242	6	Concrete	Excellent	0	0	0
Even Side:	Even	242	4	Concrete	Fair	Lifting	Linear Cracking	Alligator Cracking
Segment: FAIRVIEW AVE-04								

	Exists	Length	Width	Material	Condition	Major Issues		
From:FREDRICK ST	To: CLIFF ST							
Odd Side:	Odd	203	5	Concrete	Fair	Linear Cracking	Depressions	Grass
Even Side:	Even	203	4	Concrete	Poor	Alligator Cracking	Lifting	Patching

Segment: FAIRVIEW AVE-05

From:CLIFF ST	To: HILLSIDE AVE							
Odd Side:	Odd	271	5	Concrete	Good	Linear Cracking	Grass	0
Even Side:	Even	271	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions

Street : FARMSTEAD LANE

Segment: FARMSTEAD LN

From:GRAHAM RIDGE RD	To: CUL DE SAC							
Odd Side:	Odd	691	4	Concrete	Excellent	Lifting	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : FAWN MEADOW DRIVE

Segment: FAWN MEADOW DR-01

From:MULBERRY ST	To: WILD CHERRY DR							
Odd Side:	Odd	948	4	Concrete	Excellent	0	0	0
Even Side:	Even	948	4	Concrete	Excellent	Grass	0	0

Segment: FAWN MEADOW DR-02

From:WILD CHERRY DR	To: APPLE BLOSSOM DR							
Odd Side:	Odd	1,065	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	1,065	4	Concrete	Good	Grass	Lifting	0

Segment: FAWN MEADOW DR-03

From:APPLE BLOSSOM DR	To: PEAR TREE DR							
Odd Side:	Odd	337	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	337	4	Concrete	Excellent	Grass	0	0

Segment: FAWN MEADOW DR-04

From:PEAR TREE DR	To: SWIFT LN							
Odd Side:	Odd	329	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	329	4	Concrete	Excellent	Grass	0	0

Street : FERN STREET

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: FERN ST-01								
From:CHESTNUT ST		To: COTTAGE ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	166	4	Asphalt	Excellent	0	0	0

Segment: FERN ST-02								
From:COTTAGE ST		To: MILLVILLE AVE						
Odd Side:	Odd	588	4	Mix	Fair	Patching	Alligator Cracking	0
Even Side:	Even	654	4	Mix	Replace	Patching	Alligator Cracking	Tree Roots

Street : FIELD STREET

Segment: FIELD ST-14								
From:HILLSIDE AVE		To: NORTH CHURCH ST						
Odd Side:	Odd	262	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : FREDRICK STREET

Segment: FREDRICK ST								
From:FAIRVIEW AVE		To: CLIFF ST						
Odd Side:	Odd	417	4	Concrete	Replace	Alligator Cracking	Depressions	Lifting
Even Side:	Even	417	4	Concrete	Fair	Lifting	Alligator Cracking	Linear Cracking

Street : GALPIN STREET

Segment: GALPIN ST-01								
From:AETNA ST		To: MARSHALL AVE						
Odd Side:	Odd	587	4	Concrete	Fair	Grass	Linear Cracking	Lifting
Even Side:	Even	587	4	Concrete	Poor	Patching	Alligator Cracking	Linear Cracking

Segment: GALPIN ST-02								
From:MARSHALL AVE		To: WEST ST						
Odd Side:	Odd	238	4	Concrete	Poor	Grass	Alligator Cracking	Lifting
Even Side:	Even	238	4	Concrete	Fair	Linear Cracking	Grass	Lifting

Segment: GALPIN ST-03

	Exists	Length	Width	Material	Condition	Major Issues		
From:WEST ST	To: HIGHLAND AVE							
Odd Side:	Odd	225	4	Mix	Fair	Linear Cracking	Alligator Cracking	Patching
Even Side:	Even	225	4	Mix	Fair	Linear Cracking	Grass	0

Street : GENERAL DALTON DRIVE

Segment: GENERAL DALTON DR-01

From:MARJORIE ST	To: GENERAL DALTON DR							
Odd Side:	Odd	610	4	Concrete	Fair	Lifting	Depressions	Grass
Even Side:	Even	610	4	Concrete	Good	Lifting	Grass	Linear Cracking

Segment: GENERAL DALTON DR-02

From:GENERAL DALTON DR	To: DEAD END							
Odd Side:	Odd	135	4	Concrete	Good	Linear Cracking	0	0
Even Side:	Even	75	4	Concrete	Good	Lifting	Linear Cracking	0

Street : GENERAL PATTON DRIVE

Segment: GENERAL PATTON DR-01

From:MARJORIE ST	To: GENERAL DALTON DR							
Odd Side:	Odd	802	4	Concrete	Fair	Linear Cracking	Depressions	Alligator Cracking
Even Side:	Even	762	4	Concrete	Fair	Patching	Depressions	Lifting

Segment: GENERAL PATTON DR-02

From:GENERAL DALTON DR	To: GLENDALE CT							
Odd Side:	Odd	513	4	Concrete	Good	Linear Cracking	0	0
Even Side:	Even	684	4	Concrete	Fair	Linear Cracking	Patching	Depressions

Segment: GENERAL PATTON DR-03

From:GLENDALE CT	To: DEAD END							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	155	4	Concrete	Good	Linear Cracking	Lifting	0

Street : GENERAL PULASKI WALK

Segment: GENERAL PULASKI WALK

From:BRIDGE ST	To: DEAD END							
Odd Side:	Odd	300	4	Concrete	Good	Linear Cracking	Grass	0
Even Side:	Even	500	4	Concrete	Poor	Patching	Depressions	Linear Cracking

	Exists	Length	Width	Material	Condition	Major Issues		
Street : GEORGE STREET								
Segment: GEORGE ST								
From:FAIRVIEW AVE		To: CLIFF ST						
Odd Side:	Odd	402	4	Concrete	Fair	Patching	Linear Cracking	Lifting
Even Side:	Even	402	4	Concrete	Fair	Patching	Linear Cracking	0

Street : GOLDEN HILL STREET

Segment: GOLDEN HILL ST-01

From:PROSPECT ST		To: ACUSHNET ST						
Odd Side:	Odd	584	3	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	584	4	Concrete	Fair	Linear Cracking	Grass	Patching

Segment: GOLDEN HILL ST-02

From:ACUSHNET ST		To: WOODBINE ST						
Odd Side:	Odd	428	3	Concrete	Poor	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	428	3	Concrete	Poor	Grass	Linear Cracking	Depressions

Street : GOODYEAR AVENUE

Segment: GOODYEAR AVE-01

From:AETNA ST		To: TROWBRIDGE PL						
Odd Side:	Odd	732	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching
Even Side:	Even	732	4	Concrete	Poor	Depressions	Alligator Cracking	Lifting

Segment: GOODYEAR AVE-02

From:TROWBRIDGE PL		To: HIGHLAND AVE						
Odd Side:	Odd	307	4	Concrete	Fair	Patching	Lifting	Linear Cracking
Even Side:	Even	307	4	Concrete	Poor	Patching	Lifting	Depressions

Street : GORMAN STREET

Segment: GORMAN ST-01

From:LEWIS ST		To: OLIVE ST						
Odd Side:	Odd	298	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Patching
Even Side:	Even	694	4	Concrete	Fair	Grass	Linear Cracking	Patching

Segment: GORMAN ST-02

	Exists	Length	Width	Material	Condition	Major Issues		
From:OLIVE ST	To: VAGNINI DR							
Odd Side:	Odd	328	6	Mix	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	328	6	Mix	Fair	Linear Cracking	Alligator Cracking	Alligator Cracking

Segment: GORMAN ST-03

From:VAGNINI DR	To: FAIRCHILD ST							
Odd Side:	Odd	253	4	Concrete	Fair	Lifting	Depressions	0
Even Side:	Even	253	4	Concrete	Good	Patching	Alligator Cracking	0

Segment: GORMAN ST-04

From:FAIRCHILD ST	To: SPENCER ST							
Odd Side:	Odd	281	4	Mix	Fair	Linear Cracking	Lifting	0
Even Side:	Even	562	4	Concrete	Fair	Linear Cracking	Lifting	Patching

Street : GRAHAM RIDGE ROAD

Segment: GRAHAM RIDGE RD-01

From:WESTOVER DR	To: FARMSTEAD LN							
Odd Side:	Odd	1,341	4	Concrete	Good	Grass	Lifting	0
Even Side:	Even	1,341	4	Concrete	Fair	Grass	Over Hanging Tree	Lifting

Segment: GRAHAM RIDGE RD-02

From:FARMSTEAD LN	To: WESTOVER DR							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	2,050	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Lifting

Street : GREENWOOD STREET

Segment: GREENWOOD ST-01

From:SCHOOL ST	To: BRIDGE ST							
Odd Side:	Odd	23	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	466	4	Concrete	Fair	Grass	Patching	Linear Cracking

Segment: GREENWOOD ST-02

From:BRIDGE ST	To: DEAD END							
Odd Side:	Odd	25	4	Concrete	Good	Grass	0	0
Even Side:	Even	348	4	Concrete	Fair	Linear Cracking	Patching	Grass

Street : GRIFFIN STREET

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: GRIFFIN ST								
From:N MAIN ST		To: CURTISS ST						
Odd Side:	Odd	235	4	Concrete	Good	Alligator Cracking	Grass	0
Even Side:	None	0	0	None	0	0	0	0
Street : GROVE STREET								
Segment: GROVE ST-01								
From:PARK AVE		To: MAY AVE						
Odd Side:	Odd	355	4	Mix	Fair	Patching	0	0
Even Side:	Even	355	4	Concrete	Fair	Patching	Depressions	Alligator Cracking
Segment: GROVE ST-02								
From:MAY AVE		To: WALNUT ST						
Odd Side:	Odd	217	4	Concrete	Replace	Alligator Cracking	Lifting	Depressions
Even Side:	Even	289	4	Concrete	Excellent	Grass	0	0
Segment: GROVE ST-03								
From:WALNUT ST		To: WOODLAWN AVE						
Odd Side:	Odd	327	4	Concrete	Poor	Lifting	Tree Roots	Linear Cracking
Even Side:	Even	327	4	Concrete	Poor	Patching	Alligator Cracking	Depressions
Segment: GROVE ST-04								
From:WOODLAWN AVE		To: HILLSIDE AVE						
Odd Side:	Odd	371	4	Concrete	Fair	Alligator Cracking	Depressions	0
Even Side:	Even	371	4	Mix	Good	Linear Cracking	Depressions	0
Street : HARD STREET								
Segment: HARD ST								
From:FAIRCHILD ST		To: SPENCER ST						
Odd Side:	Odd	349	4	Concrete	Good	Lifting	Linear Cracking	0
Even Side:	Even	582	4	Concrete	Fair	Patching	Linear Cracking	Depressions
Street : HICKORY ROAD								
Segment: HICKORY RD-01								

	Exists	Length	Width	Material	Condition	Major Issues				
From:HIGH ST		To: BURITT PL								
Odd Side:	None	0	0	None	0	0	0	0		
Even Side:	Even	63	4	Concrete	Excellent	Linear Cracking	0	0		
Street : HIGH STREET										
Segment: HIGH ST-06										
From:CALVINST		To: OAK ST								
Odd Side:	None	0	0	None	0	0	0	0		
Even Side:	Even	844	4	Concrete	Excellent	Linear Cracking	0	0		
Segment: HIGH ST-07										
From:OAK ST		To: HILL ST								
Odd Side:	Odd	508	4	Mix	Replace	Linear Cracking	Alligator Cracking	Depressions		
Even Side:	Even	508	4	Concrete	Excellent	Linear Cracking	0	0		
Segment: HIGH ST-08										
From:HILL ST		To: MAPLE TER								
Odd Side:	Odd	325	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions		
Even Side:	None	0	0	None	0	0	0	0		
Segment: HIGH ST-09										
From:MAY ST		To: CARROLL ST								
Odd Side:	None	0	0	None	0	0	0	0		
Even Side:	Even	833	4	Mix	Poor	Patching	Linear Cracking	Alligator Cracking		
Segment: HIGH ST-10										
From:CARROLL ST		To: HILL ST								
Odd Side:	None	0	0	None	0	0	0	0		
Even Side:	Even	169	4	Concrete	Good	Linear Cracking	Grass	0		
Segment: HIGH ST-11										
From:HILL ST		To: HICKORY RD								
Odd Side:	Odd	352	4	Concrete	Poor	Patching	Depressions	Alligator Cracking		
Even Side:	Even	352	4	Mix	Excellent	Grass	0	0		
Segment: HIGH ST-12										

	Exists	Length	Width	Material	Condition	Major Issues		
From: HICKORY RD	To: WOODLAND ST							
Odd Side:	Odd	383	4	Concrete	Poor	Patching	Lifting	Depressions
Even Side:	Even	383	4	Concrete	Good	Alligator Cracking	Linear Cracking	0

Segment: HIGH ST-13

From: WOODLAND ST	To: S MAIN ST							
Odd Side:	Odd	1,502	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	1,502	4	Mix	Fair	Alligator Cracking	Linear Cracking	Patching

Street : HIGHLAND AVENUE

Segment: HIGHLAND AVE-01

From: HOADLEY ST	To: GALPIN ST							
Odd Side:	Odd	451	4	Concrete	Replace	Patching	Linear Cracking	Alligator Cracking
Even Side:	Even	451	4	Concrete	Poor	Linear Cracking	Patching	Alligator Cracking

Segment: HIGHLAND AVE-02

From: GALPIN ST	To: BEEBE ST							
Odd Side:	Odd	250	4	Mix	Fair	Linear Cracking	Alligator Cracking	0
Even Side:	Even	250	4	Mix	Poor	Alligator Cracking	Linear Cracking	Depressions

Segment: HIGHLAND AVE-03

From: BEEBE ST	To: DUNN AVE							
Odd Side:	Odd	343	5	Mix	Fair	Linear Cracking	Patching	0
Even Side:	Even	343	5	Mix	Poor	Linear Cracking	Patching	Alligator Cracking

Segment: HIGHLAND AVE-04

From: DUNN AVE	To: HIGHLAND CIR							
Odd Side:	Odd	551	4	Mix	Poor	Linear Cracking	Alligator Cracking	0
Even Side:	Even	551	4	Mix	Fair	Alligator Cracking	Linear Cracking	Patching

Segment: HIGHLAND AVE-05

From: HIGHLAND CIR	To: WALNUT ST							
Odd Side:	Odd	121	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	121	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Patching

Street : HILL STREET

Segment: HILL ST-02

	Exists	Length	Width	Material	Condition	Major Issues		
From:FAIRLAWN ST	To: CULVER ST							
Odd Side:	Odd	110	4	Concrete	Poor	Depressions	Linear Cracking	Alligator Cracking
Even Side:	Even	274	4	Mix	Fair	Grass	Lifting	Linear Cracking

Segment: HILL ST-03

From:MAY ST	To: FAIRLAWN ST							
Odd Side:	Odd	237	4	Mix	Fair	Depressions	Linear Cracking	Lifting
Even Side:	Even	296	4	Concrete	Fair	Depressions	Linear Cracking	Lifting

Street : HILLCREST AVENUE

Segment: HILLCREST AVE-01

From:FAIRLAWN ST	To: MAY ST							
Odd Side:	Odd	288	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	288	4	Concrete	Good	Grass	Linear Cracking	0

Segment: HILLCREST AVE-02

From:CULVER ST	To: FAIRLAWN ST							
Odd Side:	Odd	234	4	Concrete	Good	Grass	Lifting	0
Even Side:	Even	234	4	Concrete	Excellent	Grass	0	0

Street : HILLSIDE AVENUE

Segment: HILLSIDE AVE-01

From:FIELD ST	To: PARK AVE							
Odd Side:	Odd	388	4	Concrete	Fair	Lifting	Linear Cracking	0
Even Side:	Even	233	4	Concrete	Fair	Depressions	Linear Cracking	0

Segment: HILLSIDE AVE-02

From:PARK AVE	To: BUCKINGHAM ST							
Odd Side:	Odd	530	4	Concrete	Good	Lifting	0	0
Even Side:	Even	530	4	Concrete	Fair	Lifting	Alligator Cracking	Grass

Segment: HILLSIDE AVE-03

From:BUCKINGHAM ST	To: JUDD ST							
Odd Side:	Odd	989	3	Concrete	Good	Lifting	Linear Cracking	0
Even Side:	Even	989	3	Concrete	Fair	Depressions	Lifting	Linear Cracking

Segment: HILLSIDE AVE-04

	Exists	Length	Width	Material	Condition	Major Issues			
From:JUDD ST		To: BRADBURY ST							
Odd Side:	Odd	385	3	Concrete	Good	Lifting	Over Hanging Tree	0	
Even Side:	Even	406	3	Concrete	Good	Lifting	0	0	
Segment: HILLSIDE AVE-05									
From:BRADBURY ST		To: SALEM ST							
Odd Side:	Odd	257	4	Concrete	Fair	Patching	Linear Cracking	Depressions	
Even Side:	Even	257	4	Concrete	Fair	Depressions	Alligator Cracking	Linear Cracking	
Segment: HILLSIDE AVE-06									
From:SALEM ST		To: GROVE ST							
Odd Side:	Odd	647	4	Concrete	Fair	Lifting	Linear Cracking	Patching	
Even Side:	Even	647	4	Mix	Poor	Linear Cracking	Grass	Grass	
Segment: HILLSIDE AVE-07									
From:GROVE ST		To: ROCKWELL AVE							
Odd Side:	Odd	217	4	Concrete	Fair	Patching	Alligator Cracking	Depressions	
Even Side:	Even	217	4	Concrete	Good	Grass	Linear Cracking	0	
Segment: HILLSIDE AVE-08									
From:ROCKWELL AVE		To: MILLVILLE AVE							
Odd Side:	Odd	585	4	Concrete	Fair	Lifting	Alligator Cracking	Linear Cracking	
Even Side:	Even	585	4	Concrete	Replace	Patching	Depressions	Alligator Cracking	
Segment: HILLSIDE AVE-09									
From:MILLVILLE AVE		To: SWEENEY ST							
Odd Side:	Odd	364	4	Concrete	Good	Linear Cracking	Patching	0	
Even Side:	Even	364	4	Mix	Good	Linear Cracking	0	0	
Segment: HILLSIDE AVE-10									
From:SWEENEY ST		To: ELMWOOD ST							
Odd Side:	Odd	395	4	Concrete	Poor	Patching	Depressions	Lifting	
Even Side:	Even	395	4	Concrete	Fair	Depressions	Alligator Cracking	Linear Cracking	
Segment: HILLSIDE AVE-11									
From:ELMWOOD ST		To: TERRACE AVE							
Odd Side:	Odd	196	4	Concrete	Poor	Lifting	Depressions	Grass	
Even Side:	Even	196	4	Concrete	Excellent	0	0	0	

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: HILLSIDE AVE-12								
From:MEADOW ST		To: PAVEMENT CHANGE						
Odd Side:	Odd	826	4	Concrete	0	Linear Cracking	Grass	0
Even Side:	Even	184	4	Concrete	Fair	Depressions	Linear Cracking	0

Segment: HILLSIDE AVE-13								
From:PAVEMENT CHANGE		To: FAIRVIEW AVE						
Odd Side:	Odd	250	4	Mix	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	250	4	Concrete	Excellent	0	0	0

Street : HOADLEY STREET

Segment: HOADLEY ST-01								
From:RUBBER AVE		To: AETNA ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	310	4	Asphalt	Good	Linear Cracking	0	0

Segment: HOADLEY ST-02								
From:AETNA ST		To: HOADLEY TER						
Odd Side:	Odd	397	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: HOADLEY ST-03								
From:HOADLEY TER		To: MARSHALL AVE						
Odd Side:	Odd	348	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: HOADLEY ST-04								
From:MARSHALL AVE		To: WEST ST						
Odd Side:	Odd	234	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: HOADLEY ST-05								
From:WEST ST		To: HIGHLAND AVE						
Odd Side:	Odd	236	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: HOADLEY ST-06								
-------------------------------	--	--	--	--	--	--	--	--

	Exists	Length	Width	Material	Condition	Major Issues		
From: HIGHLAND AVE	To: SUMMIT RD							
Odd Side:	Odd	498	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: HOADLEY ST-07

From: SUMMIT RD	To: MILLVILLE AVE							
Odd Side:	Odd	228	4	Concrete	Good	Patching	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : HOMESTEAD AVENUE

Segment: HOMESTEAD AVE-01

From: HIGH ST	To: CULVER CT							
Odd Side:	Odd	193	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0

Segment: HOMESTEAD AVE-02

From: CULVER CT	To: CULVER ST							
Odd Side:	Odd	501	4	Concrete	Fair	Patching	Linear Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0

Segment: HOMESTEAD AVE-03

From: CULVER ST	To: DEAD END							
Odd Side:	Odd	112	4	Concrete	Poor	Lifting	Linear Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0

Street : HOPKINS HILL ROAD

Segment: HOPKINS HILL RD

From: MULBERRY ST	To: CUL DE SAC							
Odd Side:	Odd	778	4	Concrete	Good	Grass	Linear Cracking	Lifting
Even Side:	Even	778	4	Concrete	Fair	Lifting	Grass	0

Street : HOTCHKISS STREET

Segment: HOTCHKISS ST

From: S MAIN ST	To: DEAD END							
Odd Side:	Odd	482	4	Mix	Fair	Linear Cracking	Grass	0
Even Side:	Even	643	4	Mix	Fair	Patching	Alligator Cracking	Depressions

	Exists	Length	Width	Material	Condition	Major Issues		
Street : IDA STREET								
Segment: IDA ST								
From:SPENCER ST		To: IRVING ST						
Odd Side:	Odd	298	4	Concrete	Fair	Tree Roots	Lifting	0
Even Side:	Even	298	4	Concrete	Excellent	0	0	0

Street : IRVING STREET

Segment: IRVING ST-01

From:SPENCER ST		To: IDA ST						
Odd Side:	Odd	696	3	Asphalt	Fair	Tree Roots	Depressions	0
Even Side:	Even	696	3	Asphalt	Fair	Linear Cracking	Alligator Cracking	Depressions

Segment: IRVING ST-02

From:IDA ST		To: SPENCER ST						
Odd Side:	Odd	856	4	Concrete	Poor	Depressions	Lifting	Alligator Cracking
Even Side:	Even	856	4	Concrete	Fair	Depressions	Lifting	Linear Cracking

Street : JONES ROAD

Segment: JONES RD-02

From:WEBB RD		To: STONE FENCE RD						
Odd Side:	Odd	386	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : JUDD STREET

Segment: JUDD ST

From:HILLSIDE AVE		To: BUCKINGHAM ST						
Odd Side:	Odd	352	4	Concrete	Good	Lifting	0	0
Even Side:	Even	352	4	Concrete	Good	Lifting	0	0

Street : LAUREL AVENUE

Segment: LAUREL AVE

From:NEW HAVEN RD		To: MARJORIE ST						
Odd Side:	Odd	301	4	Concrete	Fair	Linear Cracking	Grass	Lifting
Even Side:	Even	452	4	Concrete	Good	Linear Cracking	Grass	0

	Exists	Length	Width	Material	Condition	Major Issues		
Street : LEWIS CIRCLE								
Segment: LEWIS CIR								
From:SPENCER ST		To: CUL DE SAC						
Odd Side:	Odd	691	4	Concrete	Fair	Lifting	0	0
Even Side:	Even	691	4	Concrete	Excellent	Lifting	0	0
Street : LEWIS STREET								
Segment: LEWIS ST-01								
From:SCOTT ST		To: NIXON AVE						
Odd Side:	Odd	247	4	Mix	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	247	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Segment: LEWIS ST-02								
From:NIXON AVE		To: MANNERS AVE						
Odd Side:	Odd	191	4	Concrete	Replace	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	191	4	Mix	Fair	Depressions	Linear Cracking	0
Segment: LEWIS ST-03								
From:MANNERS AVE		To: OLIVE ST						
Odd Side:	Odd	482	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	482	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Patching
Segment: LEWIS ST-04								
From:OLIVE ST		To: FAIRCHILD ST						
Odd Side:	Odd	51	4	Concrete	Excellent	0	0	0
Even Side:	Even	506	4	Asphalt	Good	Linear Cracking	Grass	0
Segment: LEWIS ST-05								
From:FAIRCHILD ST		To: SPENCER ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	258	4	Asphalt	Good	Grass	Linear Cracking	0
Segment: LEWIS ST-06								
From:SPENCERS ST		To: SHARON AVE						
Odd Side:	Odd	352	3	Asphalt	Fair	Tree Roots	Linear Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0

	Exists	Length	Width	Material	Condition	Major Issues		
Street : LINDEN STREET								
Segment: LINDEN ST-01								
From:N MAIN ST		To: CURTISS ST						
Odd Side:	Odd	227	4	Mix	Excellent	0	0	0
Even Side:	Even	91	3	Concrete	Excellent	0	0	0

Street : LONGWOOD DRIVE								
Segment: LONGWOOD DR-02								
From:WARM EARTH RD		To: CUL DE SAC						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	76	4	Asphalt	Poor	Depressions	Alligator Cracking	Grass

Street : LYNN CIRCLE								
Segment: LYNN CIR								
From:DEERLING LN		To: CUL DE SAC						
Odd Side:	Odd	153	4	Asphalt	Poor	Linear Cracking	Depressions	Alligator Cracking
Even Side:	Even	153	4	Concrete	Fair	Grass	Tree Roots	Lifting

Street : LYNN ROAD								
Segment: LYNN RD								
From:MOORE AVE		To: DEAD END						
Odd Side:	Odd	124	4	Concrete	Fair	Linear Cracking	Lifting	0
Even Side:	None	0	0	None	0	0	0	0

Street : MALGARI COURT								
Segment: MALGARI CT								
From:FAIRCHILD ST		To: DEAD END						
Odd Side:	Odd	238	3	Concrete	Fair	Lifting	Linear Cracking	Alligator Cracking
Even Side:	Even	143	4	Concrete	Fair	Lifting	Linear Cracking	Grass

Street : MANNERS AVENUE								
Segment: MANNERS AVE-02								

	Exists	Length	Width	Material	Condition	Major Issues		
From:RUSSELL ST	To: THERESA ST							
Odd Side:	Odd	282	4	Asphalt	Fair	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	339	4	Mix	Fair	Linear Cracking	Alligator Cracking	Depressions

Street : MAPLE HILL ROAD

Segment: MAPLE HILL RD-09

From:INWOOD DR	To: OLDE FARM LN							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	257	4	Concrete	Excellent	Linear Cracking	Grass	0

Segment: MAPLE HILL RD-10

From:OLD FARM LN	To: ARBOR AVE							
Odd Side:	Odd	557	4	Asphalt	0	Linear Cracking	Grass	0
Even Side:	None	0	0	None	0	0	0	0

Segment: MAPLE HILL RD-12

From:MULBERRY ST	To: VICTORIA LN							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	847	4	Concrete	Excellent	Linear Cracking	0	0

Street : MAPLE STREET

Segment: MAPLE ST-01

From:CHURCH ST	To: OLD FIREHOUSE RD							
Odd Side:	Odd	250	6	Concrete	Good	Patching	0	0
Even Side:	Even	250	6	Concrete	Excellent	0	0	0

Segment: MAPLE ST-02

From:OLD FIREHOUSE RD	To: WATER ST							
Odd Side:	Odd	400	6	Concrete	Excellent	0	0	0
Even Side:	Even	400	5	Concrete	Replace	Depressions	Alligator Cracking	Grass

Segment: MAPLE ST-03

From:WATER ST	To: OAK ST							
Odd Side:	Odd	391	6	Concrete	Excellent	0	0	0
Even Side:	Even	391	6	Concrete	Excellent	Depressions	0	0

Segment: MAPLE ST-04

	Exists	Length	Width	Material	Condition	Major Issues		
From:OAK ST	To: CENTRAL AVE							
Odd Side:	Odd	155	4	Concrete	Excellent	0	0	0
Even Side:	Even	62	4	Concrete	Excellent	0	0	0

Segment: MAPLE ST-05

From:CENTRAL AVE	To: CARROLL ST							
Odd Side:	Odd	231	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	231	6	Concrete	Excellent	Grass	0	0

Segment: MAPLE ST-06

From:CARROLL ST	To: MAPLE TER							
Odd Side:	Odd	245	4	Concrete	Fair	Patching	Linear Cracking	Depressions
Even Side:	Even	245	4	Concrete	Fair	Patching	Linear Cracking	Depressions

Segment: MAPLE ST-07

From:MAPLE TER	To: HILL ST							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	126	4	Mix	Excellent	0	0	0

Street : MAPLE TERRACE

Segment: MAPLE TER

From:MAPLE ST	To: MAY ST							
Odd Side:	Odd	312	4	Mix	Fair	Linear Cracking	Patching	Alligator Cracking
Even Side:	None	0	0	None	0	0	0	0

Street : MARJORIE STREET

Segment: MARJORIE ST-01

From:HAZEL AVE	To: GENERAL DALTON DR							
Odd Side:	Odd	130	4	Concrete	Poor	Depressions	Linear Cracking	Alligator Cracking
Even Side:	None	0	0	None	0	0	0	0

Segment: MARJORIE ST-02

From:GENERAL DALTON DR	To: LAUREL AVE							
Odd Side:	Odd	188	4	Concrete	Replace	Depressions	Linear Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0

Segment: MARJORIE ST-03

	Exists	Length	Width	Material	Condition	Major Issues		
From:LAUREL AVE	To: GENERAL PATTON DR							
Odd Side:	Odd	125	4	Concrete	Fair	Depressions	Lifting	0
Even Side:	None	0	0	None	0	0	0	0

Street : MAY AVENUE

Segment: MAY AVE-02

From:NEW ST	To: GROVE ST							
Odd Side:	Odd	346	4	Concrete	Fair	Depressions	Linear Cracking	0
Even Side:	Even	346	4	Concrete	Fair	Tree Roots	Lifting	0

Segment: MAY AVE-03

From:GROVE ST	To: MILLVILLE AVE							
Odd Side:	Odd	816	4	Concrete	Fair	Lifting	Patching	0
Even Side:	Even	816	4	Mix	Replace	Lifting	Alligator Cracking	Patching

Street : MAY STREET

Segment: MAY ST-01

From:HIGH ST	To: HILL ST							
Odd Side:	Odd	336	4	Asphalt	Good	Linear Cracking	Depressions	0
Even Side:	Even	336	4	Mix	Fair	Linear Cracking	Alligator Cracking	Patching

Segment: MAY ST-02

From:HILL ST	To: HILLCREST AVE							
Odd Side:	Odd	161	4	Asphalt	Good	Depressions	Grass	Linear Cracking
Even Side:	Even	161	4	Concrete	Excellent	0	0	0

Segment: MAY ST-03

From:HILLCREST AVE	To: PHOENIX AVE							
Odd Side:	Odd	190	4	Asphalt	Fair	Grass	Depressions	Patching
Even Side:	Even	190	4	Concrete	Excellent	0	0	0

Segment: MAY ST-04

From:PHOENIX AVE	To: SPRUCE DR							
Odd Side:	Odd	290	4	Asphalt	Fair	Linear Cracking	Depressions	Patching
Even Side:	Even	290	4	Concrete	Excellent	0	0	0

Segment: MAY ST-16

	Exists	Length	Width	Material	Condition	Major Issues		
From:MAPLE HILL RD	To: PROSPECT TL							
Odd Side:	Odd	1,226	4	Concrete	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : MEADOW BROOK PLACE

Segment: MEADOW BROOK PL

From:CROSS ST	To: CUL DE SAC							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	538	4	Concrete	Good	Linear Cracking	Grass	0

Street : MEADOW COURT

Segment: MEADOW CT

From:CHURCH ST	To: MEADOW CT							
Odd Side:	Odd	347	4	Concrete	Good	Linear Cracking	Lifting	0
Even Side:	Even	347	4	Concrete	Good	Linear Cracking	Lifting	Patching

Street : MELBOURNE COURT

Segment: MELBOURNE CT-01

From:MELBOURNE ST	To: BROOKSIDE AVE							
Odd Side:	Odd	500	4	Asphalt	Excellent	Linear Cracking	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : MELBOURNE STREET

Segment: MELBOURNE ST-01

From:RUBBER AVE	To: MELBOURNE CT							
Odd Side:	Odd	43	4	Asphalt	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : MELISSA COURT

Segment: MELISSA CT

From:MALLANE LN	To: CUL DE SAC							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	195	4	Concrete	Good	Grass	Over Hanging Tree	0

Street : MILLVILLE AVENUE

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: MILLVILLE AVE-01								
From:FIELD ST		To: WEST HILL TER						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	115	4	Asphalt	Excellent	Grass	0	0
Segment: MILLVILLE AVE-02								
From:WEST HILL TER		To: LORANN DR						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	1,398	4	Asphalt	Good	Depressions	Linear Cracking	Grass
Segment: MILLVILLE AVE-03								
From:LORANN DR		To: PINE ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	359	4	Asphalt	Excellent	Depressions	0	0
Segment: MILLVILLE AVE-07								
From:CLEARVIEW CIR		To: N HOADLEY ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	398	4	Asphalt	Good	Grass	Linear Cracking	Depressions
Segment: MILLVILLE AVE-08								
From:N HOADLEY ST		To: FERN ST						
Odd Side:	Odd	281	4	Concrete	Fair	Linear Cracking	Depressions	Patching
Even Side:	Even	281	4	Mix	Fair	Linear Cracking	Depressions	0
Segment: MILLVILLE AVE-09								
From:FERN ST		To: QUINN ST						
Odd Side:	Odd	233	4	Concrete	Fair	Patching	Linear Cracking	Depressions
Even Side:	Even	116	4	Concrete	Good	Grass	Linear Cracking	0
Segment: MILLVILLE AVE-10								
From:QUINN ST		To: PARK AVE						
Odd Side:	Odd	355	4	Concrete	Good	Lifting	Linear Cracking	0
Even Side:	Even	213	4	Concrete	Excellent	0	0	0
Segment: MILLVILLE AVE-11								

	Exists	Length	Width	Material	Condition	Major Issues			
From: PARK AVE	To: WALNUT ST								
Odd Side:	Odd	430	4	Mix	Fair	Patching	Lifting	Alligator Cracking	
Even Side:	Even	430	4	Concrete	Excellent	0	0	0	

Segment: MILLVILLE AVE-12

From: WALNUT ST	To: WOODLAWN AVE								
Odd Side:	Odd	323	4	Concrete	Excellent	0	0	0	
Even Side:	Even	323	4	Concrete	Good	Patching	Linear Cracking	Lifting	

Segment: MILLVILLE AVE-13

From: WOODLAWN AVE	To: HILLSIDE AVE								
Odd Side:	Odd	364	4	Concrete	Excellent	0	0	0	
Even Side:	Even	364	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions	

Segment: MILLVILLE AVE-14

From: HILLSIDE AVE	To: TERRACE AVE								
Odd Side:	Odd	379	4	Concrete	Excellent	0	0	0	
Even Side:	Even	379	4	Mix	Fair	Depressions	Linear Cracking	Patching	

Street : MOORE AVENUE

Segment: MOORE AVE-01

From: CLIFF ST	To: LYNN RD								
Odd Side:	Odd	550	3	Concrete	Good	Lifting	Linear Cracking	0	
Even Side:	Even	550	3	Mix	Fair	Linear Cracking	Alligator Cracking	Patching	

Segment: MOORE AVE-02

From: LYNN RD	To: NETTLETON AVE								
Odd Side:	Odd	200	4	Concrete	Excellent	0	0	0	
Even Side:	Even	200	4	Concrete	Excellent	0	0	0	

Street : MORNING DOVE ROAD

Segment: MORNING DOVE RD-03

From: RAIN DANCE CIR	To: THISTLE DOWN LN								
Odd Side:	Odd	504	3	Asphalt	Good	Depressions	Grass	Linear Cracking	
Even Side:	None	0	0	None	0	0	0	0	

Segment: MORNING DOVE RD-04

	Exists	Length	Width	Material	Condition	Major Issues		
From: THISTLE DOWN LN	To: DEAD END							
Odd Side:	Odd	198	4	Asphalt	Good	Linear Cracking	Depressions	0
Even Side:	None	0	0	None	0	0	0	0

Street : MULBERRY STREET

Segment: MULBERRY ST-08

From: MAPLE HILL RD	To: KENT ST							
Odd Side:	Odd	304	4	Concrete	Excellent	Linear Cracking	Grass	0
Even Side:	None	0	0	None	0	0	0	0

Segment: MULBERRY ST-09

From: KENT ST	To: RUSTLING REED RD							
Odd Side:	Odd	294	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: MULBERRY ST-10

From: RUSTLING REED RD	To: DEAD END							
Odd Side:	Odd	251	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	None	0	0	None	0	0	0	0

Street : MYRTLE AVENUE

Segment: MYRTLE AVE

From: N MAIN ST	To: DEAD END							
Odd Side:	Odd	275	4	Concrete	Fair	Depressions	Grass	Linear Cracking
Even Side:	Even	275	4	Concrete	Fair	Depressions	Patching	Linear Cracking

Street : N HOADLEY STREET

Segment: N HOADLEY ST-01

From: MILLVILLE AVE	To: COTTAGE ST							
Odd Side:	Odd	549	4	Mix	Fair	Lifting	Depressions	Linear Cracking
Even Side:	Even	687	4	Mix	Fair	Patching	Lifting	Linear Cracking

Segment: N HOADLEY ST-02

From: COTTAGE ST	To: PHYLLIS DR							
Odd Side:	Odd	321	4	Concrete	Poor	Lifting	Alligator Cracking	Depressions
Even Side:	Even	267	4	Mix	Good	Linear Cracking	Grass	0

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: N HOADLEY ST-03								
From: PHYLLIS DR		To: CHESTNUT ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	82	4	Concrete	Replace	Grass	Depressions	Linear Cracking
Segment: N HOADLEY ST-04								
From: CHESTNUT ST		To: DEERING LN						
Odd Side:	Odd	338	4	Mix	Poor	Patching	Linear Cracking	Tree Roots
Even Side:	Even	338	4	Asphalt	Good	Grass	Linear Cracking	0
Segment: N HOADLEY ST-05								
From: DEERING LN		To: BIRCH LN						
Odd Side:	Odd	390	4	Mix	Fair	Linear Cracking	Grass	Depressions
Even Side:	Even	390	4	Mix	Poor	Linear Cracking	Grass	Alligator Cracking
Segment: N HOADLEY ST-06								
From: DAMSON LN		To: SURREY DR						
Odd Side:	Odd	254	4	Asphalt	Fair	Alligator Cracking	Patching	0
Even Side:	Even	254	4	Mix	Fair	Depressions	Patching	0
Segment: N HOADLEY ST-07								
From: SURREY DR		To: DAMSON LN						
Odd Side:	Odd	815	4	Mix	Fair	Lifting	Patching	0
Even Side:	Even	815	4	Mix	Poor	Linear Cracking	Alligator Cracking	Grass
Segment: N HOADLEY ST-08								
From: DAMSON LN		To: QUINN ST						
Odd Side:	Odd	433	4	Mix	Fair	Linear Cracking	Lifting	Grass
Even Side:	Even	433	4	Mix	Poor	Lifting	Depressions	Alligator Cracking
Street : N MAIN STREET								
Segment: N MAIN ST-01								
From: CALVIN ST		To: CURTISS CT						
Odd Side:	Odd	41	3	Asphalt	Fair	Patching	Linear Cracking	0
Even Side:	Even	204	4	Concrete	Excellent	0	0	0
Segment: N MAIN ST-02								

	Exists	Length	Width	Material	Condition	Major Issues				
From:CURTISS CT		To: LINDEN ST								
Odd Side:	Odd	677	3	Asphalt	Fair	Linear Cracking	Alligator Cracking	Depressions		
Even Side:	Even	677	5	Concrete	Excellent	0	0	0		
Segment: N MAIN ST-03										
From:LINDEN ST		To: GRIFFIN ST								
Odd Side:	Odd	285	3	Asphalt	Good	Patching	0	0		
Even Side:	Even	712	4	Concrete	Excellent	0	0	0		
Segment: N MAIN ST-04										
From:GRIFFIN ST		To: SMITH ST								
Odd Side:	Odd	319	4	Mix	Fair	Depressions	Linear Cracking	0		
Even Side:	Even	399	4	Concrete	Fair	Depressions	Linear Cracking	0		
Segment: N MAIN ST-05										
From:SMITH ST		To: CITY HILL ST								
Odd Side:	Odd	522	4	Mix	Excellent	0	0	0		
Even Side:	Even	522	4	Concrete	Fair	Depressions	Linear Cracking	Alligator Cracking		
Segment: N MAIN ST-06										
From:CITY HILL ST		To: PROSPECT ST								
Odd Side:	Odd	326	6	Concrete	Excellent	0	0	0		
Even Side:	Even	293	4	Concrete	Excellent	Grass	0	0		
Segment: N MAIN ST-07										
From:PROSPECT ST		To: GOLDEN CT								
Odd Side:	Odd	206	4	Mix	Good	Linear Cracking	Patching	Grass		
Even Side:	None	0	0	None	0	0	0	0		
Segment: N MAIN ST-08										
From:GOLDEN CT		To: WOOD ST								
Odd Side:	Odd	235	4	Concrete	Good	Linear Cracking	Alligator Cracking	Depressions		
Even Side:	None	0	0	None	0	0	0	0		
Segment: N MAIN ST-09										
From:WOOD ST		To: MYRTLE AVE								
Odd Side:	Odd	240	0	Concrete	Excellent	Linear Cracking	0	0		
Even Side:	None	0	0	None	0	0	0	0		

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: N MAIN ST-10								
From:MYRTLE AVE		To: WOODBINE ST						
Odd Side:	Odd	172	0	Mix	Good	Linear Cracking	Alligator Cracking	Lifting
Even Side:	None	0	0	None	0	0	0	0
Street : NETTLETON AVENUE								
Segment: NETTLETON AVE-01								
From:AETNA ST		To: MOORE AVE						
Odd Side:	Odd	458	4	Concrete	Poor	Patching	Alligator Cracking	Depressions
Even Side:	Even	367	4	Concrete	Poor	Patching	Alligator Cracking	Depressions
Segment: NETTLETON AVE-02								
From:MOORE AVE		To: TROWBRIDGE PL						
Odd Side:	Odd	199	4	Concrete	Excellent	0	0	0
Even Side:	Even	199	4	Concrete	Excellent	0	0	0
Street : NEW STREET								
Segment: NEW ST-01								
From:SALEM ST		To: HILLSIDE AVE						
Odd Side:	Odd	408	4	Concrete	Good	Patching	Linear Cracking	Grass
Even Side:	Even	408	4	Concrete	Poor	Lifting	Patching	Depressions
Segment: NEW ST-02								
From:HILLSIDE AVE		To: SVEA AVE						
Odd Side:	Odd	245	4	Mix	Fair	Patching	Lifting	Alligator Cracking
Even Side:	None	0	0	None	0	0	0	0
Segment: NEW ST-03								
From:SVEA AVE		To: WALNUT ST						
Odd Side:	Odd	350	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0
Segment: NEW ST-04								
From:WALNUT ST		To: MAY AVE						
Odd Side:	Odd	393	4	Concrete	Fair	Patching	Linear Cracking	Lifting
Even Side:	None	0	0	None	0	0	0	0

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: NEW ST-05								
From: MAY AVE		To: PARK AVE						
Odd Side:	Odd	106	3	Concrete	Good	Linear Cracking	0	0
Even Side:	Even	71	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Depressions

Street : NORTH CIRCLE

Segment: NORTH CIR

From: BROOKSIDE AVE		To: CUL DE SAC						
Odd Side:	Odd	173	4	Concrete	Poor	Lifting	Tree Roots	Depressions
Even Side:	Even	173	4	Concrete	Fair	Grass	Lifting	Tree Roots

Street : OAK STREET

Segment: OAK ST-01

From: MAPLE ST		To: HIGH ST						
Odd Side:	Odd	793	4	Mix	Poor	Depressions	Linear Cracking	Alligator Cracking
Even Side:	Even	793	4	Concrete	Fair	Linear Cracking	Alligator Cracking	0

Segment: OAK ST-02

From: HIGH ST		To: COEN ST						
Odd Side:	Odd	307	4	Concrete	Poor	Alligator Cracking	Depressions	Patching
Even Side:	Even	307	4	Concrete	Fair	Linear Cracking	Grass	Alligator Cracking

Segment: OAK ST-03

From: COEN ST		To: BRADLEY ST						
Odd Side:	Odd	108	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Lifting
Even Side:	Even	108	4	Mix	Fair	Patching	Linear Cracking	Alligator Cracking

Segment: OAK ST-04

From: BRADLEY ST		To: DEAD END						
Odd Side:	Odd	89	4	Mix	Replace	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	178	4	Mix	Poor	Patching	Depressions	Linear Cracking

Street : OLD FIREHOUSE ROAD

Segment: OLD FIREHOUSE RD

	Exists	Length	Width	Material	Condition	Major Issues		
From:MAPLE ST	To: ELM ST							
Odd Side:	Odd	1,196	4	Concrete	Excellent	Lifting	0	0
Even Side:	Even	1,196	4	Concrete	Excellent	Lifting	0	0

Street : OLDE FARM LANE

Segment: OLDE FARM LN

From:MAPLE HILL RD	To: CUL DE SAC							
Odd Side:	Odd	643	4	Concrete	Good	Grass	Lifting	0
Even Side:	Even	643	4	Concrete	Excellent	Grass	0	0

Street : OLIVE STREET

Segment: OLIVE ST-01

From:CHERRY ST	To: GORMAN ST							
Odd Side:	Odd	415	4	Concrete	Fair	Linear Cracking	Cracking	Patching
Even Side:	Even	415	4	Concrete	Fair	Linear Cracking	Cracking	Patching

Segment: OLIVE ST-02

From:GORMENT ST	To: LEWIS ST							
Odd Side:	Odd	519	4	Concrete	Fair	Linear Cracking	Grass	
Even Side:	Even	692	4	Concrete	Poor	Linear Cracking	Patching	Depressions

Street : ORCHARD STREET

Segment: ORCHARD ST-01

From:HIGH ST	To: ORCHARD TER							
Odd Side:	Odd	237	4	Concrete	Poor	Patching	Alligator Cracking	Depressions
Even Side:	Even	237	4	Mix	Fair	Linear Cracking	Alligator Cracking	Grass

Segment: ORCHARD ST-02

From:ORHCARD TER	To: N MAIN ST							
Odd Side:	Odd	503	4	Mix	Replace	Depressions	Lifting	Linear Cracking
Even Side:	Even	503	4	Mix	Good	Patching	Linear Cracking	0

Street : ORCHARD TERRACE

Segment: ORCHARD TER

	Exists	Length	Width	Material	Condition	Major Issues		
From:ORCHARD ST	To: DEAD END							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	248	4	Mix	Fair	Linear Cracking	Alligator Cracking	Patching

Street : OSBORN ROAD

Segment: OSBORN RD-03

From:D'ARCANGELO DR	To: DAVIN DR							
Odd Side:	Odd	372	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: OSBORN RD-04

From:DAVIN DR	To: CELENTANO DR							
Odd Side:	Odd	620	4	Concrete	Good	Linear Cracking	Lifting	0
Even Side:	None	0	0	None	0	0	0	0

Segment: OSBORN RD-05

From:CELENTANO DR	To: CARRIAGE DR							
Odd Side:	Odd	259	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: OSBORN RD-06

From:CARRIAGE DR	To: WISTERIA DR							
Odd Side:	Odd	594	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	356	4	Concrete	Excellent	Grass	0	0

Segment: OSBORN RD-07

From:WISTERIA DR	To: CUL DE SAC							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	476	4	Concrete	Excellent	0	0	0

Street : PARK AVENUE

Segment: PARK AVE-01

From:WALNUT TER	To: MILLVILLE AVE							
Odd Side:	Odd	921	3	Concrete	Fair	Patching	Tree Roots	Lifting
Even Side:	Even	875	3	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions

Segment: PARK AVE-02

	Exists	Length	Width	Material	Condition	Major Issues		
From: MILLVILLE AVE	To: GROVE ST							
Odd Side:	Odd	795	4	Concrete	Fair	Alligator Cracking	Depressions	Lifting
Even Side:	Even	795	4	Concrete	Fair	Lifting	Grass	Linear Cracking

Segment: PARK AVE-03

From: GROVE ST	To: NEW ST							
Odd Side:	Odd	346	4	Concrete	Good	Patching	Linear Cracking	Grass
Even Side:	Even	346	4	Mix	Fair	Grass	Lifting	Linear Cracking

Segment: PARK AVE-04

From: NEW ST	To: CHESTNUT ST							
Odd Side:	Odd	372	4	Concrete	Excellent	0	0	0
Even Side:	Even	261	4	Concrete	Good	Patching	Grass	0

Segment: PARK AVE-05

From: CHESTNUT ST	To: EAST DR							
Odd Side:	Odd	1,392	3	Concrete	Poor	Linear Cracking	Lifting	Depressions
Even Side:	None	0	0	None	0	0	0	0

Segment: PARK AVE-06

From: EAST DR	To: HILLSIDE AVE							
Odd Side:	Odd	353	4	Mix	Good	Lifting	Grass	0
Even Side:	Even	141	4	Concrete	Excellent	0	0	0

Street : PARK PLACE

Segment: PARK PL

From: CHURCH ST	To: MEADOW ST							
Odd Side:	Odd	353	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Patching
Even Side:	Even	353	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Patching

Street : PEAR TREE DRIVE

Segment: PEAR TREE DR

From: FAWN MEADOW DR	To: CUL DE SAC							
Odd Side:	Odd	614	4	Concrete	Excellent	0	0	0
Even Side:	Even	614	4	Concrete	Excellent	0	0	0

Street : PEMBROOK ROAD

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: PEMBROOK RD								
From:MAY ST		To: CUL DE SAC						
Odd Side:	Odd	618		Concrete	Excellent	Grass	0	0
Even Side:	Even	652		Concrete	Excellent	Grass	0	0

Street : PHOENIX AVENUE

Segment: PHOENIX AVE

From:MAY ST		To: JOHNSON ST						
Odd Side:	Odd	378	4	Mix	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	1,322	4	Asphalt	Good	Linear Cracking	Grass	Lifting

Street : PINE STREET

Segment: PINE ST

From:HOADLEY ST		To: MILLVILLE AVE						
Odd Side:	Odd	858	4	Mix	Good	Linear Cracking	Lifting	Grass
Even Side:	Even	1,030	5	Asphalt	Excellent	Linear Cracking	0	0

Street : PINWOOD CROSSING SOUTH

Segment: PINWOOD CROSSING SOUTH

From:SILVER BEECH DR		To: CUL DE SAC						
Odd Side:	Odd	313	4	Concrete	Excellent	0	0	0
Even Side:	Even	313	4	Concrete	Excellent	0	0	0

Street : PLEASANT VIEW STREET

Segment: PLEASANT VIEW ST

From:FAIRVIEW AVE		To: CLIFF ST						
Odd Side:	Odd	585	4	Concrete	Fair	Linear Cracking	Tree Roots	Lifting
Even Side:	Even	585	4	Concrete	Fair	Linear Cracking	Patching	Lifting

Street : POND STREET

Segment: POND ST-01

From:RUBBER AVE		To: SOUTHVIEW ST						
Odd Side:	Odd	285	4	Concrete	Poor	Patching	Grass	Linear Cracking
Even Side:	None	0	0	None	0	0	0	0

Segment: POND ST-02

	Exists	Length	Width	Material	Condition	Major Issues		
From: SOUTHVIEW ST	To: FAIRVIEW AVE							
Odd Side:	Odd	277	5	Mix	Good	Linear Cracking	Depressions	0
Even Side:	Even	46	2	Concrete	Excellent	0	0	0

Street : POND VALLEY ROAD

Segment: POND VALLEY RD

From: SILVER BEECH DR	To: CUL DE SAC							
Odd Side:	Odd	271	4	Concrete	Excellent	0	0	0
Even Side:	Even	271	4	Concrete	Excellent	0	0	0

Street : QUINN STREET

Segment: QUINN ST-01

From: FIELD ST	To: NO HOADLEY ST							
Odd Side:	Odd	376	3	Concrete	Good	Linear Cracking	Grass	0
Even Side:	Even	338	3	Concrete	Poor	Lifting	Tree Roots	Depressions

Segment: QUINN ST-02

From: N HOADLEY ST	To: QUINN ST-03							
Odd Side:	Odd	529	3	Mix	Fair	Depressions	Linear Cracking	Grass
Even Side:	Even	529	3	Concrete	Fair	Lifting	Tree Roots	0

Segment: QUINN ST-03

From: QUINN ST-02	To: SURREY DR							
Odd Side:	Odd	86	1	Concrete	Replace	Depressions	Lifting	0
Even Side:	Even	857	3	Mix	Fair	Depressions	Lifting	Grass

Segment: QUINN ST-04

From: SURREY DR	To: EAST DR							
Odd Side:	Odd	356	3	Asphalt	Replace	Tree Roots	Depressions	Alligator Cracking
Even Side:	None	0	0	None	0	0	0	0

Segment: QUINN ST-05

From: EAST DR	To: QUINN ST-02							
Odd Side:	Odd	649	3	Mix	Poor	Depressions	Linear Cracking	Grass
Even Side:	None	0	0	None	0	0	0	0

Segment: QUINN ST-06

	Exists	Length	Width	Material	Condition	Major Issues			
From: SURREY DR	To: CHESTNUT ST								
Odd Side:	Odd	1,035	3	Mix	Poor	Lifting	Tree Roots	Depressions	
Even Side:	Even	1,035	3	Mix	Fair	Lifting	Tree Roots	Patching	

Segment: QUINN ST-07

From: CHESTNUT ST	To: MILLVILLE AVE								
Odd Side:	Odd	1,495	4	Concrete	Fair	Lifting	Depressions	0	
Even Side:	Even	1,495	3	Concrete	Fair	Linear Cracking	Grass	Lifting	

Street : RADNOR AVENUE

Segment: RADNOR AVE-02

From: WILLOW LN	To: BEARDSLEY AVE								
Odd Side:	Odd	273	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Grass	
Even Side:	Even	234	4	Concrete	Poor	Alligator Cracking	Depressions	Tree Roots	

Segment: RADNOR AVE-03

From: BEARDSLEY AVE	To: SANDE AVE								
Odd Side:	Odd	336	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions	
Even Side:	Even	336	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions	

Segment: RADNOR AVE-04

From: SANDE AVE	To: WATERBURY TL								
Odd Side:	Odd	279	4	Mix	Excellent	Grass	Linear Cracking	0	
Even Side:	Even	279	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions	

Street : RAIN DANCE CIRCLE

Segment: RAIN DANCE CIR

From: MORNING DOVE CIR	To: CUL DE SAC								
Odd Side:	Odd	196	4	Asphalt	Good	Linear Cracking	Grass	Depressions	
Even Side:	None	0	0	None	0	0	0	0	

Street : ROCKWELL AVENUE

Segment: ROCKWELL AVE

From: HILLSIDE AVE	To: SALEM ST								
Odd Side:	Odd	1,052	4	Concrete	Fair	Linear Cracking	Lifting	Patching	
Even Side:	Even	1,052	4	Concrete	Poor	Patching	Alligator Cracking	Lifting	

	Exists	Length	Width	Material	Condition			Major Issues
Street : ROSEWOOD COURT								
Segment: ROSEWOOD CT								
From:APPLEWOOD LN		To: CUL DE SAC						
Odd Side:	Odd	129	4	Concrete	Excellent	0	0	0
Even Side:	Even	129	4	Concrete	Good	Grass	Linear Cracking	0
Street : RUBBER AVENUE								
Segment: RUBBER AVE-01								
From:NEUMANN ST		To: WOODRUFF AVE						
Odd Side:	Odd	1,434	4	Mix	Good	Linear Cracking	Patching	0
Even Side:	Even	179	4	Concrete	Excellent	Grass	0	0
Segment: RUBBER AVE-02								
From:WOODRUFF AVE		To: KOCZAK CT						
Odd Side:	Odd	474	3	Asphalt	Good	Linear Cracking	Depressions	0
Even Side:	None	0	0	None	0	0	0	0
Segment: RUBBER AVE-03								
From:ZOCZAK CT		To: BROOKSIDE AVE						
Odd Side:	Odd	645	4	Mix	Good	Grass	0	0
Even Side:	Even	97	4	Mix	Good	Grass	0	0
Segment: RUBBER AVE-04								
From:BROOKSIDE AVE		To: MELBOURNE ST						
Odd Side:	Odd	1,117	4	Mix	Good	Linear Cracking	Grass	Patching
Even Side:	None	0	0	None	0	0	0	0
Segment: RUBBER AVE-05								
From:MELBOURNE ST		To: EDWARD ST						
Odd Side:	Odd	1,131	4	Mix	Good	Linear Cracking	Grass	0
Even Side:	Even	113	4	Mix	Good	Grass	Linear Cracking	0
Segment: RUBBER AVE-06								
From:EDWARD ST		To: ANDREW AVE						
Odd Side:	Odd	489	4	Mix	Good	Linear Cracking	Depressions	0
Even Side:	Even	342	4	Mix	Good	Linear Cracking	Depressions	0

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: RUBBER AVE-07								
From:ANDREW AVE		To: AETNA ST						
Odd Side:	Odd	459	4	Asphalt	Good	Linear Cracking	Grass	0
Even Side:	Even	23	4	Concrete	Excellent	Grass	0	0

Segment: RUBBER AVE-08								
From:AETNA ST		To: SOUTHVIEW ST						
Odd Side:	Odd	425	4	Concrete	Fair	Grass	Linear Cracking	Alligator Cracking
Even Side:	Even	64	4	Mix	Fair	Patching	Linear Cracking	Depressions

Segment: RUBBER AVE-09								
From:SOUTHVIEW ST		To: MEADOW ST						
Odd Side:	Odd	452	4	Concrete	Good	Alligator Cracking	Linear Cracking	Grass
Even Side:	Even	452	4	Concrete	Good	Linear Cracking	Alligator Cracking	Grass

Segment: RUBBER AVE-10								
From:MEADOW ST		To: ELM ST						
Odd Side:	Odd	622	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	622	4	Concrete	Fair	Grass	Linear Cracking	Depressions

Street : RUBBER AVENUE EXTENSION

Segment: RUBBER AVE EXT-01								
From:NEUMANN ST		To: FIELD ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	535	4	Concrete	Excellent	Grass	0	0

Segment: RUBBER AVE EXT-03								
From:SOUTHWOOD APT RD		To: CROFUT RD						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	108	3	Concrete	Good	Grass	0	0

Segment: RUBBER AVE EXT-04								
From:CROFUT RD		To: BRIGHTON RD						
Odd Side:	Odd	431	4	Concrete	Excellent	Grass	0	0
Even Side:	None	0	0	None	0	0	0	0

Street : S MAIN STREET (ROUTE 63)

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: S MAIN ST (ROUTE 63)-02								
From:MAPLE ST		To: HOTCHKISS ST						
Odd Side:	Odd	759	6	Concrete	Excellent	Grass	0	0
Even Side:	Even	759	4	Asphalt	Good	Linear Cracking	Depressions	0

Street : SALEM STREET

Segment: SALEM ST-01

From:MILLVILLE AVE		To: ROCKWELL AVE						
Odd Side:	Odd	1,009	4	Mix	Replace	Patching	Tree Roots	Lifting
Even Side:	Even	151	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Lifting

Segment: SALEM ST-02

From:ROCKWELL AVE		To: NEW ST						
Odd Side:	Odd	372	4	Concrete	Poor	Depressions	Alligator Cracking	Patching
Even Side:	Even	372	4	Concrete	Replace	Alligator Cracking	Depressions	0

Street : SANDE AVENUE

Segment: SANDE AVE-01

From:PLATTS MILLS RD		To: RADNOR AVE						
Odd Side:	Odd	278	4	Mix	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	278	4	Mix	Poor	Linear Cracking	Alligator Cracking	Tree Roots

Segment: SANDE AVE-02

From:RADNOR AVE		To: WATERBURY TL						
Odd Side:	Odd	174	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Grass
Even Side:	Even	249	4	Concrete	Fair	Linear Cracking	Alligator Cracking	Depressions

Street : SCHOOL STREET

Segment: SCHOOL ST-01

From:BRIDGE ST		To: ANDERSON ST						
Odd Side:	Odd	405	4	Mix	Good	Linear Cracking	Grass	Depressions
Even Side:	Even	20	4	Concrete	Excellent	0	0	0

Segment: SCHOOL ST-02

	Exists	Length	Width	Material	Condition	Major Issues		
From:ANDERSON ST	To: SCHOOL ST EXT							
Odd Side:	Odd	836	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	125	4	Concrete	Good	Linear Cracking	0	0

Segment: SCHOOL ST-03

From:SCHOOL ST EXT	To: DEAD END							
Odd Side:	Odd	418	4	Concrete	Poor	Depressions	Lifting	Linear Cracking
Even Side:	None	0	0	None	0	0	0	0

Street : SCOTT STREET

Segment: SCOTT ST-01

From:ELM ST	To: GORMAN ST							
Odd Side:	Odd	836	4	Mix	Good	Linear Cracking	Patching	Depressions
Even Side:	Even	794	4	Mix	Excellent	Patching	Lifting	0

Segment: SCOTT ST-02

From:GORMAN ST	To: ARCH ST							
Odd Side:	Odd	243	4	Mix	Replace	Alligator Cracking	Depressions	Patching
Even Side:	Even	231	4	Asphalt	Fair	Patching	Linear Cracking	Depressions

Segment: SCOTT ST-03

From:ARCH ST	To: THERESA ST							
Odd Side:	Odd	684	4	Mix	Replace	Alligator Cracking	Depressions	Patching
Even Side:	Even	684	4	Asphalt	Replace	Alligator Cracking	Depressions	Patching

Segment: SCOTT ST-04

From:THERESA ST	To: ANDREW AVE							
Odd Side:	Odd	544	4	Mix	Replace	Linear Cracking	Depressions	Alligator Cracking
Even Side:	Even	435	4	Mix	Fair	Linear Cracking	Lifting	0

Segment: SCOTT ST-05

From:ANDREW AVE	To: MELBOURNE ST							
Odd Side:	Odd	863	4	Mix	Poor	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	690	4	Mix	Replace	Alligator Cracking	Linear Cracking	Depressions

Street : SETH DRIVE

Segment: SETH DR

	Exists	Length	Width	Material	Condition	Major Issues		
From: HIGHLAND AVE	To: CUL DE SAC							
Odd Side:	Odd	412	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	291	4	Concrete	Excellent	Grass	0	0

Street : SHARON AVENUE

Segment: SHARON AVE

From: SPENCER ST	To: LEWIS ST							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	168	4	Asphalt	Excellent	0	0	0

Street : SHERMAN STREET

Segment: SHERMAN ST-01

From: NORHT CHURCH ST	To: BEECHER ST							
Odd Side:	Odd	629	4	Concrete	Poor	Alligator Cracking	Linear Cracking	Lifting
Even Side:	Even	662	4	Concrete	Good	Lifting	Linear Cracking	0

Segment: SHERMAN ST-02

From: BEECHER ST	To: HILLSIDE AVE							
Odd Side:	Odd	352	4	Concrete	Fair	Over Hanging Tree	Lifting	0
Even Side:	Even	352	3	Concrete	Good	Lifting	0	0

Street : SIERRA RIDGE ROAD

Segment: SIERRA RIDGE RD

From: DONOVAN RD	To: CUL DE SAC							
Odd Side:	Odd	958	4	Concrete	Good	Alligator Cracking	Grass	Lifting
Even Side:	Even	958	4	Concrete	Excellent	Grass	Lifting	0

Street : SILVER BEECH DRIVE

Segment: SILVER BEECH DR-01

From: MAPLE HILL RD	To: POND VALLY RD							
Odd Side:	Odd	381	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	381	4	Concrete	Excellent	Lifting	0	0

Segment: SILVER BEECH DR-02

	Exists	Length	Width	Material	Condition	Major Issues		
From: POND VALLY RD	To: PINEWOOD CROSSING SOUTH							
Odd Side:	Odd	531	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	531	4	Concrete	Excellent	Grass	0	0

Segment: SILVER BEECH DR-03

From: PINEWOOD CROSSING SOUTH	To: CUL DE SAC							
Odd Side:	Odd	386	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	386	4	Concrete	Excellent	Grass	0	0

Street : SKYVIEW DRIVE

Segment: SKYVIEW DR-01

From: CITY BROOK RD	To: WINDVIEW DR							
Odd Side:	Odd	445	4	Concrete	Good	Grass	Lifting	0
Even Side:	Even	445	4	Concrete	Excellent	Grass	0	0

Segment: SKYVIEW DR-02

From: WINDVIEW DR	To: APPLEWOOD LN							
Odd Side:	Odd	417	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	417	4	Concrete	Excellent	Grass	0	0

Street : SMITH STREET

Segment: SMITH ST

From: N MAIN ST	To: ROUTE 8							
Odd Side:	Odd	9	4	Concrete	Good	Linear Cracking	0	0
Even Side:	Even	189	4	Concrete	Good	Linear Cracking	0	0

Street : SOUTH CIRCLE

Segment: SOUTH CIR

From: BROOKSIDE AVE	To: CUL DE SAC							
Odd Side:	None	173	4	None	Good	Patching	Grass	Lifting
Even Side:	Even	173	4	Concrete	Fair	Tree Roots	Lifting	0

Street : SPENCER STREET

Segment: SPENCER ST-01

	Exists	Length	Width	Material	Condition	Major Issues		
From:ELM ST		To: WARD ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	402	4	Concrete	Excellent	Linear Cracking	0	0
Segment: SPENCER ST-02								
From:WARD ST		To: CHERRY ST						
Odd Side:	Odd	166	4	Mix	Good	Patching	Linear Cracking	0
Even Side:	Even	414	4	Concrete	Good	Linear Cracking	Grass	0
Segment: SPENCER ST-03								
From:CHERRY ST		To: GORMAN ST						
Odd Side:	Odd	399	4	Concrete	Fair	Alligator Cracking	Depressions	Patching
Even Side:	None	0	0	None	0	0	0	0
Segment: SPENCER ST-04								
From:GORMAN ST		To: HARD ST						
Odd Side:	Odd	321	3	Asphalt	Fair	Depressions	Linear Cracking	0
Even Side:	None	0	0	None	0	0	0	0
Segment: SPENCER ST-05								
From:HARD ST		To: SHARON AVE						
Odd Side:	Odd	319	3	Asphalt	Fair	Alligator Cracking	Linear Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0
Segment: SPENCER ST-06								
From:SHARON AVE		To: LEWIS ST						
Odd Side:	Odd	532	3	Concrete	Fair	Depressions	Grass	Linear Cracking
Even Side:	None	0	0	None	0	0	0	0
Segment: SPENCER ST-07								
From:LEWIS ST		To: IRVING ST						
Odd Side:	Odd	268	3	Asphalt	Poor	Alligator Cracking	Depressions	Patching
Even Side:	Even	268	3	Asphalt	Poor	Tree Roots	Linear Cracking	Depressions
Segment: SPENCER ST-08								
From:IRVING ST		To: IDA ST						
Odd Side:	Odd	344	3	Asphalt	Replace	Linear Cracking	Tree Roots	Depressions
Even Side:	Even	344	3	Asphalt	Fair	Depressions	Alligator Cracking	Linear Cracking

	Exists	Length	Width	Material	Condition	Major Issues		
Segment: SPENCER ST-09								
From:IDA ST		To: IRVING ST						
Odd Side:	Odd	598	4	Concrete	Poor	Tree Roots	Lifting	Linear Cracking
Even Side:	Even	598	4	Concrete	Poor	Lifting	Tree Roots	Depressions

Segment: SPENCER ST-10								
From:IRVING ST		To: DEAD END						
Odd Side:	Odd	125	4	Concrete	Good	Lifting	Linear Cracking	0
Even Side:	Even	125	4	Concrete	Good	Patching	Linear Cracking	0

Street : SPRING STREET

Segment: SPRING ST-01								
From:BRIDGE ST		To: DIAMOND ST						
Odd Side:	Odd	491	4	Concrete	Fair	Linear Cracking	Patching	0
Even Side:	Even	491	4	Concrete	Good	Linear Cracking	0	0

Segment: SPRING ST-02								
From:DIAMOND ST		To: ANDERSON ST						
Odd Side:	Odd	206	4	Concrete	Fair	Patching	0	0
Even Side:	Even	206	4	Concrete	Fair	Patching	0	0

Segment: SPRING ST-03								
From:ANDERSON ST		To: DUNN LN						
Odd Side:	Odd	643	4	Concrete	Poor	Patching	Depressions	Grass
Even Side:	Even	643	4	Concrete	Fair	Patching	Depressions	Grass

Street : SURREY DRIVE

Segment: SURREY DR								
From:N HOADLEY ST		To: QUINN ST						
Odd Side:	Odd	303	4	Mix	Poor	Depressions	Tree Roots	Lifting
Even Side:	Even	303	4	Mix	Poor	Tree Roots	Lifting	Linear Cracking

Street : SVEA AVENUE

Segment: SVEA AVE								
--------------------------	--	--	--	--	--	--	--	--

	Exists	Length	Width	Material	Condition	Major Issues		
From:NEW ST	To: DEAD END							
Odd Side:	Odd	32	4	Asphalt	Fair	Linear Cracking	Depressions	0
Even Side:	Even	16	4	Asphalt	Good	Linear Cracking	0	0

Street : SWEENEY STREET

Segment: SWEENEY ST

From:WALNUT ST	To: HILLSIDE AVE							
Odd Side:	Odd	237	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Depressions
Even Side:	Even	237	4	Concrete	Fair	Linear Cracking	Patching	0

Street : SWIFT LANE

Segment: SWIFT LN

From:FAWN MEADOW DR	To: BLUEBIRD DR							
Odd Side:	Odd	152	4	Concrete	Good	0	0	0
Even Side:	Even	152	4	Concrete	Good	Grass	Over Hanging Tree	0

Street : TERRACE AVENUE

Segment: TERRACE AVE-01

From:HILLSIDE AVE	To: MILLVILLE AVE							
Odd Side:	Odd	283	4	Mix	Excellent	0	0	0
Even Side:	Even	1,130	4	Mix	Poor	Linear Cracking	Alligator Cracking	Depressions

Segment: TERRACE AVE-02

From:MILLVILLE AVE	To: SALEM ST							
Odd Side:	Odd	478	4	Mix	Good	Linear Cracking	Depressions	0
Even Side:	None	0	0	None	0	0	0	0

Segment: TERRACE AVE-03

From:SALEM ST	To: WATER ST							
Odd Side:	Odd	385	4	Concrete	Good	Grass	Linear Cracking	0
Even Side:	Even	385	4	Concrete	Good	Grass	Linear Cracking	0

Street : THISTLE DOWN LANE

Segment: THISTLE DOWN LN-03

	Exists	Length	Width	Material	Condition	Major Issues		
From: MORNING DOVE RD	To: CUL DE SAC							
Odd Side:	Odd	53	3	Asphalt	Good	Linear Cracking	Linear Cracking	0
Even Side:	None	0	0	None	0	0	0	0

Street : TIDMOUTH LANE

Segment: TIDMOUTH LN

From: UNION CITY RD	To: CUL DE SAC							
Odd Side:	Odd	538	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	323	4	Concrete	Good	Grass	Linear Cracking	0

Street : TROWBRIDGE PLACE

Segment: TROWBRIDGE PL-01

From: CLIFF ST	To: NETTLETON AVE							
Odd Side:	Odd	688	4	Concrete	Fair	Alligator Cracking	Patching	0
Even Side:	Even	688	4	Concrete	Poor	Patching	Alligator Cracking	0

Segment: TROWBRIDGE PL-02

From: NETTLETON AVE	To: GOODYEAR AVE							
Odd Side:	Odd	161	4	Concrete	Excellent	0	0	0
Even Side:	Even	161	4	Concrete	Excellent	0	0	0

Street : TYLER HILL ROAD

Segment: TYLER HILL RD

From: APPLEWOOD LN	To: CUL DE SAC							
Odd Side:	Odd	925	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	976	4	Concrete	Excellent	Grass	0	0

Street : UNION CITY ROAD

Segment: UNION CITY RD-03

From: TIDMOUTH LN	To: GAIL DR							
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	372	4	Concrete	Good	0	Linear Cracking	0

Street : WALNUT STREET

Segment: WALNUT ST-01

	Exists	Length	Width	Material	Condition	Major Issues				
From:NEW ST		To: GROVE ST								
Odd Side:	Odd	429	4	Concrete	Poor	Patching	Depressions	Alligator Cracking		
Even Side:	Even	214	4	Concrete	Good	Linear Cracking	Patching	0		
Segment: WALNUT ST-02										
From:GROVE ST		To: MILLVILLE AVE								
Odd Side:	Odd	795	4	Concrete	Poor	Patching	Lifting	Depressions		
Even Side:	Even	795	4	Concrete	Replace	Patching	Linear Cracking	Depressions		
Segment: WALNUT ST-03										
From:MILLVILLE AVE		To: SWEENEY ST								
Odd Side:	Odd	279	4	Concrete	Fair	Patching	Alligator Cracking	Depressions		
Even Side:	Even	279	4	Concrete	Poor	Alligator Cracking	Patching	Depressions		
Segment: WALNUT ST-04										
From:SWEENEY ST		To: ELMWOOD ST								
Odd Side:	Odd	537	4	Concrete	Fair	Alligator Cracking	Patching	0		
Even Side:	Even	537	4	Concrete	Fair	Lifting	Patching	Depressions		
Segment: WALNUT ST-05										
From:ELMWOOD ST		To: WALNUT TER								
Odd Side:	Odd	113	4	Concrete	Fair	Lifting	Linear Cracking	Alligator Cracking		
Even Side:	Even	113	4	Concrete	Fair	Linear Cracking	Grass	Depressions		
Segment: WALNUT ST-06										
From:WALNUT TER		To: HIGHLAND CIR								
Odd Side:	None	161	4	Concrete	Fair	Depressions	Alligator Cracking	Grass		
Even Side:	Even	161	4	Concrete	Fair	Alligator Cracking	Linear Cracking	Grass		
Segment: WALNUT ST-07										
From:HIGHLAND CIR		To: HIGHLAND AVE								
Odd Side:	Odd	121	4	Concrete	Fair	Grass	Linear Cracking	Alligator Cracking		
Even Side:	Even	121	4	Concrete	Good	Grass	Linear Cracking	0		
Segment: WALNUT ST-08										
From:HIGHLAND AVE		To: CLIFF ST								
Odd Side:	Odd	109	4	Concrete	Excellent	Linear Cracking	0	0		
Even Side:	Even	109	4	Asphalt	Fair	Depressions	Linear Cracking	Grass		

	Exists	Length	Width	Material	Condition	Major Issues		
Street : WALNUT TERRACE								
Segment: WALNUT TER								
From:WALNUT ST		To: PARK AVE						
Odd Side:	Odd	415	3	Concrete	Fair	Tree Roots	Lifting	Linear Cracking
Even Side:	Even	415	3	Concrete	Fair	Alligator Cracking	Depressions	Lifting

Street : WARD STREET

Segment: WARD ST-01

From:ELM ST		To: NEVILLE ST						
Odd Side:	Odd	537	4	Mix	Good	Linear Cracking	Grass	0
Even Side:	Even	537	4	Concrete	Replace	Patching	Depressions	Alligator Cracking

Segment: WARD ST-02

From:NEVILLE ST		To: SPENCER ST						
Odd Side:	Odd	1,408	4	Concrete	Poor	Patching	Linear Cracking	Depressions
Even Side:	Even	1,408	4	Mix	Poor	Patching	Linear Cracking	Depressions

Street : WATER STREET

Segment: WATER ST-01

From:NORTH CHURCH ST		To: MILLVILLE AVE						
Odd Side:	Odd	347	4	Mix	Good	Patching	0	0
Even Side:	None	0	0	None	0	0	0	0

Segment: WATER ST-02

From:MILLVILLE AVE		To: CEDAR ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	1,279	6	Concrete	Fair	Alligator Cracking	Depressions	Lifting

Segment: WATER ST-03

From:CEDAR ST		To: MAPLE ST						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	776	4	Mix	Fair	Patching	Linear Cracking	Grass

Street : WEST STREET

Segment: WEST ST

	Exists	Length	Width	Material	Condition		Major Issues	
From: GALPIN ST								
To: HOADLEY ST								
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	477	3	Asphalt	Poor	Depressions	Alligator Cracking	Linear Cracking

Street : WESTOVER DRIVE

Segment: WESTOVER DR-01

From: KRODEL RD								
To: GRAHAM RIDGE RD								
Odd Side:	Odd	243	4	Concrete	Good	Grass	Lifting	0
Even Side:	Even	243	4	Concrete	Excellent	Grass	0	0

Segment: WESTOVER DR-02

From: GRAHAM RIDGE RD								
To: GRAHAM RIDGE RD								
Odd Side:	Odd	538	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	538	4	Concrete	Fair	Lifting	Depressions	0

Segment: WESTOVER DR-03

From: GRAHAM RIDGE RD								
To: WEBB RD								
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	421	4	Concrete	Excellent	0	0	0

Street : WILD CHERRY DRIVE

Segment: WILD CHERRY DR

From: FAWN MEADOW DR								
To: CUL DE SAC								
Odd Side:	Odd	284	4	Concrete	Excellent	0	0	0
Even Side:	Even	284	4	Concrete	Excellent	0	0	0

Street : WILLOW LANE

Segment: WILLOW LN

From: RADNOR AVE								
To: CUL DE SAC								
Odd Side:	Odd	148	6	Asphalt	Excellent	0	0	0
Even Side:	Even	235	6	Asphalt	Fair	Linear Cracking	Alligator Cracking	Grass

Street : WINDVIEW DRIVE

Segment: WINDVIEW DR

	Exists	Length	Width	Material	Condition	Major Issues		
From:SKYVIEW DR	To: CUL DE SAC							
Odd Side:	Odd	527	4	Concrete	Good	Grass	Linear Cracking	Lifting
Even Side:	Even	527	4	Concrete	Good	Grass	Linear Cracking	Lifting

Street : WINSLOW COURT

Segment: WINSLOW CT

From:MEADOW ST	To: DEAD END							
Odd Side:	Odd	69	2	Asphalt	Good	Linear Cracking	0	0
Even Side:	Even	69	2	Concrete	Excellent	0	0	0

Street : WISTERIA DRIVE

Segment: WISTERIA DR-01

From:OSBORN RD	To: ROLLINGWOOD DR							
Odd Side:	Odd	482	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	482	4	Concrete	Good	Grass	0	0

Segment: WISTERIA DR-02

From:ROLLINGWOOD DR	To: ADRIATIC LN							
Odd Side:	Odd	1,672	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	1,672	4	Concrete	Excellent	Grass	0	0

Segment: WISTERIA DR-03

From:ADRIATIC LN	To: ROLLINGWOOD DR							
Odd Side:	Odd	981	4	Concrete	Excellent	Grass	0	0
Even Side:	Even	981	4	Concrete	Excellent	Grass	0	0

Segment: WISTERIA DR-04

From:ROLLINGWOOD DR	To: CUL DE SAC							
Odd Side:	Odd	759	4	Concrete	Excellent	0	0	0
Even Side:	Even	759	4	Concrete	Excellent	0	0	0

Street : WOOD STREET

Segment: WOOD ST

From:N MAIN ST	To: DEAD END							
Odd Side:	Odd	223	4	Concrete	Poor	Linear Cracking	Alligator Cracking	Depressions
Even Side:	Even	200	4	Mix	Poor	Linear Cracking	Alligator Cracking	0

	Exists	Length	Width	Material	Condition	Major Issues		
Street : WOODBINE STREET								
Segment: WOODBINE ST-02								
From:GEN HILL ST		To: STANLEY ST						
Odd Side:	Odd	20	3	Asphalt	Excellent	0	0	0
Even Side:	None	0	0	None	0	0	0	0
Street : WOODLAWN AVENUE								
Segment: WOODLAWN AVE								
From:GROVE ST		To: MILLVILLE AVE						
Odd Side:	Odd	795	4	Mix	Fair	Patching	Linear Cracking	Depressions
Even Side:	None	0	0	None	0	0	0	0
Street : WOODSIDE DRIVE								
Segment: WOODSIDE DR								
From:MULBERRY ST		To: CUL DE SAC						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	402	3	Asphalt	Fair	Grass	Linear Cracking	Alligator Cracking
Street : WOOSTER STREET								
Segment: WOOSTER ST-04								
From:DONOVAN RD		To: KOSKO LN						
Odd Side:	Odd	454	4	Concrete	Good	Depressions	Grass	0
Even Side:	None	0	0	None	0	0	0	0
Segment: WOOSTER ST-05								
From:KOSKO LN		To: WHITNEY PL						
Odd Side:	Odd	417	4	Concrete	Excellent	Lifting	0	0
Even Side:	None	0	0	None	0	0	0	0
Segment: WOOSTER ST-07								
From:APPLEWOOD LN		To: GLEN HOLLOW RD						
Odd Side:	None	0	0	None	0	0	0	0
Even Side:	Even	321	4	Concrete	Excellent	0	0	0

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Condition and Estimated Replacement Costs - Asphalt

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
AETNA STREET									
AETNA ST-02	GALPIN ST	BEEBE ST	Odd	31	4	Asphalt	Defer Maintenance	Excellent	\$0.00
Total Length: 31								Total Cost: \$0.00	
ANDERSON STREET									
ANDERSON ST	SCHOOL ST	SPRING ST	Even	739	4	Asphalt	10% Replacement	Good	\$4,926.67
ANDERSON ST	SCHOOL ST	SPRING ST	Odd	739	4	Asphalt	10% Replacement	Good	\$4,926.67
Total Length: 1,478								Total Cost: \$9,853.33	
ARBOR AVENUE									
ARBOR AVE-01	MAPLE HILL RD	KENT ST	Even	304	4	Asphalt	25% Replacement	Fair	\$3,377.78
ARBOR AVE-02	KENT ST	RUSTLING REED RD	Even	297	4	Asphalt	10% Replacement	Good	\$1,980.00
Total Length: 601								Total Cost: \$5,357.78	
CHERRY STREET EXTENSION									
CHERRY ST EXT-03	ANN ST	DEAD END	Even	141	4	Asphalt	100% Replacement	Replace	\$4,700.00
CHERRY ST EXT-03	ANN ST	DEAD END	Odd	70	4	Asphalt	100% Replacement	Replace	\$2,333.33
Total Length: 211								Total Cost: \$7,033.33	
CHESTNUT STREET									
CHESTNUT ST-02	FERN ST	QUINN ST	Odd	261	4	Asphalt	25% Replacement	Fair	\$2,900.00
Total Length: 261								Total Cost: \$2,900.00	
CITY HILL STREET									
CITY HILL ST-08	CITY BROOK RD	DONOVAN RD	Odd	196	2	Asphalt	100% Replacement	Replace	\$3,266.67
Total Length: 196								Total Cost: \$3,266.67	
CLARK ROAD									
CLARK RD-01	NEW HAVEN RD	VALLEY MOBILE HOME PARK	Even	643	2	Asphalt	100% Replacement	Replace	\$10,716.67
Total Length: 643								Total Cost: \$10,716.67	
CLIFF STREET									
CLIFF ST-01	AETNA ST	LE CLAIR CT	Odd	13	4	Asphalt	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
	Total Length: 13							Total Cost: \$0.00	
CURTISS STREET									
CURTISS ST-02	LINDEN ST	GRIFFIN ST	Even	708	4	Asphalt	50% Replacement	Poor	\$15,733.33
	Total Length: 708							Total Cost: \$15,733.33	
DONOVAN ROAD									
DONOVAN RD-06	DONOVAN CT	WOOSTER ST	Odd	468	4	Asphalt	Defer Maintenance	Excellent	\$0.00
	Total Length: 468							Total Cost: \$0.00	
EAGLE STREET									
EAGLE ST-01	PROSPECT ST	ENDOGEN ST	Even	31	3	Asphalt	10% Replacement	Good	\$155.00
	Total Length: 31							Total Cost: \$155.00	
EAST DRIVE									
EAST DR	PARK AVE	QUINN ST	Even	206	4	Asphalt	25% Replacement	Fair	\$2,288.89
	Total Length: 206							Total Cost: \$2,288.89	
FERN STREET									
FERN ST-01	CHESTNUT ST	COTTAGE ST	Even	166	4	Asphalt	Defer Maintenance	Excellent	\$0.00
	Total Length: 166							Total Cost: \$0.00	
HOADLEY STREET									
HOADLEY ST-01	RUBBER AVE	AETNA ST	Even	310	4	Asphalt	10% Replacement	Good	\$2,066.67
	Total Length: 310							Total Cost: \$2,066.67	
IRVING STREET									
IRVING ST-01	SPENCER ST	IDA ST	Even	696	3	Asphalt	25% Replacement	Fair	\$5,800.00
IRVING ST-01	SPENCER ST	IDA ST	Odd	696	3	Asphalt	25% Replacement	Fair	\$5,800.00
	Total Length: 1,392							Total Cost: \$11,600.00	
LEWIS STREET									
LEWIS ST-04	OLIVE ST	FAIRCHILD ST	Even	506	4	Asphalt	10% Replacement	Good	\$3,373.33
LEWIS ST-05	FAIRCHILD ST	SPENCER ST	Even	258	4	Asphalt	10% Replacement	Good	\$1,720.00
LEWIS ST-06	SPENCERS ST	SHARON AVE	Odd	352	3	Asphalt	25% Replacement	Fair	\$2,933.33
	Total Length: 1,116							Total Cost: \$8,026.67	
LONGWOOD DRIVE									
LONGWOOD DR-02	WARM EARTH RD	CUL DE SAC	Even	76	4	Asphalt	50% Replacement	Poor	\$1,688.89
	Total Length: 76							Total Cost: \$1,688.89	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
LYNN CIRCLE									
LYNN CIR	DEERLING LN	CUL DE SAC	Odd	153	4	Asphalt	50% Replacement	Poor	\$3,400.00
Total Length: 153								Total Cost: \$3,400.00	
MANNERS AVENUE									
MANNERS AVE-02	RUSSELL ST	THERESA ST	Odd	282	4	Asphalt	25% Replacement	Fair	\$3,133.33
Total Length: 282								Total Cost: \$3,133.33	
MAY STREET									
MAY ST-01	HIGH ST	HILL ST	Odd	336	4	Asphalt	10% Replacement	Good	\$2,240.00
MAY ST-02	HILL ST	HILLCREST AVE	Odd	161	4	Asphalt	10% Replacement	Good	\$1,073.33
MAY ST-03	HILLCREST AVE	PHOENIX AVE	Odd	190	4	Asphalt	25% Replacement	Fair	\$2,111.11
MAY ST-04	PHOENIX AVE	SPRUCE DR	Odd	290	4	Asphalt	25% Replacement	Fair	\$3,222.22
Total Length: 977								Total Cost: \$8,646.67	
MELBOURNE COURT									
MELBOURNE CT-01	MELBOURNE ST	BROOKSIDE AVE	Odd	500	4	Asphalt	Defer Maintenance	Excellent	\$0.00
Total Length: 500								Total Cost: \$0.00	
MELBOURNE STREET									
MELBOURNE ST-01	RUBBER AVE	MELBOURNE CT	Odd	43	4	Asphalt	Defer Maintenance	Excellent	\$0.00
Total Length: 43								Total Cost: \$0.00	
MILLVILLE AVENUE									
MILLVILLE AVE-01	FIELD ST	WEST HILL TER	Even	115	4	Asphalt	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-02	WEST HILL TER	LORANN DR	Even	1398	4	Asphalt	10% Replacement	Good	\$9,320.00
MILLVILLE AVE-03	LORANN DR	PINE ST	Even	359	4	Asphalt	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-07	CLEARVIEW CIR	N HOADLEY ST	Even	398	4	Asphalt	10% Replacement	Good	\$2,653.33
Total Length: 2,270								Total Cost: \$11,973.33	
MORNING DOVE ROAD									
MORNING DOVE RD-03	RAIN DANCE CIR	THISTLE DOWN LN	Odd	504	3	Asphalt	10% Replacement	Good	\$2,520.00
MORNING DOVE RD-04	THISTLE DOWN LN	DEAD END	Odd	198	4	Asphalt	10% Replacement	Good	\$1,320.00
Total Length: 702								Total Cost: \$3,840.00	
N HOADLEY STREET									
N HOADLEY ST-04	CHESTNUT ST	DEERING LN	Even	338	4	Asphalt	10% Replacement	Good	\$2,253.33
N HOADLEY ST-06	DAMSON LN	SURREY DR	Odd	254	4	Asphalt	25% Replacement	Fair	\$2,822.22

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 592								Total Cost: \$5,075.56	
N MAIN STREET									
N MAIN ST-01	CALVIN ST	CURTISS CT	Odd	41	3	Asphalt	25% Replacement	Fair	\$341.67
N MAIN ST-02	CURTISS CT	LINDEN ST	Odd	677	3	Asphalt	25% Replacement	Fair	\$5,641.67
N MAIN ST-03	LINDEN ST	GRIFFIN ST	Odd	285	3	Asphalt	10% Replacement	Good	\$1,425.00
Total Length: 1,003								Total Cost: \$7,408.33	
PHOENIX AVENUE									
PHOENIX AVE	MAY ST	JOHNSON ST	Even	1322	4	Asphalt	10% Replacement	Good	\$8,813.33
Total Length: 1,322								Total Cost: \$8,813.33	
PINE STREET									
PINE ST	HOADLEY ST	MILLVILLE AVE	Even	1030	5	Asphalt	Defer Maintenance	Excellent	\$0.00
Total Length: 1,030								Total Cost: \$0.00	
QUINN STREET									
QUINN ST-04	SURREY DR	EAST DR	Odd	356	3	Asphalt	100% Replacement	Replace	\$8,900.00
Total Length: 356								Total Cost: \$8,900.00	
RAIN DANCE CIRCLE									
RAIN DANCE CIR	MORNING DOVE CIR	CUL DE SAC	Odd	196	4	Asphalt	10% Replacement	Good	\$1,306.67
Total Length: 196								Total Cost: \$1,306.67	
RUBBER AVENUE									
RUBBER AVE-02	WOODRUFF AVE	KOCZAK CT	Odd	474	3	Asphalt	10% Replacement	Good	\$2,370.00
RUBBER AVE-07	ANDREW AVE	AETNA ST	Odd	459	4	Asphalt	10% Replacement	Good	\$3,060.00
Total Length: 933								Total Cost: \$5,430.00	
S MAIN STREET (ROUTE 63)									
S MAIN ST (ROUTE 63)-02	MAPLE ST	HOTCHKISS ST	Even	759	4	Asphalt	10% Replacement	Good	\$5,060.00
Total Length: 759								Total Cost: \$5,060.00	
SCOTT STREET									
SCOTT ST-02	GORMAN ST	ARCH ST	Even	231	4	Asphalt	25% Replacement	Fair	\$2,566.67
SCOTT ST-03	ARCH ST	THERESA ST	Even	684	4	Asphalt	100% Replacement	Replace	\$22,800.00
Total Length: 915								Total Cost: \$25,366.67	
SHARON AVENUE									
SHARON AVE	SPENCER ST	LEWIS ST	Even	168	4	Asphalt	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 168								Total Cost: \$0.00	
SPENCER STREET									
SPENCER ST-04	GORMAN ST	HARD ST	Odd	321	3	Asphalt	25% Replacement	Fair	\$2,675.00
SPENCER ST-05	HARD ST	SHARON AVE	Odd	319	3	Asphalt	25% Replacement	Fair	\$2,658.33
SPENCER ST-07	LEWIS ST	IRVING ST	Even	268	3	Asphalt	50% Replacement	Poor	\$4,466.67
SPENCER ST-07	LEWIS ST	IRVING ST	Odd	268	3	Asphalt	50% Replacement	Poor	\$4,466.67
SPENCER ST-08	IRVING ST	IDA ST	Even	344	3	Asphalt	25% Replacement	Fair	\$2,866.67
SPENCER ST-08	IRVING ST	IDA ST	Odd	344	3	Asphalt	100% Replacement	Replace	\$8,600.00
Total Length: 1,864								Total Cost: \$25,733.33	
SVEA AVENUE									
SVEA AVE	NEW ST	DEAD END	Even	16	4	Asphalt	10% Replacement	Good	\$106.67
SVEA AVE	NEW ST	DEAD END	Odd	32	4	Asphalt	25% Replacement	Fair	\$355.56
Total Length: 48								Total Cost: \$462.22	
THISTLE DOWN LANE									
THISTLE DOWN LN-03	MORNING DOVE RD	CUL DE SAC	Odd	53	3	Asphalt	10% Replacement	Good	\$265.00
Total Length: 53								Total Cost: \$265.00	
WALNUT STREET									
WALNUT ST-08	HIGHLAND AVE	CLIFF ST	Even	109	4	Asphalt	25% Replacement	Fair	\$1,211.11
Total Length: 109								Total Cost: \$1,211.11	
WEST STREET									
WEST ST	GALPIN ST	HOADLEY ST	Even	477	3	Asphalt	50% Replacement	Poor	\$7,950.00
Total Length: 477								Total Cost: \$7,950.00	
WILLOW LANE									
WILLOW LN	RADNOR AVE	CUL DE SAC	Even	235	6	Asphalt	25% Replacement	Fair	\$3,916.67
WILLOW LN	RADNOR AVE	CUL DE SAC	Odd	148	6	Asphalt	Defer Maintenance	Excellent	\$0.00
Total Length: 383								Total Cost: \$3,916.67	
WINSLOW COURT									
WINSLOW CT	MEADOW ST	DEAD END	Odd	69	2	Asphalt	10% Replacement	Good	\$230.00
Total Length: 69								Total Cost: \$230.00	
WOODBINE STREET									
WOODBINE ST-02	GEN HILL ST	STANLEY ST	Odd	20	3	Asphalt	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 20								Total Cost: \$0.00	
WOODSIDE DRIVE									
WOODSIDE DR	MULBERRY ST	CUL DE SAC	Even	402	3	Asphalt	25% Replacement	Fair	\$3,350.00
Total Length: 402								Total Cost: \$3,350.00	

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Condition and Estimated Replacement Costs - Concrete

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
ACUSHNET STREET									
ACUSHNET ST-01	GOLDEN HILL ST	STANLEY ST	Odd	95	2	Concrete	100% Replacement	Replace	\$3,166.67
Total Length: 95								Total Cost:	\$3,166.67
ADRIATIC LANE									
ADRIATIC LN-01	VILLAGE CIR	D'ARCANGELO DR	Even	147	4	Concrete	Defer Maintenance	Excellent	\$0.00
ADRIATIC LN-01	VILLAGE CIR	D'ARCANGELO DR	Odd	147	4	Concrete	Defer Maintenance	Excellent	\$0.00
ADRIATIC LN-02	D'ARCANGELO DR	WISTERIA DR	Even	149	4	Concrete	Defer Maintenance	Excellent	\$0.00
ADRIATIC LN-02	D'ARCANGELO DR	WISTERIA DR	Odd	149	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 592								Total Cost:	\$0.00
AETNA STREET									
AETNA ST-02	GALPIN ST	BEEBE ST	Even	21	2	Concrete	25% Replacement	Fair	\$233.33
AETNA ST-03	BEEBE ST	EDWARD ST	Even	18	4	Concrete	Defer Maintenance	Excellent	\$0.00
AETNA ST-04	EDWARD ST	GOODYEAR AVE	Even	120	4	Concrete	10% Replacement	Good	\$800.00
AETNA ST-05	GOODYEAR AVE	NETTLETON AVE	Even	260	4	Concrete	25% Replacement	Fair	\$5,777.78
AETNA ST-05	GOODYEAR AVE	NETTLETON AVE	Odd	260	4	Concrete	25% Replacement	Fair	\$5,777.78
AETNA ST-06	NETTLETON AVE	CLIFF ST	Even	629	4	Concrete	25% Replacement	Fair	\$13,977.78
AETNA ST-06	NETTLETON AVE	CLIFF ST	Odd	629	4	Concrete	50% Replacement	Poor	\$20,966.67
AETNA ST-07	CLIFF ST	AETNA PL	Even	216	4	Concrete	50% Replacement	Poor	\$7,200.00
AETNA ST-07	CLIFF ST	AETNA PL	Odd	216	4	Concrete	50% Replacement	Poor	\$7,200.00
AETNA ST-08	AETNA PL	RUBBER AVE	Even	243	4	Concrete	50% Replacement	Poor	\$8,100.00
AETNA ST-08	AETNA PL	RUBBER AVE	Odd	243	4	Concrete	100% Replacement	Replace	\$16,200.00
Total Length: 2,855								Total Cost:	\$86,233.33
ANDREW AVENUE									
ANDREW AVE-01	RUBBER AVE	SCOTT ST	Even	38	4	Concrete	Defer Maintenance	Excellent	\$0.00
ANDREW AVE-01	RUBBER AVE	SCOTT ST	Odd	76	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 114								Total Cost:	\$0.00
APPLE BLOSSOM DRIVE									
APPLE BLOSSOM DR	FAWN MEADOW DR	CUL DE SAC	Even	641	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLE BLOSSOM DR	FAWN MEADOW DR	CUL DE SAC	Odd	641	4	Concrete	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 1,282								Total Cost: \$0.00	
APPLEWOOD LANE									
APPLEWOOD LN-01	WOOSTER ST	TYLER HILL RD	Even	1039	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-01	WOOSTER ST	TYLER HILL RD	Odd	1039	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-02	TYLER HILL RD	SKYVIEW DR	Even	1147	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-02	TYLER HILL RD	SKYVIEW DR	Odd	1147	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-03	SKYVIEW DR	DONOVAN RD	Even	521	4	Concrete	10% Replacement	Good	\$3,473.33
APPLEWOOD LN-03	SKYVIEW DR	DONOVAN RD	Odd	695	4	Concrete	10% Replacement	Good	\$4,633.33
APPLEWOOD LN-04	DONOVAN RD	ROSEWOOD CT	Even	350	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-04	DONOVAN RD	ROSEWOOD CT	Odd	350	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-05	ROSEWOOD CT	COUNTRY HOLLOW RD	Even	537	4	Concrete	Defer Maintenance	Excellent	\$0.00
APPLEWOOD LN-05	ROSEWOOD CT	COUNTRY HOLLOW RD	Odd	537	4	Concrete	10% Replacement	Good	\$3,580.00
Total Length: 7,362								Total Cost: \$11,686.67	
ARCH STREET									
ARCH ST	SCOTT ST	RUBBER AVE	Odd	184	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 184								Total Cost: \$0.00	
AUBURN STREET									
AUBURN ST-07	ALBION ST	CUL DE SAC	Even	508	4	Concrete	Defer Maintenance	Excellent	\$0.00
AUBURN ST-07	ALBION ST	CUL DE SAC	Odd	305	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 813								Total Cost: \$0.00	
BEARDSLEY AVENUE									
BEARDSLEY AVE-01	PLATTS MILLS RD	RADNOR AVE	Even	288	4	Concrete	25% Replacement	Fair	\$6,400.00
BEARDSLEY AVE-01	PLATTS MILLS RD	RADNOR AVE	Odd	288	4	Concrete	10% Replacement	Good	\$1,920.00
BEARDSLEY AVE-02	RADNOR AVE	WATERBURY TL	Even	649	4	Concrete	50% Replacement	Poor	\$21,633.33
BEARDSLEY AVE-02	RADNOR AVE	WATERBURY TL	Odd	584	4	Concrete	25% Replacement	Fair	\$12,977.78
Total Length: 1,809								Total Cost: \$42,931.11	
BEEBE STREET									
BEEBE ST	AETNA ST	HIGHLAND AVE	Even	986	4	Concrete	50% Replacement	Poor	\$32,866.67
Total Length: 986								Total Cost: \$32,866.67	
BEECHER STREET									
BEECHER ST	BUCKINGHAM ST	SHERMAN ST	Even	573	4	Concrete	10% Replacement	Good	\$3,820.00
BEECHER ST	BUCKINGHAM ST	SHERMAN ST	Odd	573	4	Concrete	25% Replacement	Fair	\$12,733.33
Total Length: 1,146								Total Cost: \$16,553.33	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
BRADLEY STREET									
BRADLEY ST	OAK ST	HILL ST	Even	555	4	Concrete	50% Replacement	Poor	\$18,500.00
Total Length: 555								Total Cost:	\$18,500.00
BRENNAN STREET									
BRENNAN ST-01	BRIDGE ST	CROWN ST	Even	21	4	Concrete	Defer Maintenance	Excellent	\$0.00
BRENNAN ST-01	BRIDGE ST	CROWN ST	Odd	429	4	Concrete	Defer Maintenance	Excellent	\$0.00
BRENNAN ST-02	CROWN ST	SPRING ST	Odd	28	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 478								Total Cost:	\$0.00
BROOKSIDE AVENUE									
BROOKSIDE AVE-01	RUBBER AVE	NORTH CIR	Even	555	4	Concrete	10% Replacement	Good	\$3,700.00
BROOKSIDE AVE-01	RUBBER AVE	NORTH CIR	Odd	555	4	Concrete	50% Replacement	Poor	\$18,500.00
BROOKSIDE AVE-02	NORTH CIR	SOUTH CIR	Even	288	4	Concrete	25% Replacement	Fair	\$6,400.00
BROOKSIDE AVE-03	SOUTH CIR	MELBOURNE CT	Odd	280	4	Concrete	50% Replacement	Poor	\$9,333.33
Total Length: 1,678								Total Cost:	\$37,933.33
BUCKINGHAM STREET									
BUCKINGHAM ST-01	HILLSIDE AVE	BEECHER ST	Even	389	4	Concrete	10% Replacement	Good	\$2,593.33
BUCKINGHAM ST-01	HILLSIDE AVE	BEECHER ST	Odd	389	4	Concrete	10% Replacement	Good	\$2,593.33
BUCKINGHAM ST-02	BEECHER ST	JUDD ST	Even	373	4	Concrete	25% Replacement	Fair	\$8,288.89
BUCKINGHAM ST-02	BEECHER ST	JUDD ST	Odd	373	4	Concrete	25% Replacement	Fair	\$8,288.89
BUCKINGHAM ST-03	JUDD ST	NORTH CHURCH ST	Even	279	4	Concrete	10% Replacement	Good	\$1,860.00
BUCKINGHAM ST-03	JUDD ST	NORTH CHURCH ST	Odd	279	4	Concrete	10% Replacement	Good	\$1,860.00
Total Length: 2,082								Total Cost:	\$25,484.44
CALVIN STREET									
CALVIN ST	N MAIN ST	HIGH ST	Odd	659	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 659								Total Cost:	\$0.00
CAROLYN CIRCLE									
CAROLYN CIR	PICTURE LN	PICTURE LN	Even	364	3	Concrete	25% Replacement	Fair	\$6,066.67
CAROLYN CIR	PICTURE LN	PICTURE LN	Odd	364	3	Concrete	25% Replacement	Fair	\$6,066.67
Total Length: 728								Total Cost:	\$12,133.33
CARROLL COURT									
CARROLL CT	CARROLL ST	DEAD END	Even	338	3	Concrete	25% Replacement	Fair	\$5,633.33
CARROLL CT	CARROLL ST	DEAD END	Odd	338	4	Concrete	25% Replacement	Fair	\$7,511.11
Total Length: 676								Total Cost:	\$13,144.44

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
CARROLL STREET									
CARROLL ST-01	MAPLE ST	CENTRAL AVE	Even	790	4	Concrete	Defer Maintenance	Excellent	\$0.00
CARROLL ST-01	MAPLE ST	CENTRAL AVE	Odd	790	4	Concrete	Defer Maintenance	Excellent	\$0.00
CARROLL ST-02	CENTRAL AVE	CARROLL CT	Even	261	4	Concrete	Defer Maintenance	Excellent	\$0.00
CARROLL ST-02	CENTRAL AVE	CARROLL CT	Odd	261	4	Concrete	Defer Maintenance	Excellent	\$0.00
CARROLL ST-03	CARROLL CT	HIGH ST	Even	181	4	Concrete	50% Replacement	Poor	\$6,033.33
CARROLL ST-03	CARROLL CT	HIGH ST	Odd	181	4	Concrete	25% Replacement	Fair	\$4,022.22
Total Length: 2,464								Total Cost:	\$10,055.56
CEDAR STREET									
CEDAR ST	CHURCH ST	WATER ST	Even	289	5	Concrete	10% Replacement	Good	\$2,408.33
Total Length: 289								Total Cost:	\$2,408.33
CENTRAL AVENUE									
CENTRAL AVE	MAPLE ST	CARROLL ST	Odd	210	4	Concrete	100% Replacement	Replace	\$14,000.00
Total Length: 210								Total Cost:	\$14,000.00
CHARLES STREET									
CHARLES ST-02	CHARLES CT	ANN ST	Odd	209	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 209								Total Cost:	\$0.00
CHERRY STREET									
CHERRY ST-01	SPENCER ST	OLIVE ST	Even	1103	5	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST-01	SPENCER ST	OLIVE ST	Odd	1103	4	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST-02	OLIVE ST	ROUTE 63	Even	1287	4	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST-02	OLIVE ST	ROUTE 63	Odd	1287	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 4,780								Total Cost:	\$0.00
CHERRY STREET EXTENSION									
CHERRY ST EXT-01	SPENCER ST	CHARLES ST	Even	447	4	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST EXT-01	SPENCER ST	CHARLES ST	Odd	447	4	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST EXT-02	CHARLES ST	ANN ST	Even	141	4	Concrete	Defer Maintenance	Excellent	\$0.00
CHERRY ST EXT-02	CHARLES ST	ANN ST	Odd	401	4	Concrete	10% Replacement	Good	\$2,673.33
Total Length: 1,436								Total Cost:	\$2,673.33
CHESTNUT STREET									
CHESTNUT ST-03	QUINN ST	PARK AVE	Even	86	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 86								Total Cost:	\$0.00
CHURCH STREET									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
CHURCH ST-01	RUBBER AVE	BARNUM CT	Even	527	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-01	RUBBER AVE	BARNUM CT	Odd	527	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-02	BARNUM CT	PARK PL	Even	262	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-02	BARNUM CT	PARK PL	Odd	262	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-03	PARK PL	MAPLE ST	Even	428	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-03	PARK PL	MAPLE ST	Odd	428	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-04	MAPLE ST	DIVISION ST	Even	150	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-04	MAPLE ST	DIVISION ST	Odd	150	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-05	DIVISION ST	CEDAR ST	Even	547	6	Concrete	Defer Maintenance	Excellent	\$0.00
CHURCH ST-05	DIVISION ST	CEDAR ST	Odd	547	6	Concrete	25% Replacement	Fair	\$18,233.33
CHURCH ST-06	CEDAR ST	MEADOW CT	Even	448	4	Concrete	25% Replacement	Fair	\$9,955.56
CHURCH ST-06	CEDAR ST	MEADOW CT	Odd	448	4	Concrete	25% Replacement	Fair	\$9,955.56
CHURCH ST-07	MEADOW CT	WATER ST	Even	677	4	Concrete	10% Replacement	Good	\$4,513.33
CHURCH ST-07	MEADOW CT	WATER ST	Odd	677	4	Concrete	10% Replacement	Good	\$4,513.33
Total Length: 6,078								Total Cost: \$47,171.11	

CITY BROOK ROAD

CITY BROOK RD-01	CITY HILL ST	SKYVIEW DR	Even	641	4	Concrete	10% Replacement	Good	\$4,273.33
CITY BROOK RD-01	CITY HILL ST	SKYVIEW DR	Odd	675	4	Concrete	10% Replacement	Good	\$4,500.00
CITY BROOK RD-02	SKYVIEW DR	DONOVAN RD	Even	460	4	Concrete	10% Replacement	Good	\$3,066.67
CITY BROOK RD-02	SKYVIEW DR	DONOVAN RD	Odd	460	4	Concrete	25% Replacement	Fair	\$10,222.22
Total Length: 2,236								Total Cost: \$22,062.22	

CITY HILL STREET

CITY HILL ST-01	N MIAN ST	CITY HILL CT	Even	641	4	Concrete	50% Replacement	Poor	\$21,366.67
CITY HILL ST-02	CITY HILL CT	HIGH ST	Even	406	4	Concrete	50% Replacement	Poor	\$13,533.33
CITY HILL ST-02	CITY HILL CT	HIGH ST	Odd	406	4	Concrete	25% Replacement	Fair	\$9,022.22
CITY HILL ST-03	HIGH ST	JOHN ST	Even	491	4	Concrete	Defer Maintenance	Excellent	\$0.00
CITY HILL ST-04	JOHN ST	WOOSTER ST	Even	473	4	Concrete	Defer Maintenance	Excellent	\$0.00
CITY HILL ST-04	JOHN ST	WOOSTER ST	Odd	118	4	Concrete	Defer Maintenance	Excellent	\$0.00
CITY HILL ST-05	WOOSTER ST	COEN LN	Even	1012	4	Concrete	Defer Maintenance	Excellent	\$0.00
CITY HILL ST-05	WOOSTER ST	COEN LN	Odd	202	4	Concrete	10% Replacement	Good	\$1,346.67
CITY HILL ST-06	COEN LN	MORRIS ST	Odd	263	4	Concrete	Defer Maintenance	Excellent	\$0.00
CITY HILL ST-07	MORRIS ST	CITY BROOK RD	Odd	920	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 4,932								Total Cost: \$45,268.89	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
CLEARVIEW CIRCLE									
CLEARVIEW CIR	MILLVILLE AVE	MILLVILLE AVE	Even	1017	4	Concrete	25% Replacement	Fair	\$22,600.00
CLEARVIEW CIR	MILLVILLE AVE	MILLVILLE AVE	Odd	1272	4	Concrete	10% Replacement	Good	\$8,480.00
Total Length: 2,289								Total Cost: \$31,080.00	
CLIFF STREET									
CLIFF ST-01	AETNA ST	LE CLAIR CT	Even	258	4	Concrete	10% Replacement	Good	\$1,720.00
CLIFF ST-02	LE CLAIR CT	PLEASANT VIEW ST	Even	467	4	Concrete	25% Replacement	Fair	\$10,377.78
CLIFF ST-03	PLEASANT VIEW ST	GEORGE ST	Even	423	4	Concrete	25% Replacement	Fair	\$9,400.00
CLIFF ST-03	PLEASANT VIEW ST	GEORGE ST	Odd	423	4	Concrete	25% Replacement	Fair	\$9,400.00
CLIFF ST-04	GEORGE ST	FREDRICK ST	Even	241	4	Concrete	10% Replacement	Good	\$1,606.67
CLIFF ST-04	GEORGE ST	FREDRICK ST	Odd	241	4	Concrete	25% Replacement	Fair	\$5,355.56
CLIFF ST-05	FREDRICK ST	WALNUT ST	Even	321	4	Concrete	50% Replacement	Poor	\$10,700.00
CLIFF ST-05	FREDRICK ST	WALNUT ST	Odd	321	4	Concrete	25% Replacement	Fair	\$7,133.33
CLIFF ST-06	WALNUT ST	FAIRVIEW AVE	Even	314	4	Concrete	25% Replacement	Fair	\$6,977.78
CLIFF ST-06	WALNUT ST	FAIRVIEW AVE	Odd	314	4	Concrete	100% Replacement	Replace	\$20,933.33
Total Length: 3,323								Total Cost: \$83,604.44	
COBBLE STREETONE COURT									
COBBLE STONE CT	PEMBROOK RD	CUL DE SAC	Even	419	4	Concrete	Defer Maintenance	Excellent	\$0.00
COBBLE STONE CT	PEMBROOK RD	CUL DE SAC	Odd	375	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 794								Total Cost: \$0.00	
COEN STREET									
COEN ST	OAK ST	DEAD END	Even	956	4	Concrete	25% Replacement	Fair	\$21,244.44
COEN ST	OAK ST	DEAD END	Odd	956	4	Concrete	25% Replacement	Fair	\$21,244.44
Total Length: 1,912								Total Cost: \$42,488.89	
COLD SPRING CIRCLE									
COLD SPRING CIR-01	BROOK ST	CUL DE SAC	Even	223	3	Concrete	50% Replacement	Poor	\$5,575.00
COLD SPRING CIR-01	BROOK ST	CUL DE SAC	Odd	223	3	Concrete	10% Replacement	Good	\$1,115.00
COLD SPRING CIR-02	CUL DE SAC	COLD SPRING CIR	Even	1137	3	Concrete	25% Replacement	Fair	\$18,950.00
COLD SPRING CIR-02	CUL DE SAC	COLD SPRING CIR	Odd	1137	3	Concrete	25% Replacement	Fair	\$18,950.00
Total Length: 2,720								Total Cost: \$44,590.00	
CROFUT ROAD									
CROFUT RD	WEBB RD	RUBBER AVE EXT	Odd	581	3	Concrete	10% Replacement	Good	\$2,905.00
Total Length: 581								Total Cost: \$2,905.00	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost	
CROSSING NORTH										
	PINEWOOD CROSSING NORTH SILVER BEECH DR	CUL DE SAC	Even	411	4	Concrete	Defer Maintenance	Excellent	\$0.00	
	PINEWOOD CROSSING NORTH SILVER BEECH DR	CUL DE SAC	Odd	411	4	Concrete	Defer Maintenance	Excellent	\$0.00	
Total Length: 822								Total Cost: \$0.00		
CULVER STREET										
	CULVER ST-01	HILL ST	HILLCREST AVE	Even	279	4	Concrete	25% Replacement	Fair	\$6,200.00
	CULVER ST-02	HILLCREST AVE	HOMESTEAD AVE	Even	261	3	Concrete	50% Replacement	Poor	\$6,525.00
	CULVER ST-02	HILLCREST AVE	HOMESTEAD AVE	Odd	234	4	Concrete	10% Replacement	Good	\$1,560.00
Total Length: 774								Total Cost: \$14,285.00		
CURTISS STREET										
	CURTISS ST-01	N MAIN ST	LINDEN ST	Even	537	5	Concrete	50% Replacement	Poor	\$22,375.00
	CURTISS ST-01	N MAIN ST	LINDEN ST	Odd	269	4	Concrete	25% Replacement	Fair	\$5,977.78
	CURTISS ST-03	GRIFFINS ST	ROUTE 8	Even	305	4	Concrete	100% Replacement	Replace	\$20,333.33
	CURTISS ST-03	GRIFFINS ST	ROUTE 8	Odd	305	4	Concrete	50% Replacement	Poor	\$10,166.67
Total Length: 1,416								Total Cost: \$58,852.78		
DAMSON LANE										
	DAMSON LN-01	N HOADLEY ST	BIRCH LN	Odd	188	4	Concrete	10% Replacement	Good	\$1,253.33
	DAMSON LN-02	BIRCH LN	N HOADLEY ST	Odd	866	4	Concrete	50% Replacement	Poor	\$28,866.67
Total Length: 1,054								Total Cost: \$30,120.00		
DIAMOND STREET										
	DIAMOND ST	SPRING ST	BRENNAN ST	Even	395	4	Concrete	10% Replacement	Good	\$2,633.33
	DIAMOND ST	SPRING ST	BRENNAN ST	Odd	395	4	Concrete	10% Replacement	Good	\$2,633.33
Total Length: 790								Total Cost: \$5,266.67		
DIVISION STREET										
	DIVISION ST	CHURCH ST	MEADOW ST	Even	349	4	Concrete	25% Replacement	Fair	\$7,755.56
	DIVISION ST	CHURCH ST	MEADOW ST	Odd	349	4	Concrete	10% Replacement	Good	\$2,326.67
Total Length: 698								Total Cost: \$10,082.22		
DONOVAN ROAD										
	DONOVAN RD-01	MAY ST	CITY HILL ST	Even	252	4	Concrete	Defer Maintenance	Excellent	\$0.00
	DONOVAN RD-02	CITY HILL ST	CITY BROOK RD	Even	475	4	Concrete	Defer Maintenance	Excellent	\$0.00
	DONOVAN RD-03	CITY BROOK RD	APPLEWOOD LN	Even	328	4	Concrete	10% Replacement	Good	\$2,186.67
	DONOVAN RD-04	APPLEWOOD LN	SIRRA RIDGE RD	Even	436	4	Concrete	10% Replacement	Good	\$2,906.67
	DONOVAN RD-04	APPLEWOOD LN	SIRRA RIDGE RD	Odd	872	4	Concrete	10% Replacement	Good	\$5,813.33

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
DONOVAN RD-05	SIERRA RIDGE RD	DONOVAN CT	Odd	590	4	Concrete	10% Replacement	Good	\$3,933.33
Total Length: 2,953								Total Cost: \$14,840.00	
EAST DRIVE									
EAST DR	PARK AVE	QUINN ST	Odd	41	4	Concrete	100% Replacement	Replace	\$2,733.33
Total Length: 41								Total Cost: \$2,733.33	
ELM STREET									
ELM ST-02	SCOTT ST	CHERRY ST	Odd	292	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 292								Total Cost: \$0.00	
ELMWOOD STREET									
ELMWOOD ST-01	WALNUT ST	ELMHURST ST	Even	239	4	Concrete	25% Replacement	Fair	\$5,311.11
ELMWOOD ST-01	WALNUT ST	ELMHURST ST	Odd	239	4	Concrete	25% Replacement	Fair	\$5,311.11
ELMWOOD ST-02	ELMHURST ST	HILLSIDE AVE	Even	208	4	Concrete	Defer Maintenance	Excellent	\$0.00
ELMWOOD ST-02	ELMHURST ST	HILLSIDE AVE	Odd	208	4	Concrete	10% Replacement	Good	\$1,386.67
Total Length: 894								Total Cost: \$12,008.89	
FAIRCHILD STREET									
FAIRCHILD ST-01	LEWIS ST	MALGARI CT	Even	321	4	Concrete	10% Replacement	Good	\$2,140.00
FAIRCHILD ST-03	HARD ST	GORMAN ST	Even	106	4	Concrete	10% Replacement	Good	\$706.67
Total Length: 427								Total Cost: \$2,846.67	
FAIRFIELD COURT									
FAIRFIELD CT	FIELD ST	CUL DE SAC	Odd	20	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 20								Total Cost: \$0.00	
FAIRLAWN STREET									
FAIRLAWN ST	HILL ST	HILLCREST AVE	Even	237	4	Concrete	25% Replacement	Fair	\$5,266.67
FAIRLAWN ST	HILL ST	HILLCREST AVE	Odd	237	4	Concrete	25% Replacement	Fair	\$5,266.67
Total Length: 474								Total Cost: \$10,533.33	
FAIRVIEW AVENUE									
FAIRVIEW AVE-01	POND ST	PLEASANT VIEW ST	Even	277	4	Concrete	50% Replacement	Poor	\$9,233.33
FAIRVIEW AVE-02	PLEASANT VIEW ST	GEORGE ST	Even	748	0	Concrete	100% Replacement	Replace	\$0.00
FAIRVIEW AVE-03	GEORGE ST	FREDRICK ST	Even	242	4	Concrete	25% Replacement	Fair	\$5,377.78
FAIRVIEW AVE-03	GEORGE ST	FREDRICK ST	Odd	242	6	Concrete	Defer Maintenance	Excellent	\$0.00
FAIRVIEW AVE-04	FREDRICK ST	CLIFF ST	Even	203	4	Concrete	50% Replacement	Poor	\$6,766.67
FAIRVIEW AVE-04	FREDRICK ST	CLIFF ST	Odd	203	5	Concrete	25% Replacement	Fair	\$5,638.89
FAIRVIEW AVE-05	CLIFF ST	HILLSIDE AVE	Even	271	4	Concrete	50% Replacement	Poor	\$9,033.33

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
FAIRVIEW AVE-05	CLIFF ST	HILLSIDE AVE	Odd	271	5	Concrete	10% Replacement	Good	\$2,258.33
Total Length: 2,457								Condition:	Total Cost: \$38,308.33
FARMSTEAD LANE									
FARMSTEAD LN	GRAHAM RIDGE RD	CUL DE SAC	Odd	691	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 691								Condition:	Total Cost: \$0.00
FAWN MEADOW DRIVE									
FAWN MEADOW DR-01	MULBERRY ST	WILD CHERRY DR	Even	948	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-01	MULBERRY ST	WILD CHERRY DR	Odd	948	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-02	WILD CHERRY DR	APPLE BLOSSOM DR	Even	1065	4	Concrete	10% Replacement	Good	\$7,100.00
FAWN MEADOW DR-02	WILD CHERRY DR	APPLE BLOSSOM DR	Odd	1065	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-03	APPLE BLOSSOM DR	PEAR TREE DR	Even	337	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-03	APPLE BLOSSOM DR	PEAR TREE DR	Odd	337	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-04	PEAR TREE DR	SWIFT LN	Even	329	4	Concrete	Defer Maintenance	Excellent	\$0.00
FAWN MEADOW DR-04	PEAR TREE DR	SWIFT LN	Odd	329	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 5,358								Condition:	Total Cost: \$7,100.00
FIELD STREET									
FIELD ST-14	HILLSIDE AVE	NORTH CHURCH ST	Odd	262	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 262								Condition:	Total Cost: \$0.00
FREDRICK STREET									
FREDRICK ST	FAIRVIEW AVE	CLIFF ST	Even	417	4	Concrete	25% Replacement	Fair	\$9,266.67
FREDRICK ST	FAIRVIEW AVE	CLIFF ST	Odd	417	4	Concrete	100% Replacement	Replace	\$27,800.00
Total Length: 834								Condition:	Total Cost: \$37,066.67
GALPIN STREET									
GALPIN ST-01	AETNA ST	MARSHALL AVE	Even	587	4	Concrete	50% Replacement	Poor	\$19,566.67
GALPIN ST-01	AETNA ST	MARSHALL AVE	Odd	587	4	Concrete	25% Replacement	Fair	\$13,044.44
GALPIN ST-02	MARSHALL AVE	WEST ST	Even	238	4	Concrete	25% Replacement	Fair	\$5,288.89
GALPIN ST-02	MARSHALL AVE	WEST ST	Odd	238	4	Concrete	50% Replacement	Poor	\$7,933.33
Total Length: 1,650								Condition:	Total Cost: \$45,833.33
GENERAL DALTON DRIVE									
GENERAL DALTON DR-01	MARJORIE ST	GENERAL DALTON DR	Even	610	4	Concrete	10% Replacement	Good	\$4,066.67
GENERAL DALTON DR-01	MARJORIE ST	GENERAL DALTON DR	Odd	610	4	Concrete	25% Replacement	Fair	\$13,555.56
GENERAL DALTON DR-02	GENERAL DALTON DR	DEAD END	Even	75	4	Concrete	10% Replacement	Good	\$500.00
GENERAL DALTON DR-02	GENERAL DALTON DR	DEAD END	Odd	135	4	Concrete	10% Replacement	Good	\$900.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 1,430								Total Cost: \$19,022.22	
GENERAL PATTON DRIVE									
GENERAL PATTON DR-01	MARJORIE ST	GENERAL DALTON DR	Even	762	4	Concrete	25% Replacement	Fair	\$16,933.33
GENERAL PATTON DR-01	MARJORIE ST	GENERAL DALTON DR	Odd	802	4	Concrete	25% Replacement	Fair	\$17,822.22
GENERAL PATTON DR-02	GENERAL DALTON DR	GLENDALE CT	Even	684	4	Concrete	25% Replacement	Fair	\$15,200.00
GENERAL PATTON DR-02	GENERAL DALTON DR	GLENDALE CT	Odd	513	4	Concrete	10% Replacement	Good	\$3,420.00
GENERAL PATTON DR-03	GLENDALE CT	DEAD END	Even	155	4	Concrete	10% Replacement	Good	\$1,033.33
Total Length: 2,916								Total Cost: \$54,408.89	
GENERAL PULASKI WALK									
GENERAL PULASKI WALK	BRIDGE ST	DEAD END	Even	500	4	Concrete	50% Replacement	Poor	\$16,666.67
GENERAL PULASKI WALK	BRIDGE ST	DEAD END	Odd	300	4	Concrete	10% Replacement	Good	\$2,000.00
Total Length: 800								Total Cost: \$18,666.67	
GEORGE STREET									
GEORGE ST	FAIRVIEW AVE	CLIFF ST	Even	402	4	Concrete	25% Replacement	Fair	\$8,933.33
GEORGE ST	FAIRVIEW AVE	CLIFF ST	Odd	402	4	Concrete	25% Replacement	Fair	\$8,933.33
Total Length: 804								Total Cost: \$17,866.67	
GOLDEN HILL STREET									
GOLDEN HILL ST-01	PROSPECT ST	ACUSHNET ST	Even	584	4	Concrete	25% Replacement	Fair	\$12,977.78
GOLDEN HILL ST-01	PROSPECT ST	ACUSHNET ST	Odd	584	3	Concrete	50% Replacement	Poor	\$14,600.00
GOLDEN HILL ST-02	ACUSHNET ST	WOODBINE ST	Even	428	3	Concrete	50% Replacement	Poor	\$10,700.00
GOLDEN HILL ST-02	ACUSHNET ST	WOODBINE ST	Odd	428	3	Concrete	50% Replacement	Poor	\$10,700.00
Total Length: 2,024								Total Cost: \$48,977.78	
GOODYEAR AVENUE									
GOODYEAR AVE-01	AETNA ST	TROWBRIDGE PL	Even	732	4	Concrete	50% Replacement	Poor	\$24,400.00
GOODYEAR AVE-01	AETNA ST	TROWBRIDGE PL	Odd	732	4	Concrete	25% Replacement	Fair	\$16,266.67
GOODYEAR AVE-02	TROWBRIDGE PL	HIGHLAND AVE	Even	307	4	Concrete	50% Replacement	Poor	\$10,233.33
GOODYEAR AVE-02	TROWBRIDGE PL	HIGHLAND AVE	Odd	307	4	Concrete	25% Replacement	Fair	\$6,822.22
Total Length: 2,078								Total Cost: \$57,722.22	
GORMAN STREET									
GORMAN ST-01	LEWIS ST	OLIVE ST	Even	694	4	Concrete	25% Replacement	Fair	\$15,422.22
GORMAN ST-01	LEWIS ST	OLIVE ST	Odd	298	4	Concrete	25% Replacement	Fair	\$6,622.22
GORMAN ST-03	VAGNINI DR	FAIRCHILD ST	Even	253	4	Concrete	10% Replacement	Good	\$1,686.67
GORMAN ST-03	VAGNINI DR	FAIRCHILD ST	Odd	253	4	Concrete	25% Replacement	Fair	\$5,622.22

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
GORMAN ST-04	FAIRCHILD ST	SPENCER ST	Even	562	4	Concrete	25% Replacement	Fair	\$12,488.89
Total Length: 2,060								Total Cost:	\$41,842.22
GRAHAM RIDGE ROAD									
GRAHAM RIDGE RD-01	WESTOVER DR	FARMSTEAD LN	Even	1341	4	Concrete	25% Replacement	Fair	\$29,800.00
GRAHAM RIDGE RD-01	WESTOVER DR	FARMSTEAD LN	Odd	1341	4	Concrete	10% Replacement	Good	\$8,940.00
GRAHAM RIDGE RD-02	FARMSTEAD LN	WESTOVER DR	Even	2050	4	Concrete	25% Replacement	Fair	\$45,555.56
Total Length: 4,732								Total Cost:	\$84,295.56
GREENWOOD STREET									
GREENWOOD ST-01	SCHOOL ST	BRIDGE ST	Even	466	4	Concrete	25% Replacement	Fair	\$10,355.56
GREENWOOD ST-01	SCHOOL ST	BRIDGE ST	Odd	23	4	Concrete	Defer Maintenance	Excellent	\$0.00
GREENWOOD ST-02	BRIDGE ST	DEAD END	Even	348	4	Concrete	25% Replacement	Fair	\$7,733.33
GREENWOOD ST-02	BRIDGE ST	DEAD END	Odd	25	4	Concrete	10% Replacement	Good	\$166.67
Total Length: 862								Total Cost:	\$18,255.56
GRIFFIN STREET									
GRIFFIN ST	N MAIN ST	CURTISS ST	Odd	235	4	Concrete	10% Replacement	Good	\$1,566.67
Total Length: 235								Total Cost:	\$1,566.67
GROVE STREET									
GROVE ST-01	PARK AVE	MAY AVE	Even	355	4	Concrete	25% Replacement	Fair	\$7,888.89
GROVE ST-02	MAY AVE	WALNUT ST	Even	289	4	Concrete	Defer Maintenance	Excellent	\$0.00
GROVE ST-02	MAY AVE	WALNUT ST	Odd	217	4	Concrete	100% Replacement	Replace	\$14,466.67
GROVE ST-03	WALNUT ST	WOODLAWN AVE	Even	327	4	Concrete	50% Replacement	Poor	\$10,900.00
GROVE ST-03	WALNUT ST	WOODLAWN AVE	Odd	327	4	Concrete	50% Replacement	Poor	\$10,900.00
GROVE ST-04	WOODLAWN AVE	HILLSIDE AVE	Odd	371	4	Concrete	25% Replacement	Fair	\$8,244.44
Total Length: 1,886								Total Cost:	\$52,400.00
HARD STREET									
HARD ST	FAIRCHILD ST	SPENCER ST	Even	582	4	Concrete	25% Replacement	Fair	\$12,933.33
HARD ST	FAIRCHILD ST	SPENCER ST	Odd	349	4	Concrete	10% Replacement	Good	\$2,326.67
Total Length: 931								Total Cost:	\$15,260.00
HICKORY ROAD									
HICKORY RD-01	HIGH ST	BURITT PL	Even	63	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 63								Total Cost:	\$0.00
HIGH STREET									
HIGH ST-06	CALVINST	OAK ST	Even	844	4	Concrete	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
HIGH ST-07	OAK ST	HILL ST	Even	508	4	Concrete	Defer Maintenance	Excellent	\$0.00
HIGH ST-08	HILL ST	MAPLE TER	Odd	325	4	Concrete	25% Replacement	Fair	\$7,222.22
HIGH ST-10	CARROLL ST	HILL ST	Even	169	4	Concrete	10% Replacement	Good	\$1,126.67
HIGH ST-11	HILL ST	HICKORY RD	Odd	352	4	Concrete	50% Replacement	Poor	\$11,733.33
HIGH ST-12	HICKORY RD	WOODLAND ST	Even	383	4	Concrete	10% Replacement	Good	\$2,553.33
HIGH ST-12	HICKORY RD	WOODLAND ST	Odd	383	4	Concrete	50% Replacement	Poor	\$12,766.67
HIGH ST-13	WOODLAND ST	S MAIN ST	Odd	1502	4	Concrete	25% Replacement	Fair	\$33,377.78
Total Length: 4,466								Total Cost:	\$68,780.00

HIGHLAND AVENUE

HIGHLAND AVE-01	HOADLEY ST	GALPIN ST	Even	451	4	Concrete	50% Replacement	Poor	\$15,033.33
HIGHLAND AVE-01	HOADLEY ST	GALPIN ST	Odd	451	4	Concrete	100% Replacement	Replace	\$30,066.67
HIGHLAND AVE-05	HIGHLAND CIR	WALNUT ST	Even	121	4	Concrete	50% Replacement	Poor	\$4,033.33
HIGHLAND AVE-05	HIGHLAND CIR	WALNUT ST	Odd	121	4	Concrete	50% Replacement	Poor	\$4,033.33
Total Length: 1,144								Total Cost:	\$53,166.67

HILL STREET

HILL ST-02	FAIRLAWN ST	CULVER ST	Odd	110	4	Concrete	50% Replacement	Poor	\$3,666.67
HILL ST-03	MAY ST	FAIRLAWN ST	Even	296	4	Concrete	25% Replacement	Fair	\$6,577.78
Total Length: 406								Total Cost:	\$10,244.44

HILLCREST AVENUE

HILLCREST AVE-01	FAIRLAWN ST	MAY ST	Even	288	4	Concrete	10% Replacement	Good	\$1,920.00
HILLCREST AVE-01	FAIRLAWN ST	MAY ST	Odd	288	4	Concrete	10% Replacement	Good	\$1,920.00
HILLCREST AVE-02	CULVER ST	FAIRLAWN ST	Even	234	4	Concrete	Defer Maintenance	Excellent	\$0.00
HILLCREST AVE-02	CULVER ST	FAIRLAWN ST	Odd	234	4	Concrete	10% Replacement	Good	\$1,560.00
Total Length: 1,044								Total Cost:	\$5,400.00

HILLSIDE AVENUE

HILLSIDE AVE-01	FIELD ST	PARK AVE	Even	233	4	Concrete	25% Replacement	Fair	\$5,177.78
HILLSIDE AVE-01	FIELD ST	PARK AVE	Odd	388	4	Concrete	25% Replacement	Fair	\$8,622.22
HILLSIDE AVE-02	PARK AVE	BUCKINGHAM ST	Even	530	4	Concrete	25% Replacement	Fair	\$11,777.78
HILLSIDE AVE-02	PARK AVE	BUCKINGHAM ST	Odd	530	4	Concrete	10% Replacement	Good	\$3,533.33
HILLSIDE AVE-03	BUCKINGHAM ST	JUDD ST	Even	989	3	Concrete	25% Replacement	Fair	\$16,483.33
HILLSIDE AVE-03	BUCKINGHAM ST	JUDD ST	Odd	989	3	Concrete	10% Replacement	Good	\$4,945.00
HILLSIDE AVE-04	JUDD ST	BRADBURY ST	Even	406	3	Concrete	10% Replacement	Good	\$2,030.00
HILLSIDE AVE-04	JUDD ST	BRADBURY ST	Odd	385	3	Concrete	10% Replacement	Good	\$1,925.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
HILLSIDE AVE-05	BRADBURY ST	SALEM ST	Even	257	4	Concrete	25% Replacement	Fair	\$5,711.11
HILLSIDE AVE-05	BRADBURY ST	SALEM ST	Odd	257	4	Concrete	25% Replacement	Fair	\$5,711.11
HILLSIDE AVE-06	SALEM ST	GROVE ST	Odd	647	4	Concrete	25% Replacement	Fair	\$14,377.78
HILLSIDE AVE-07	GROVE ST	ROCKWELL AVE	Even	217	4	Concrete	10% Replacement	Good	\$1,446.67
HILLSIDE AVE-07	GROVE ST	ROCKWELL AVE	Odd	217	4	Concrete	25% Replacement	Fair	\$4,822.22
HILLSIDE AVE-08	ROCKWELL AVE	MILLVILLE AVE	Even	585	4	Concrete	100% Replacement	Replace	\$39,000.00
HILLSIDE AVE-08	ROCKWELL AVE	MILLVILLE AVE	Odd	585	4	Concrete	25% Replacement	Fair	\$13,000.00
HILLSIDE AVE-09	MILLVILLE AVE	SWEENEY ST	Odd	364	4	Concrete	10% Replacement	Good	\$2,426.67
HILLSIDE AVE-10	SWEENEY ST	ELMWOOD ST	Even	395	4	Concrete	25% Replacement	Fair	\$8,777.78
HILLSIDE AVE-10	SWEENEY ST	ELMWOOD ST	Odd	395	4	Concrete	50% Replacement	Poor	\$13,166.67
HILLSIDE AVE-11	ELMWOOD ST	TERRACE AVE	Even	196	4	Concrete	Defer Maintenance	Excellent	\$0.00
HILLSIDE AVE-11	ELMWOOD ST	TERRACE AVE	Odd	196	4	Concrete	50% Replacement	Poor	\$6,533.33
HILLSIDE AVE-12	MEADOW ST	PAVEMENT CHANGE	Even	184	4	Concrete	25% Replacement	Fair	\$4,088.89
HILLSIDE AVE-13	PAVEMENT CHANGE	FAIRVIEW AVE	Even	250	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 9,195								Total Cost: \$173,556.67	

HOADLEY STREET

HOADLEY ST-02	AETNA ST	HOADLEY TER	Odd	397	4	Concrete	Defer Maintenance	Excellent	\$0.00
HOADLEY ST-03	HOADLEY TER	MARSHALL AVE	Odd	348	4	Concrete	Defer Maintenance	Excellent	\$0.00
HOADLEY ST-04	MARSHALL AVE	WEST ST	Odd	234	4	Concrete	Defer Maintenance	Excellent	\$0.00
HOADLEY ST-05	WEST ST	HIGHLAND AVE	Odd	236	4	Concrete	Defer Maintenance	Excellent	\$0.00
HOADLEY ST-06	HIGHLAND AVE	SUMMIT RD	Odd	498	4	Concrete	Defer Maintenance	Excellent	\$0.00
HOADLEY ST-07	SUMMIT RD	MILLVILLE AVE	Odd	228	4	Concrete	10% Replacement	Good	\$1,520.00
Total Length: 1,941								Total Cost: \$1,520.00	

HOMESTEAD AVENUE

HOMESTEAD AVE-01	HIGH ST	CULVER CT	Odd	193	4	Concrete	25% Replacement	Fair	\$4,288.89
HOMESTEAD AVE-02	CULVER CT	CULVER ST	Odd	501	4	Concrete	25% Replacement	Fair	\$11,133.33
HOMESTEAD AVE-03	CULVER ST	DEAD END	Odd	112	4	Concrete	50% Replacement	Poor	\$3,733.33
Total Length: 806								Total Cost: \$19,155.56	

HOPKINS HILL ROAD

HOPKINS HILL RD	MULBERRY ST	CUL DE SAC	Even	778	4	Concrete	25% Replacement	Fair	\$17,288.89
HOPKINS HILL RD	MULBERRY ST	CUL DE SAC	Odd	778	4	Concrete	10% Replacement	Good	\$5,186.67
Total Length: 1,556								Total Cost: \$22,475.56	

IDA STREET

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
IDA ST	SPENCER ST	IRVING ST	Even	298	4	Concrete	Defer Maintenance	Excellent	\$0.00
IDA ST	SPENCER ST	IRVING ST	Odd	298	4	Concrete	25% Replacement	Fair	\$6,622.22
Total Length: 596								Total Cost:	\$6,622.22
IRVING STREET									
IRVING ST-02	IDA ST	SPENCER ST	Even	856	4	Concrete	25% Replacement	Fair	\$19,022.22
IRVING ST-02	IDA ST	SPENCER ST	Odd	856	4	Concrete	50% Replacement	Poor	\$28,533.33
Total Length: 1,712								Total Cost:	\$47,555.56
JONES ROAD									
JONES RD-02	WEBB RD	STONE FENCE RD	Odd	386	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 386								Total Cost:	\$0.00
JUDD STREET									
JUDD ST	HILLSIDE AVE	BUCKINGHAM ST	Even	352	4	Concrete	10% Replacement	Good	\$2,346.67
JUDD ST	HILLSIDE AVE	BUCKINGHAM ST	Odd	352	4	Concrete	10% Replacement	Good	\$2,346.67
Total Length: 704								Total Cost:	\$4,693.33
LAUREL AVENUE									
LAUREL AVE	NEW HAVEN RD	MARJORIE ST	Even	452	4	Concrete	10% Replacement	Good	\$3,013.33
LAUREL AVE	NEW HAVEN RD	MARJORIE ST	Odd	301	4	Concrete	25% Replacement	Fair	\$6,688.89
Total Length: 753								Total Cost:	\$9,702.22
LEWIS CIRCLE									
LEWIS CIR	SPENCER ST	CUL DE SAC	Even	691	4	Concrete	Defer Maintenance	Excellent	\$0.00
LEWIS CIR	SPENCER ST	CUL DE SAC	Odd	691	4	Concrete	25% Replacement	Fair	\$15,355.56
Total Length: 1,382								Total Cost:	\$15,355.56
LEWIS STREET									
LEWIS ST-01	SCOTT ST	NIXON AVE	Even	247	4	Concrete	50% Replacement	Poor	\$8,233.33
LEWIS ST-02	NIXON AVE	MANNERS AVE	Odd	191	4	Concrete	100% Replacement	Replace	\$12,733.33
LEWIS ST-03	MANNERS AVE	OLIVE ST	Even	482	4	Concrete	50% Replacement	Poor	\$16,066.67
LEWIS ST-03	MANNERS AVE	OLIVE ST	Odd	482	4	Concrete	50% Replacement	Poor	\$16,066.67
LEWIS ST-04	OLIVE ST	FAIRCHILD ST	Odd	51	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,453								Total Cost:	\$53,100.00
LINDEN STREET									
LINDEN ST-01	N MAIN ST	CURTISS ST	Even	91	3	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 91								Total Cost:	\$0.00
LYNN CIRCLE									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
LYNN CIR	DEERLING LN	CUL DE SAC	Even	153	4	Concrete	25% Replacement	Fair	\$3,400.00
Total Length: 153								Total Cost:	\$3,400.00
LYNN ROAD									
LYNN RD	MOORE AVE	DEAD END	Odd	124	4	Concrete	25% Replacement	Fair	\$2,755.56
Total Length: 124								Total Cost:	\$2,755.56
MALGARI COURT									
MALGARI CT	FAIRCHILD ST	DEAD END	Even	143	4	Concrete	25% Replacement	Fair	\$3,177.78
MALGARI CT	FAIRCHILD ST	DEAD END	Odd	238	3	Concrete	25% Replacement	Fair	\$3,966.67
Total Length: 381								Total Cost:	\$7,144.44
MAPLE HILL ROAD									
MAPLE HILL RD-09	INWOOD DR	OLDE FARM LN	Even	257	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE HILL RD-12	MULBERRY ST	VICTORIA LN	Even	847	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,104								Total Cost:	\$0.00
MAPLE STREET									
MAPLE ST-01	CHURCH ST	OLD FIREHOUSE RD	Even	250	6	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-01	CHURCH ST	OLD FIREHOUSE RD	Odd	250	6	Concrete	10% Replacement	Good	\$2,500.00
MAPLE ST-02	OLD FIREHOUSE RD	WATER ST	Even	400	5	Concrete	100% Replacement	Replace	\$33,333.33
MAPLE ST-02	OLD FIREHOUSE RD	WATER ST	Odd	400	6	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-03	WATER ST	OAK ST	Even	391	6	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-03	WATER ST	OAK ST	Odd	391	6	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-04	OAK ST	CENTRAL AVE	Even	62	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-04	OAK ST	CENTRAL AVE	Odd	155	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-05	CENTRAL AVE	CARROLL ST	Even	231	6	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-05	CENTRAL AVE	CARROLL ST	Odd	231	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAPLE ST-06	CARROLL ST	MAPLE TER	Even	245	4	Concrete	25% Replacement	Fair	\$5,444.44
MAPLE ST-06	CARROLL ST	MAPLE TER	Odd	245	4	Concrete	25% Replacement	Fair	\$5,444.44
Total Length: 3,251								Total Cost:	\$46,722.22
MARJORIE STREET									
MARJORIE ST-01	HAZEL AVE	GENERAL DALTON DR	Odd	130	4	Concrete	50% Replacement	Poor	\$4,333.33
MARJORIE ST-02	GENERAL DALTON DR	LAUREL AVE	Odd	188	4	Concrete	100% Replacement	Replace	\$12,533.33
MARJORIE ST-03	LAUREL AVE	GENERAL PATTON DR	Odd	125	4	Concrete	25% Replacement	Fair	\$2,777.78
Total Length: 443								Total Cost:	\$19,644.44
MAY AVENUE									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
MAY AVE-02	NEW ST	GROVE ST	Even	346	4	Concrete	25% Replacement	Fair	\$7,688.89
MAY AVE-02	NEW ST	GROVE ST	Odd	346	4	Concrete	25% Replacement	Fair	\$7,688.89
MAY AVE-03	GROVE ST	MILLVILLE AVE	Odd	816	4	Concrete	25% Replacement	Fair	\$18,133.33
Total Length: 1,508								Total Cost:	\$33,511.11
MAY STREET									
MAY ST-02	HILL ST	HILLCREST AVE	Even	161	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAY ST-03	HILLCREST AVE	PHOENIX AVE	Even	190	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAY ST-04	PHOENIX AVE	SPRUCE DR	Even	290	4	Concrete	Defer Maintenance	Excellent	\$0.00
MAY ST-16	MAPLE HILL RD	PROSPECT TL	Odd	1226	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,867								Total Cost:	\$0.00
MEADOW BROOK PLACE									
MEADOW BROOK PL	CROSS ST	CUL DE SAC	Even	538	4	Concrete	10% Replacement	Good	\$3,586.67
Total Length: 538								Total Cost:	\$3,586.67
MEADOW COURT									
MEADOW CT	CHURCH ST	MEADOW CT	Even	347	4	Concrete	10% Replacement	Good	\$2,313.33
MEADOW CT	CHURCH ST	MEADOW CT	Odd	347	4	Concrete	10% Replacement	Good	\$2,313.33
Total Length: 694								Total Cost:	\$4,626.67
MELISSA COURT									
MELISSA CT	MALLANE LN	CUL DE SAC	Even	195	4	Concrete	10% Replacement	Good	\$1,300.00
Total Length: 195								Total Cost:	\$1,300.00
MILLVILLE AVENUE									
MILLVILLE AVE-08	N HOADLEY ST	FERN ST	Odd	281	4	Concrete	25% Replacement	Fair	\$6,244.44
MILLVILLE AVE-09	FERN ST	QUINN ST	Even	116	4	Concrete	10% Replacement	Good	\$773.33
MILLVILLE AVE-09	FERN ST	QUINN ST	Odd	233	4	Concrete	25% Replacement	Fair	\$5,177.78
MILLVILLE AVE-10	QUINN ST	PARK AVE	Even	213	4	Concrete	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-10	QUINN ST	PARK AVE	Odd	355	4	Concrete	10% Replacement	Good	\$2,366.67
MILLVILLE AVE-11	PARK AVE	WALNUT ST	Even	430	4	Concrete	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-12	WALNUT ST	WOODLAWN AVE	Even	323	4	Concrete	10% Replacement	Good	\$2,153.33
MILLVILLE AVE-12	WALNUT ST	WOODLAWN AVE	Odd	323	4	Concrete	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-13	WOODLAWN AVE	HILLSIDE AVE	Even	364	4	Concrete	50% Replacement	Poor	\$12,133.33
MILLVILLE AVE-13	WOODLAWN AVE	HILLSIDE AVE	Odd	364	4	Concrete	Defer Maintenance	Excellent	\$0.00
MILLVILLE AVE-14	HILLSIDE AVE	TERRACE AVE	Odd	379	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 3,381								Total Cost:	\$28,848.89

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
MOORE AVENUE									
MOORE AVE-01	CLIFF ST	LYNN RD	Odd	550	3	Concrete	10% Replacement	Good	\$2,750.00
MOORE AVE-02	LYNN RD	NETTLETON AVE	Even	200	4	Concrete	Defer Maintenance	Excellent	\$0.00
MOORE AVE-02	LYNN RD	NETTLETON AVE	Odd	200	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 950								Total Cost: \$2,750.00	
MULBERRY STREET									
MULBERRY ST-08	MAPLE HILL RD	KENT ST	Odd	304	4	Concrete	Defer Maintenance	Excellent	\$0.00
MULBERRY ST-09	KENT ST	RUSTLING REED RD	Odd	294	4	Concrete	Defer Maintenance	Excellent	\$0.00
MULBERRY ST-10	RUSTLING REED RD	DEAD END	Odd	251	4	Concrete	10% Replacement	Good	\$1,673.33
Total Length: 849								Total Cost: \$1,673.33	
MYRTLE AVENUE									
MYRTLE AVE	N MAIN ST	DEAD END	Even	275	4	Concrete	25% Replacement	Fair	\$6,111.11
MYRTLE AVE	N MAIN ST	DEAD END	Odd	275	4	Concrete	25% Replacement	Fair	\$6,111.11
Total Length: 550								Total Cost: \$12,222.22	
N HOADLEY STREET									
N HOADLEY ST-02	COTTAGE ST	PHYLLIS DR	Odd	321	4	Concrete	50% Replacement	Poor	\$10,700.00
N HOADLEY ST-03	PHYLLIS DR	CHESTNUT ST	Even	82	4	Concrete	100% Replacement	Replace	\$5,466.67
Total Length: 403								Total Cost: \$16,166.67	
N MAIN STREET									
N MAIN ST-01	CALVIN ST	CURTISS CT	Even	204	4	Concrete	Defer Maintenance	Excellent	\$0.00
N MAIN ST-02	CURTISS CT	LINDEN ST	Even	677	5	Concrete	Defer Maintenance	Excellent	\$0.00
N MAIN ST-03	LINDEN ST	GRIFFIN ST	Even	712	4	Concrete	Defer Maintenance	Excellent	\$0.00
N MAIN ST-04	GRIFFIN ST	SMITH ST	Even	399	4	Concrete	25% Replacement	Fair	\$8,866.67
N MAIN ST-05	SMITH ST	CITY HILL ST	Even	522	4	Concrete	25% Replacement	Fair	\$11,600.00
N MAIN ST-06	CITY HILL ST	PROSPECT ST	Even	293	4	Concrete	Defer Maintenance	Excellent	\$0.00
N MAIN ST-06	CITY HILL ST	PROSPECT ST	Odd	326	6	Concrete	Defer Maintenance	Excellent	\$0.00
N MAIN ST-08	GOLDEN CT	WOOD ST	Odd	235	4	Concrete	10% Replacement	Good	\$1,566.67
N MAIN ST-09	WOOD ST	MYRTLE AVE	Odd	240	0	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 3,608								Total Cost: \$22,033.33	
NETTLETON AVENUE									
NETTLETON AVE-01	AETNA ST	MOORE AVE	Even	367	4	Concrete	50% Replacement	Poor	\$12,233.33
NETTLETON AVE-01	AETNA ST	MOORE AVE	Odd	458	4	Concrete	50% Replacement	Poor	\$15,266.67
NETTLETON AVE-02	MOORE AVE	TROWBRIDGE PL	Even	199	4	Concrete	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
NETTLETON AVE-02	MOORE AVE	TROWBRIDGE PL	Odd	199	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,223								Total Cost: \$27,500.00	
NEW STREET									
NEW ST-01	SALEM ST	HILLSIDE AVE	Even	408	4	Concrete	50% Replacement	Poor	\$13,600.00
NEW ST-01	SALEM ST	HILLSIDE AVE	Odd	408	4	Concrete	10% Replacement	Good	\$2,720.00
NEW ST-03	SVEA AVE	WALNUT ST	Odd	350	4	Concrete	50% Replacement	Poor	\$11,666.67
NEW ST-04	WALNUT ST	MAY AVE	Odd	393	4	Concrete	25% Replacement	Fair	\$8,733.33
NEW ST-05	MAY AVE	PARK AVE	Even	71	4	Concrete	50% Replacement	Poor	\$2,366.67
NEW ST-05	MAY AVE	PARK AVE	Odd	106	3	Concrete	10% Replacement	Good	\$530.00
Total Length: 1,736								Total Cost: \$39,616.67	
NORTH CIRCLE									
NORTH CIR	BROOKSIDE AVE	CUL DE SAC	Even	173	4	Concrete	25% Replacement	Fair	\$3,844.44
NORTH CIR	BROOKSIDE AVE	CUL DE SAC	Odd	173	4	Concrete	50% Replacement	Poor	\$5,766.67
Total Length: 346								Total Cost: \$9,611.11	
OAK STREET									
OAK ST-01	MAPLE ST	HIGH ST	Even	793	4	Concrete	25% Replacement	Fair	\$17,622.22
OAK ST-02	HIGH ST	COEN ST	Even	307	4	Concrete	25% Replacement	Fair	\$6,822.22
OAK ST-02	HIGH ST	COEN ST	Odd	307	4	Concrete	50% Replacement	Poor	\$10,233.33
OAK ST-03	COEN ST	BRADLEY ST	Odd	108	4	Concrete	25% Replacement	Fair	\$2,400.00
Total Length: 1,515								Total Cost: \$37,077.78	
OLD FIREHOUSE ROAD									
OLD FIREHOUSE RD	MAPLE ST	ELM ST	Even	1196	4	Concrete	Defer Maintenance	Excellent	\$0.00
OLD FIREHOUSE RD	MAPLE ST	ELM ST	Odd	1196	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 2,392								Total Cost: \$0.00	
OLDE FARM LANE									
OLDE FARM LN	MAPLE HILL RD	CUL DE SAC	Even	643	4	Concrete	Defer Maintenance	Excellent	\$0.00
OLDE FARM LN	MAPLE HILL RD	CUL DE SAC	Odd	643	4	Concrete	10% Replacement	Good	\$4,286.67
Total Length: 1,286								Total Cost: \$4,286.67	
OLIVE STREET									
OLIVE ST-01	CHERRY ST	GORMAN ST	Even	415	4	Concrete	25% Replacement	Fair	\$9,222.22
OLIVE ST-01	CHERRY ST	GORMAN ST	Odd	415	4	Concrete	25% Replacement	Fair	\$9,222.22
OLIVE ST-02	GORMENT ST	LEWIS ST	Even	692	4	Concrete	50% Replacement	Poor	\$23,066.67
OLIVE ST-02	GORMENT ST	LEWIS ST	Odd	519	4	Concrete	25% Replacement	Fair	\$11,533.33

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 2,041								Total Cost: \$53,044.44	
ORCHARD STREET									
ORCHARD ST-01	HIGH ST	ORCHARD TER	Odd	237	4	Concrete	50% Replacement	Poor	\$7,900.00
Total Length: 237								Total Cost: \$7,900.00	
OSBORN ROAD									
OSBORN RD-03	D'ARCANGELO DR	DAVIN DR	Odd	372	4	Concrete	Defer Maintenance	Excellent	\$0.00
OSBORN RD-04	DAVIN DR	CELENTANO DR	Odd	620	4	Concrete	10% Replacement	Good	\$4,133.33
OSBORN RD-05	CELENTANO DR	CARRIAGE DR	Odd	259	4	Concrete	Defer Maintenance	Excellent	\$0.00
OSBORN RD-06	CARRIAGE DR	WISTERIA DR	Even	356	4	Concrete	Defer Maintenance	Excellent	\$0.00
OSBORN RD-06	CARRIAGE DR	WISTERIA DR	Odd	594	4	Concrete	Defer Maintenance	Excellent	\$0.00
OSBORN RD-07	WISTERIA DR	CUL DE SAC	Even	476	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 2,677								Total Cost: \$4,133.33	
PARK AVENUE									
PARK AVE-01	WALNUT TER	MILLVILLE AVE	Even	875	3	Concrete	25% Replacement	Fair	\$14,583.33
PARK AVE-01	WALNUT TER	MILLVILLE AVE	Odd	921	3	Concrete	25% Replacement	Fair	\$15,350.00
PARK AVE-02	MILLVILLE AVE	GROVE ST	Even	795	4	Concrete	25% Replacement	Fair	\$17,666.67
PARK AVE-02	MILLVILLE AVE	GROVE ST	Odd	795	4	Concrete	25% Replacement	Fair	\$17,666.67
PARK AVE-03	GROVE ST	NEW ST	Odd	346	4	Concrete	10% Replacement	Good	\$2,306.67
PARK AVE-04	NEW ST	CHESTNUT ST	Even	261	4	Concrete	10% Replacement	Good	\$1,740.00
PARK AVE-04	NEW ST	CHESTNUT ST	Odd	372	4	Concrete	Defer Maintenance	Excellent	\$0.00
PARK AVE-05	CHESTNUT ST	EAST DR	Odd	1392	3	Concrete	50% Replacement	Poor	\$34,800.00
PARK AVE-06	EAST DR	HILLSIDE AVE	Even	141	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 5,898								Total Cost: \$104,113.33	
PARK PLACE									
PARK PL	CHURCH ST	MEADOW ST	Even	353	4	Concrete	25% Replacement	Fair	\$7,844.44
PARK PL	CHURCH ST	MEADOW ST	Odd	353	4	Concrete	25% Replacement	Fair	\$7,844.44
Total Length: 706								Total Cost: \$15,688.89	
PEAR TREE DRIVE									
PEAR TREE DR	FAWN MEADOW DR	CUL DE SAC	Even	614	4	Concrete	Defer Maintenance	Excellent	\$0.00
PEAR TREE DR	FAWN MEADOW DR	CUL DE SAC	Odd	614	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,228								Total Cost: \$0.00	
PEMBROOK ROAD									
PEMBROOK RD	MAY ST	CUL DE SAC	Even	652		Concrete	Defer Maintenance	Excellent	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
PEMBROOK RD	MAY ST	CUL DE SAC	Odd	618		Concrete	Defer Maintenance	Excellent	
Total Length: 1,270								Total Cost:	
PINEWOOD CROSSING SOUTH									
PINEWOOD CROSSING SOUTH	SILVER BEECH DR	CUL DE SAC	Even	313	4	Concrete	Defer Maintenance	Excellent	\$0.00
PINEWOOD CROSSING SOUTH	SILVER BEECH DR	CUL DE SAC	Odd	313	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 626								Total Cost: \$0.00	
PLEASANT VIEW STREET									
PLEASANT VIEW ST	FAIRVIEW AVE	CLIFF ST	Even	585	4	Concrete	25% Replacement	Fair	\$13,000.00
PLEASANT VIEW ST	FAIRVIEW AVE	CLIFF ST	Odd	585	4	Concrete	25% Replacement	Fair	\$13,000.00
Total Length: 1,170								Total Cost: \$26,000.00	
POND STREET									
POND ST-01	RUBBER AVE	SOUTHVIEW ST	Odd	285	4	Concrete	50% Replacement	Poor	\$9,500.00
POND ST-02	SOUTHVIEW ST	FAIRVIEW AVE	Even	46	2	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 331								Total Cost: \$9,500.00	
POND VALLEY ROAD									
POND VALLEY RD	SILVER BEECH DR	CUL DE SAC	Even	271	4	Concrete	Defer Maintenance	Excellent	\$0.00
POND VALLEY RD	SILVER BEECH DR	CUL DE SAC	Odd	271	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 542								Total Cost: \$0.00	
QUINN STREET									
QUINN ST-01	FIELD ST	NO HOADLEY ST	Even	338	3	Concrete	50% Replacement	Poor	\$8,450.00
QUINN ST-01	FIELD ST	NO HOADLEY ST	Odd	376	3	Concrete	10% Replacement	Good	\$1,880.00
QUINN ST-02	N HOADLEY ST	QUINN ST-03	Even	529	3	Concrete	25% Replacement	Fair	\$8,816.67
QUINN ST-03	QUINN ST-02	SURREY DR	Odd	86	1	Concrete	100% Replacement	Replace	\$1,433.33
QUINN ST-07	CHESTNUT ST	MILLVILLE AVE	Even	1495	3	Concrete	25% Replacement	Fair	\$24,916.67
QUINN ST-07	CHESTNUT ST	MILLVILLE AVE	Odd	1495	4	Concrete	25% Replacement	Fair	\$33,222.22
Total Length: 4,319								Total Cost: \$78,718.89	
RADNOR AVENUE									
RADNOR AVE-02	WILLOW LN	BEARDSLEY AVE	Even	234	4	Concrete	50% Replacement	Poor	\$7,800.00
RADNOR AVE-02	WILLOW LN	BEARDSLEY AVE	Odd	273	4	Concrete	25% Replacement	Fair	\$6,066.67
RADNOR AVE-03	BEARDSLEY AVE	SANDE AVE	Even	336	4	Concrete	25% Replacement	Fair	\$7,466.67
RADNOR AVE-03	BEARDSLEY AVE	SANDE AVE	Odd	336	4	Concrete	25% Replacement	Fair	\$7,466.67
RADNOR AVE-04	SANDE AVE	WATERBURY TL	Even	279	4	Concrete	25% Replacement	Fair	\$6,200.00
Total Length: 1,458								Total Cost: \$35,000.00	

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
ROCKWELL AVENUE									
ROCKWELL AVE	HILLSIDE AVE	SALEM ST	Even	1052	4	Concrete	50% Replacement	Poor	\$35,066.67
ROCKWELL AVE	HILLSIDE AVE	SALEM ST	Odd	1052	4	Concrete	25% Replacement	Fair	\$23,377.78
Total Length: 2,104								Total Cost:	\$58,444.44
ROSEWOOD COURT									
ROSEWOOD CT	APPLEWOOD LN	CUL DE SAC	Even	129	4	Concrete	10% Replacement	Good	\$860.00
ROSEWOOD CT	APPLEWOOD LN	CUL DE SAC	Odd	129	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 258								Total Cost:	\$860.00
RUBBER AVENUE									
RUBBER AVE-01	NEUMANN ST	WOODRUFF AVE	Even	179	4	Concrete	Defer Maintenance	Excellent	\$0.00
RUBBER AVE-07	ANDREW AVE	AETNA ST	Even	23	4	Concrete	Defer Maintenance	Excellent	\$0.00
RUBBER AVE-08	AETNA ST	SOUTHVIEW ST	Odd	425	4	Concrete	25% Replacement	Fair	\$9,444.44
RUBBER AVE-09	SOUTHVIEW ST	MEADOW ST	Even	452	4	Concrete	10% Replacement	Good	\$3,013.33
RUBBER AVE-09	SOUTHVIEW ST	MEADOW ST	Odd	452	4	Concrete	10% Replacement	Good	\$3,013.33
RUBBER AVE-10	MEADOW ST	ELM ST	Even	622	4	Concrete	25% Replacement	Fair	\$13,822.22
RUBBER AVE-10	MEADOW ST	ELM ST	Odd	622	4	Concrete	10% Replacement	Good	\$4,146.67
Total Length: 2,775								Total Cost:	\$33,440.00
RUBBER AVENUE EXTENSION									
RUBBER AVE EXT-01	NEUMANN ST	FIELD ST	Even	535	4	Concrete	Defer Maintenance	Excellent	\$0.00
RUBBER AVE EXT-03	SOUTHWOOD APT RD	CROFUT RD	Even	108	3	Concrete	10% Replacement	Good	\$540.00
RUBBER AVE EXT-04	CROFUT RD	BRIGHTON RD	Odd	431	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,074								Total Cost:	\$540.00
S MAIN STREET (ROUTE 63)									
S MAIN ST (ROUTE 63)-02	MAPLE ST	HOTCHKISS ST	Odd	759	6	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 759								Total Cost:	\$0.00
SALEM STREET									
SALEM ST-01	MILLVILLE AVE	ROCKWELL AVE	Even	151	4	Concrete	50% Replacement	Poor	\$5,033.33
SALEM ST-02	ROCKWELL AVE	NEW ST	Even	372	4	Concrete	100% Replacement	Replace	\$24,800.00
SALEM ST-02	ROCKWELL AVE	NEW ST	Odd	372	4	Concrete	50% Replacement	Poor	\$12,400.00
Total Length: 895								Total Cost:	\$42,233.33
SANDE AVENUE									
SANDE AVE-02	RADNOR AVE	WATERBURY TL	Even	249	4	Concrete	25% Replacement	Fair	\$5,533.33
SANDE AVE-02	RADNOR AVE	WATERBURY TL	Odd	174	4	Concrete	50% Replacement	Poor	\$5,800.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 423								Total Cost: \$11,333.33	
SCHOOL STREET									
SCHOOL ST-01	BRIDGE ST	ANDERSON ST	Even	20	4	Concrete	Defer Maintenance	Excellent	\$0.00
SCHOOL ST-02	ANDERSON ST	SCHOOL ST EXT	Even	125	4	Concrete	10% Replacement	Good	\$833.33
SCHOOL ST-02	ANDERSON ST	SCHOOL ST EXT	Odd	836	4	Concrete	50% Replacement	Poor	\$27,866.67
SCHOOL ST-03	SCHOOL ST EXT	DEAD END	Odd	418	4	Concrete	50% Replacement	Poor	\$13,933.33
Total Length: 1,399								Total Cost: \$42,633.33	
SETH DRIVE									
SETH DR	HIGHLAND AVE	CUL DE SAC	Even	291	4	Concrete	Defer Maintenance	Excellent	\$0.00
SETH DR	HIGHLAND AVE	CUL DE SAC	Odd	412	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 703								Total Cost: \$0.00	
SHERMAN STREET									
SHERMAN ST-01	NORHT CHURCH ST	BEECHER ST	Even	662	4	Concrete	10% Replacement	Good	\$4,413.33
SHERMAN ST-01	NORHT CHURCH ST	BEECHER ST	Odd	629	4	Concrete	50% Replacement	Poor	\$20,966.67
SHERMAN ST-02	BEECHER ST	HILLSIDE AVE	Even	352	3	Concrete	10% Replacement	Good	\$1,760.00
SHERMAN ST-02	BEECHER ST	HILLSIDE AVE	Odd	352	4	Concrete	25% Replacement	Fair	\$7,822.22
Total Length: 1,995								Total Cost: \$34,962.22	
SIERRA RIDGE ROAD									
SIERRA RIDGE RD	DONOVAN RD	CUL DE SAC	Even	958	4	Concrete	Defer Maintenance	Excellent	\$0.00
SIERRA RIDGE RD	DONOVAN RD	CUL DE SAC	Odd	958	4	Concrete	10% Replacement	Good	\$6,386.67
Total Length: 1,916								Total Cost: \$6,386.67	
SILVER BEECH DRIVE									
SILVER BEECH DR-01	MAPLE HILL RD	POND VALLY RD	Even	381	4	Concrete	Defer Maintenance	Excellent	\$0.00
SILVER BEECH DR-01	MAPLE HILL RD	POND VALLY RD	Odd	381	4	Concrete	Defer Maintenance	Excellent	\$0.00
SILVER BEECH DR-02	POND VALLY RD	PINEWOOD CROSSING SOUTH	Even	531	4	Concrete	Defer Maintenance	Excellent	\$0.00
SILVER BEECH DR-02	POND VALLY RD	PINEWOOD CROSSING SOUTH	Odd	531	4	Concrete	Defer Maintenance	Excellent	\$0.00
SILVER BEECH DR-03	PINEWOOD CROSSING SO	CUL DE SAC	Even	386	4	Concrete	Defer Maintenance	Excellent	\$0.00
SILVER BEECH DR-03	PINEWOOD CROSSING SO	CUL DE SAC	Odd	386	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 2,596								Total Cost: \$0.00	
SKYVIEW DRIVE									
SKYVIEW DR-01	CITY BROOK RD	WINDVIEW DR	Even	445	4	Concrete	Defer Maintenance	Excellent	\$0.00
SKYVIEW DR-01	CITY BROOK RD	WINDVIEW DR	Odd	445	4	Concrete	10% Replacement	Good	\$2,966.67
SKYVIEW DR-02	WINDVIEW DR	APPLEWOOD LN	Even	417	4	Concrete	Defer Maintenance	Excellent	\$0.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
SKYVIEW DR-02	WINDVIEW DR	APPLEWOOD LN	Odd	417	4	Concrete	10% Replacement	Good	\$2,780.00
Total Length: 1,724								Total Cost: \$5,746.67	
SMITH STREET									
SMITH ST	N MAIN ST	ROUTE 8	Even	189	4	Concrete	10% Replacement	Good	\$1,260.00
SMITH ST	N MAIN ST	ROUTE 8	Odd	9	4	Concrete	10% Replacement	Good	\$60.00
Total Length: 198								Total Cost: \$1,320.00	
SOUTH CIRCLE									
SOUTH CIR	BROOKSIDE AVE	CUL DE SAC	Even	173	4	Concrete	25% Replacement	Fair	\$3,844.44
Total Length: 173								Total Cost: \$3,844.44	
SPENCER STREET									
SPENCER ST-01	ELM ST	WARD ST	Even	402	4	Concrete	Defer Maintenance	Excellent	\$0.00
SPENCER ST-02	WARD ST	CHERRY ST	Even	414	4	Concrete	10% Replacement	Good	\$2,760.00
SPENCER ST-03	CHERRY ST	GORMAN ST	Odd	399	4	Concrete	25% Replacement	Fair	\$8,866.67
SPENCER ST-06	SHARON AVE	LEWIS ST	Odd	532	3	Concrete	25% Replacement	Fair	\$8,866.67
SPENCER ST-09	IDA ST	IRVING ST	Even	598	4	Concrete	50% Replacement	Poor	\$19,933.33
SPENCER ST-09	IDA ST	IRVING ST	Odd	598	4	Concrete	50% Replacement	Poor	\$19,933.33
SPENCER ST-10	IRVING ST	DEAD END	Even	125	4	Concrete	10% Replacement	Good	\$833.33
SPENCER ST-10	IRVING ST	DEAD END	Odd	125	4	Concrete	10% Replacement	Good	\$833.33
Total Length: 3,193								Total Cost: \$62,026.67	
SPRING STREET									
SPRING ST-01	BRIDGE ST	DIAMOND ST	Even	491	4	Concrete	10% Replacement	Good	\$3,273.33
SPRING ST-01	BRIDGE ST	DIAMOND ST	Odd	491	4	Concrete	25% Replacement	Fair	\$10,911.11
SPRING ST-02	DIAMOND ST	ANDERSON ST	Even	206	4	Concrete	25% Replacement	Fair	\$4,577.78
SPRING ST-02	DIAMOND ST	ANDERSON ST	Odd	206	4	Concrete	25% Replacement	Fair	\$4,577.78
SPRING ST-03	ANDERSON ST	DUNN LN	Even	643	4	Concrete	25% Replacement	Fair	\$14,288.89
SPRING ST-03	ANDERSON ST	DUNN LN	Odd	643	4	Concrete	50% Replacement	Poor	\$21,433.33
Total Length: 2,680								Total Cost: \$59,062.22	
SWEENEY STREET									
SWEENEY ST	WALNUT ST	HILLSIDE AVE	Even	237	4	Concrete	25% Replacement	Fair	\$5,266.67
SWEENEY ST	WALNUT ST	HILLSIDE AVE	Odd	237	4	Concrete	25% Replacement	Fair	\$5,266.67
Total Length: 474								Total Cost: \$10,533.33	
SWIFT LANE									
SWIFT LN	FAWN MEADOW DR	BLUEBIRD DR	Even	152	4	Concrete	10% Replacement	Good	\$1,013.33

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
SWIFT LN	FAWN MEADOW DR	BLUEBIRD DR	Odd	152	4	Concrete	10% Replacement	Good	\$1,013.33
Total Length: 304								Total Cost:	\$2,026.67
TERRACE AVENUE									
TERRACE AVE-03	SALEM ST	WATER ST	Even	385	4	Concrete	10% Replacement	Good	\$2,566.67
TERRACE AVE-03	SALEM ST	WATER ST	Odd	385	4	Concrete	10% Replacement	Good	\$2,566.67
Total Length: 770								Total Cost:	\$5,133.33
TIDMOUTH LANE									
TIDMOUTH LN	UNION CITY RD	CUL DE SAC	Even	323	4	Concrete	10% Replacement	Good	\$2,153.33
TIDMOUTH LN	UNION CITY RD	CUL DE SAC	Odd	538	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 861								Total Cost:	\$2,153.33
TROWBRIDGE PLACE									
TROWBRIDGE PL-01	CLIFF ST	NETTLETON AVE	Even	688	4	Concrete	50% Replacement	Poor	\$22,933.33
TROWBRIDGE PL-01	CLIFF ST	NETTLETON AVE	Odd	688	4	Concrete	25% Replacement	Fair	\$15,288.89
TROWBRIDGE PL-02	NETTLETON AVE	GOODYEAR AVE	Even	161	4	Concrete	Defer Maintenance	Excellent	\$0.00
TROWBRIDGE PL-02	NETTLETON AVE	GOODYEAR AVE	Odd	161	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,698								Total Cost:	\$38,222.22
TYLER HILL ROAD									
TYLER HILL RD	APPLEWOOD LN	CUL DE SAC	Even	976	4	Concrete	Defer Maintenance	Excellent	\$0.00
TYLER HILL RD	APPLEWOOD LN	CUL DE SAC	Odd	925	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,901								Total Cost:	\$0.00
UNION CITY ROAD									
UNION CITY RD-03	TIDMOUTH LN	GAIL DR	Even	372	4	Concrete	10% Replacement	Good	\$2,480.00
Total Length: 372								Total Cost:	\$2,480.00
WALNUT STREET									
WALNUT ST-01	NEW ST	GROVE ST	Even	214	4	Concrete	10% Replacement	Good	\$1,426.67
WALNUT ST-01	NEW ST	GROVE ST	Odd	429	4	Concrete	50% Replacement	Poor	\$14,300.00
WALNUT ST-02	GROVE ST	MILLVILLE AVE	Even	795	4	Concrete	100% Replacement	Replace	\$53,000.00
WALNUT ST-02	GROVE ST	MILLVILLE AVE	Odd	795	4	Concrete	50% Replacement	Poor	\$26,500.00
WALNUT ST-03	MILLVILLE AVE	SWEENEY ST	Even	279	4	Concrete	50% Replacement	Poor	\$9,300.00
WALNUT ST-03	MILLVILLE AVE	SWEENEY ST	Odd	279	4	Concrete	25% Replacement	Fair	\$6,200.00
WALNUT ST-04	SWEENEY ST	ELMWOOD ST	Even	537	4	Concrete	25% Replacement	Fair	\$11,933.33
WALNUT ST-04	SWEENEY ST	ELMWOOD ST	Odd	537	4	Concrete	25% Replacement	Fair	\$11,933.33
WALNUT ST-05	ELMWOOD ST	WALNUT TER	Even	113	4	Concrete	25% Replacement	Fair	\$2,511.11

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
WALNUT ST-05	ELMWOOD ST	WALNUT TER	Odd	113	4	Concrete	25% Replacement	Fair	\$2,511.11
WALNUT ST-06	WALNUT TER	HIGHLAND CIR	Even	161	4	Concrete	25% Replacement	Fair	\$3,577.78
WALNUT ST-07	HIGHLAND CIR	HIGHLAND AVE	Even	121	4	Concrete	10% Replacement	Good	\$806.67
WALNUT ST-07	HIGHLAND CIR	HIGHLAND AVE	Odd	121	4	Concrete	25% Replacement	Fair	\$2,688.89
WALNUT ST-08	HIGHLAND AVE	CLIFF ST	Odd	109	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 4,603								Total Cost:	\$146,688.89
WALNUT TERRACE									
WALNUT TER	WALNUT ST	PARK AVE	Even	415	3	Concrete	25% Replacement	Fair	\$6,916.67
WALNUT TER	WALNUT ST	PARK AVE	Odd	415	3	Concrete	25% Replacement	Fair	\$6,916.67
Total Length: 830								Total Cost:	\$13,833.33
WARD STREET									
WARD ST-01	ELM ST	NEVILLE ST	Even	537	4	Concrete	100% Replacement	Replace	\$35,800.00
WARD ST-02	NEVILLE ST	SPENCER ST	Odd	1408	4	Concrete	50% Replacement	Poor	\$46,933.33
Total Length: 1,945								Total Cost:	\$82,733.33
WATER STREET									
WATER ST-02	MILLVILLE AVE	CEDAR ST	Even	1279	6	Concrete	25% Replacement	Fair	\$42,633.33
Total Length: 1,279								Total Cost:	\$42,633.33
WESTOVER DRIVE									
WESTOVER DR-01	KRODEL RD	GRAHAM RIDGE RD	Even	243	4	Concrete	Defer Maintenance	Excellent	\$0.00
WESTOVER DR-01	KRODEL RD	GRAHAM RIDGE RD	Odd	243	4	Concrete	10% Replacement	Good	\$1,620.00
WESTOVER DR-02	GRAHAM RIDGE RD	GRAHAM RIDGE RD	Even	538	4	Concrete	25% Replacement	Fair	\$11,955.56
WESTOVER DR-02	GRAHAM RIDGE RD	GRAHAM RIDGE RD	Odd	538	4	Concrete	Defer Maintenance	Excellent	\$0.00
WESTOVER DR-03	GRAHAM RIDGE RD	WEBB RD	Even	421	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,983								Total Cost:	\$13,575.56
WILD CHERRY DRIVE									
WILD CHERRY DR	FAWN MEADOW DR	CUL DE SAC	Even	284	4	Concrete	Defer Maintenance	Excellent	\$0.00
WILD CHERRY DR	FAWN MEADOW DR	CUL DE SAC	Odd	284	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 568								Total Cost:	\$0.00
WINDVIEW DRIVE									
WINDVIEW DR	SKYVIEW DR	CUL DE SAC	Even	527	4	Concrete	10% Replacement	Good	\$3,513.33
WINDVIEW DR	SKYVIEW DR	CUL DE SAC	Odd	527	4	Concrete	10% Replacement	Good	\$3,513.33
Total Length: 1,054								Total Cost:	\$7,026.67
WINSLOW COURT									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
WINSLOW CT	MEADOW ST	DEAD END	Even	69	2	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 69								Total Cost: \$0.00	
WISTERIA DRIVE									
WISTERIA DR-01	OSBORN RD	ROLLINGWOOD DR	Even	482	4	Concrete	10% Replacement	Good	\$3,213.33
WISTERIA DR-01	OSBORN RD	ROLLINGWOOD DR	Odd	482	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-02	ROLLINGWOOD DR	ADRIATIC LN	Even	1672	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-02	ROLLINGWOOD DR	ADRIATIC LN	Odd	1672	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-03	ADRIATIC LN	ROLLINGWOOD DR	Even	981	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-03	ADRIATIC LN	ROLLINGWOOD DR	Odd	981	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-04	ROLLINGWOOD DR	CUL DE SAC	Even	759	4	Concrete	Defer Maintenance	Excellent	\$0.00
WISTERIA DR-04	ROLLINGWOOD DR	CUL DE SAC	Odd	759	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 7,788								Total Cost: \$3,213.33	
WOOD STREET									
WOOD ST	N MAIN ST	DEAD END	Odd	223	4	Concrete	50% Replacement	Poor	\$7,433.33
Total Length: 223								Total Cost: \$7,433.33	
WOOSTER STREET									
WOOSTER ST-04	DONOVAN RD	KOSKO LN	Odd	454	4	Concrete	10% Replacement	Good	\$3,026.67
WOOSTER ST-05	KOSKO LN	WHITNEY PL	Odd	417	4	Concrete	Defer Maintenance	Excellent	\$0.00
WOOSTER ST-07	APPLEWOOD LN	GLEN HOLLOW RD	Even	321	4	Concrete	Defer Maintenance	Excellent	\$0.00
Total Length: 1,192								Total Cost: \$3,026.67	

Borough of Naugatuck, Connecticut

Pavement Management Program

Sidewalk Condition and Estimated Replacement Costs - Mix Materials

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
ANDREW AVENUE									
ANDREW AVE-03	MANNERS AVE	MELBOURNE ST	Even	959	4	Mix	10% Replacement	Good	\$6,393.33
									Total Cost: \$6,393.33
ARCH STREET									
ARCH ST	SCOTT ST	RUBBER AVE	Even	737	4	Mix	25% Replacement	Fair	\$8,188.89
									Total Cost: \$8,188.89
BARNUM COURT									
BARNUM CT	CHURCH ST	DEAD END	Even	60	2	Mix	10% Replacement	Good	\$200.00
									Total Cost: \$200.00
BEEBE STREET									
BEEBE ST	AETNA ST	HIGHLAND AVE	Odd	986	4	Mix	25% Replacement	Fair	\$10,955.56
									Total Cost: \$10,955.56
BRADLEY STREET									
BRADLEY ST	OAK ST	HILL ST	Odd	555	4	Mix	25% Replacement	Fair	\$6,166.67
									Total Cost: \$6,166.67
BROOKSIDE AVENUE									
BROOKSIDE AVE-02	NORTH CIR	SOUTH CIR	Odd	288	4	Mix	50% Replacement	Poor	\$6,400.00
BROOKSIDE AVE-03	SOUTH CIR	MELBOURNE CT	Even	373	4	Mix	25% Replacement	Fair	\$4,144.44
									Total Cost: \$10,544.44
CEDAR STREET									
CEDAR ST	CHURCH ST	WATER ST	Odd	578	5	Mix	10% Replacement	Good	\$4,816.67
									Total Cost: \$4,816.67
CHESTNUT STREET									
CHESTNUT ST-01	N HOADLEY ST	FERN ST	Odd	277	4	Mix	100% Replacement	Replace	\$9,233.33
CHESTNUT ST-03	QUINN ST	PARK AVE	Odd	143	3	Mix	10% Replacement	Good	\$715.00
									Total Cost: \$9,948.33
CITY HILL STREET									
CITY HILL ST-01	N MIAN ST	CITY HILL CT	Odd	641	4	Mix	25% Replacement	Fair	\$7,122.22
									Total Cost: \$7,122.22
CLIFF STREET									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
CLIFF ST-02	LE CLAIR CT	PLEASANT VIEW ST	Odd	467	4	Mix	10% Replacement	Good	\$3,113.33
Total Length: 467									Total Cost: \$3,113.33
CURTISS STREET									
CURTISS ST-02	LINDEN ST	GRIFFIN ST	Odd	106	4	Mix	Defer Maintenance	Excellent	\$0.00
Total Length: 106									Total Cost: \$0.00
DAMSON LANE									
DAMSON LN-01	N HOADLEY ST	BIRCH LN	Even	188	4	Mix	10% Replacement	Good	\$1,253.33
DAMSON LN-02	BIRCH LN	N HOADLEY ST	Even	866	4	Mix	100% Replacement	Replace	\$28,866.67
Total Length: 1,054									Total Cost: \$30,120.00
DEERING LANE									
DEERING LN	N HOADLEY ST	DEAD END	Even	588	4	Mix	10% Replacement	Good	\$3,920.00
DEERING LN	N HOADLEY ST	DEAD END	Odd	588	4	Mix	25% Replacement	Fair	\$6,533.33
Total Length: 1,176									Total Cost: \$10,453.33
ELM STREET									
ELM ST-01	RUBBER AVE	SCOTT ST	Odd	826	4	Mix	25% Replacement	Fair	\$9,177.78
ELM ST-03	CHERRY ST	SPENCER ST	Odd	321	4	Mix	100% Replacement	Replace	\$10,700.00
Total Length: 1,147									Total Cost: \$19,877.78
FAIRCHILD STREET									
FAIRCHILD ST-01	LEWIS ST	MALGARI CT	Odd	429	4	Mix	25% Replacement	Fair	\$4,766.67
FAIRCHILD ST-02	MALGARI CT	HARD ST	Odd	234	4	Mix	10% Replacement	Good	\$1,560.00
Total Length: 663									Total Cost: \$6,326.67
FAIRVIEW AVENUE									
FAIRVIEW AVE-01	POND ST	PLEASANT VIEW ST	Odd	277	5	Mix	10% Replacement	Good	\$2,308.33
FAIRVIEW AVE-02	PLEASANT VIEW ST	GEORGE ST	Odd	748	0	Mix	10% Replacement	Good	\$0.00
Total Length: 1,025									Total Cost: \$2,308.33
FERN STREET									
FERN ST-02	COTTAGE ST	MILLVILLE AVE	Even	654	4	Mix	100% Replacement	Replace	\$21,800.00
FERN ST-02	COTTAGE ST	MILLVILLE AVE	Odd	588	4	Mix	25% Replacement	Fair	\$6,533.33
Total Length: 1,242									Total Cost: \$28,333.33
GALPIN STREET									
GALPIN ST-03	WEST ST	HIGHLAND AVE	Even	225	4	Mix	25% Replacement	Fair	\$2,500.00
GALPIN ST-03	WEST ST	HIGHLAND AVE	Odd	225	4	Mix	25% Replacement	Fair	\$2,500.00
Total Length: 450									Total Cost: \$5,000.00
GORMAN STREET									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
GORMAN ST-02	OLIVE ST	VAGNINI DR	Even	328	6	Mix	25% Replacement	Fair	\$5,466.67
GORMAN ST-02	OLIVE ST	VAGNINI DR	Odd	328	6	Mix	25% Replacement	Fair	\$5,466.67
GORMAN ST-04	FAIRCHILD ST	SPENCER ST	Odd	281	4	Mix	25% Replacement	Fair	\$3,122.22
Total Length: 937								Total Cost:	\$14,055.56
GROVE STREET									
GROVE ST-01	PARK AVE	MAY AVE	Odd	355	4	Mix	25% Replacement	Fair	\$3,944.44
GROVE ST-04	WOODLAWN AVE	HILLSIDE AVE	Even	371	4	Mix	10% Replacement	Good	\$2,473.33
Total Length: 726								Total Cost:	\$6,417.78
HIGH STREET									
HIGH ST-07	OAK ST	HILL ST	Odd	508	4	Mix	100% Replacement	Replace	\$16,933.33
HIGH ST-09	MAY ST	CARROLL ST	Even	833	4	Mix	50% Replacement	Poor	\$18,511.11
HIGH ST-11	HILL ST	HICKORY RD	Even	352	4	Mix	Defer Maintenance	Excellent	\$0.00
HIGH ST-13	WOODLAND ST	S MAIN ST	Even	1502	4	Mix	25% Replacement	Fair	\$16,688.89
Total Length: 3,195								Total Cost:	\$52,133.33
HIGHLAND AVENUE									
HIGHLAND AVE-02	GALPIN ST	BEEBE ST	Even	250	4	Mix	50% Replacement	Poor	\$5,555.56
HIGHLAND AVE-02	GALPIN ST	BEEBE ST	Odd	250	4	Mix	25% Replacement	Fair	\$2,777.78
HIGHLAND AVE-03	BEEBE ST	DUNN AVE	Even	343	5	Mix	50% Replacement	Poor	\$9,527.78
HIGHLAND AVE-03	BEEBE ST	DUNN AVE	Odd	343	5	Mix	25% Replacement	Fair	\$4,763.89
HIGHLAND AVE-04	DUNN AVE	HIGHLAND CIR	Even	551	4	Mix	25% Replacement	Fair	\$6,122.22
HIGHLAND AVE-04	DUNN AVE	HIGHLAND CIR	Odd	551	4	Mix	50% Replacement	Poor	\$12,244.44
Total Length: 2,288								Total Cost:	\$40,991.67
HILL STREET									
HILL ST-02	FAIRLAWN ST	CULVER ST	Even	274	4	Mix	25% Replacement	Fair	\$3,044.44
HILL ST-03	MAY ST	FAIRLAWN ST	Odd	237	4	Mix	25% Replacement	Fair	\$2,633.33
Total Length: 511								Total Cost:	\$5,677.78
HILLSIDE AVENUE									
HILLSIDE AVE-06	SALEM ST	GROVE ST	Even	647	4	Mix	50% Replacement	Poor	\$14,377.78
HILLSIDE AVE-09	MILLVILLE AVE	SWEENEY ST	Even	364	4	Mix	10% Replacement	Good	\$2,426.67
HILLSIDE AVE-13	PAVEMENT CHANGE	FAIRVIEW AVE	Odd	250	4	Mix	25% Replacement	Fair	\$2,777.78
Total Length: 1,261								Total Cost:	\$19,582.22
HOTCHKISS STREET									
HOTCHKISS ST	S MAIN ST	DEAD END	Even	643	4	Mix	25% Replacement	Fair	\$7,144.44
HOTCHKISS ST	S MAIN ST	DEAD END	Odd	482	4	Mix	25% Replacement	Fair	\$5,355.56

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 1,125								Total Cost: \$12,500.00	
LEWIS STREET									
LEWIS ST-01	SCOTT ST	NIXON AVE	Odd	247	4	Mix	50% Replacement	Poor	\$5,488.89
LEWIS ST-02	NIXON AVE	MANNERS AVE	Even	191	4	Mix	25% Replacement	Fair	\$2,122.22
Total Length: 438								Total Cost: \$7,611.11	
LINDEN STREET									
LINDEN ST-01	N MAIN ST	CURTISS ST	Odd	227	4	Mix	Defer Maintenance	Excellent	\$0.00
Total Length: 227								Total Cost: \$0.00	
MANNERS AVENUE									
MANNERS AVE-02	RUSSELL ST	THERESA ST	Even	339	4	Mix	25% Replacement	Fair	\$3,766.67
Total Length: 339								Total Cost: \$3,766.67	
MAPLE STREET									
MAPLE ST-07	MAPLE TER	HILL ST	Even	126	4	Mix	Defer Maintenance	Excellent	\$0.00
Total Length: 126								Total Cost: \$0.00	
MAPLE TERRACE									
MAPLE TER	MAPLE ST	MAY ST	Odd	312	4	Mix	25% Replacement	Fair	\$3,466.67
Total Length: 312								Total Cost: \$3,466.67	
MAY AVENUE									
MAY AVE-03	GROVE ST	MILLVILLE AVE	Even	816	4	Mix	100% Replacement	Replace	\$27,200.00
Total Length: 816								Total Cost: \$27,200.00	
MAY STREET									
MAY ST-01	HIGH ST	HILL ST	Even	336	4	Mix	25% Replacement	Fair	\$3,733.33
Total Length: 336								Total Cost: \$3,733.33	
MILLVILLE AVENUE									
MILLVILLE AVE-08	N HOADLEY ST	FERN ST	Even	281	4	Mix	25% Replacement	Fair	\$3,122.22
MILLVILLE AVE-11	PARK AVE	WALNUT ST	Odd	430	4	Mix	25% Replacement	Fair	\$4,777.78
MILLVILLE AVE-14	HILLSIDE AVE	TERRACE AVE	Even	379	4	Mix	25% Replacement	Fair	\$4,211.11
Total Length: 1,090								Total Cost: \$12,111.11	
MOORE AVENUE									
MOORE AVE-01	CLIFF ST	LYNN RD	Even	550	3	Mix	25% Replacement	Fair	\$4,583.33
Total Length: 550								Total Cost: \$4,583.33	
N HOADLEY STREET									
N HOADLEY ST-01	MILLVILLE AVE	COTTAGE ST	Even	687	4	Mix	25% Replacement	Fair	\$7,633.33
N HOADLEY ST-01	MILLVILLE AVE	COTTAGE ST	Odd	549	4	Mix	25% Replacement	Fair	\$6,100.00

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
N HOADLEY ST-02	COTTAGE ST	PHYLLIS DR	Even	267	4	Mix	10% Replacement	Good	\$1,780.00
N HOADLEY ST-04	CHESTNUT ST	DEERING LN	Odd	338	4	Mix	50% Replacement	Poor	\$7,511.11
N HOADLEY ST-05	DEERING LN	BIRCH LN	Even	390	4	Mix	50% Replacement	Poor	\$8,666.67
N HOADLEY ST-05	DEERING LN	BIRCH LN	Odd	390	4	Mix	25% Replacement	Fair	\$4,333.33
N HOADLEY ST-06	DAMSON LN	SURREY DR	Even	254	4	Mix	25% Replacement	Fair	\$2,822.22
N HOADLEY ST-07	SURREY DR	DAMSON LN	Even	815	4	Mix	50% Replacement	Poor	\$18,111.11
N HOADLEY ST-07	SURREY DR	DAMSON LN	Odd	815	4	Mix	25% Replacement	Fair	\$9,055.56
N HOADLEY ST-08	DAMSON LN	QUINN ST	Even	433	4	Mix	50% Replacement	Poor	\$9,622.22
N HOADLEY ST-08	DAMSON LN	QUINN ST	Odd	433	4	Mix	25% Replacement	Fair	\$4,811.11

Total Length: 5,371

Total Cost: \$80,446.67

N MAIN STREET

N MAIN ST-04	GRIFFIN ST	SMITH ST	Odd	319	4	Mix	25% Replacement	Fair	\$3,544.44
N MAIN ST-05	SMITH ST	CITY HILL ST	Odd	522	4	Mix	Defer Maintenance	Excellent	\$0.00
N MAIN ST-07	PROSPECT ST	GOLDEN CT	Odd	206	4	Mix	10% Replacement	Good	\$1,373.33
N MAIN ST-10	MYRTLE AVE	WOODBINE ST	Odd	172	0	Mix	10% Replacement	Good	\$0.00

Total Length: 1,219

Total Cost: \$4,917.78

NEW STREET

NEW ST-02	HILLSIDE AVE	SVEA AVE	Odd	245	4	Mix	25% Replacement	Fair	\$2,722.22
-----------	--------------	----------	-----	-----	---	-----	-----------------	------	------------

Total Length: 245

Total Cost: \$2,722.22

OAK STREET

OAK ST-01	MAPLE ST	HIGH ST	Odd	793	4	Mix	50% Replacement	Poor	\$17,622.22
OAK ST-03	COEN ST	BRADLEY ST	Even	108	4	Mix	25% Replacement	Fair	\$1,200.00
OAK ST-04	BRADLEY ST	DEAD END	Even	178	4	Mix	50% Replacement	Poor	\$3,955.56
OAK ST-04	BRADLEY ST	DEAD END	Odd	89	4	Mix	100% Replacement	Replace	\$2,966.67

Total Length: 1,168

Total Cost: \$25,744.44

ORCHARD STREET

ORCHARD ST-01	HIGH ST	ORCHARD TER	Even	237	4	Mix	25% Replacement	Fair	\$2,633.33
ORCHARD ST-02	ORHCARD TER	N MAIN ST	Even	503	4	Mix	10% Replacement	Good	\$3,353.33
ORCHARD ST-02	ORHCARD TER	N MAIN ST	Odd	503	4	Mix	100% Replacement	Replace	\$16,766.67

Total Length: 1,243

Total Cost: \$22,753.33

ORCHARD TERRACE

ORCHARD TER	ORCHARD ST	DEAD END	Even	248	4	Mix	25% Replacement	Fair	\$2,755.56
-------------	------------	----------	------	-----	---	-----	-----------------	------	------------

Total Length: 248

Total Cost: \$2,755.56

PARK AVENUE

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
PARK AVE-03	GROVE ST	NEW ST	Even	346	4	Mix	25% Replacement	Fair	\$3,844.44
PARK AVE-06	EAST DR	HILLSIDE AVE	Odd	353	4	Mix	10% Replacement	Good	\$2,353.33
Total Length: 699								Total Cost: \$6,197.78	
PHOENIX AVENUE									
PHOENIX AVE	MAY ST	JOHNSON ST	Odd	378	4	Mix	50% Replacement	Poor	\$8,400.00
Total Length: 378								Total Cost: \$8,400.00	
PINE STREET									
PINE ST	HOADLEY ST	MILLVILLE AVE	Odd	858	4	Mix	10% Replacement	Good	\$5,720.00
Total Length: 858								Total Cost: \$5,720.00	
POND STREET									
POND ST-02	SOUTHVIEW ST	FAIRVIEW AVE	Odd	277	5	Mix	10% Replacement	Good	\$2,308.33
Total Length: 277								Total Cost: \$2,308.33	
QUINN STREET									
QUINN ST-02	N HOADLEY ST	QUINN ST-03	Odd	529	3	Mix	25% Replacement	Fair	\$4,408.33
QUINN ST-03	QUINN ST-02	SURREY DR	Even	857	3	Mix	25% Replacement	Fair	\$7,141.67
QUINN ST-05	EAST DR	QUINN ST-02	Odd	649	3	Mix	50% Replacement	Poor	\$10,816.67
QUINN ST-06	SURREY DR	CHESTNUT ST	Even	1035	3	Mix	25% Replacement	Fair	\$8,625.00
QUINN ST-06	SURREY DR	CHESTNUT ST	Odd	1035	3	Mix	50% Replacement	Poor	\$17,250.00
Total Length: 4,105								Total Cost: \$48,241.67	
RADNOR AVENUE									
RADNOR AVE-04	SANDE AVE	WATERBURY TL	Odd	279	4	Mix	Defer Maintenance	Excellent	\$0.00
Total Length: 279								Total Cost: \$0.00	
RUBBER AVENUE									
RUBBER AVE-01	NEUMANN ST	WOODRUFF AVE	Odd	1434	4	Mix	10% Replacement	Good	\$9,560.00
RUBBER AVE-03	ZOCZAK CT	BROOKSIDE AVE	Even	97	4	Mix	10% Replacement	Good	\$646.67
RUBBER AVE-03	ZOCZAK CT	BROOKSIDE AVE	Odd	645	4	Mix	10% Replacement	Good	\$4,300.00
RUBBER AVE-04	BROOKSIDE AVE	MELBOURNE ST	Odd	1117	4	Mix	10% Replacement	Good	\$7,446.67
RUBBER AVE-05	MELBOURNE ST	EDWARD ST	Even	113	4	Mix	10% Replacement	Good	\$753.33
RUBBER AVE-05	MELBOURNE ST	EDWARD ST	Odd	1131	4	Mix	10% Replacement	Good	\$7,540.00
RUBBER AVE-06	EDWARD ST	ANDREW AVE	Even	342	4	Mix	10% Replacement	Good	\$2,280.00
RUBBER AVE-06	EDWARD ST	ANDREW AVE	Odd	489	4	Mix	10% Replacement	Good	\$3,260.00
RUBBER AVE-08	AETNA ST	SOUTHVIEW ST	Even	64	4	Mix	25% Replacement	Fair	\$711.11
Total Length: 5,432								Total Cost: \$36,497.78	
SALEM STREET									

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
SALEM ST-01	MILLVILLE AVE	ROCKWELL AVE	Odd	1009	4	Mix	100% Replacement	Replace	\$33,633.33
Total Length: 1,009								Total Cost: \$33,633.33	
SANDE AVENUE									
SANDE AVE-01	PLATTS MILLS RD	RADNOR AVE	Even	278	4	Mix	50% Replacement	Poor	\$6,177.78
SANDE AVE-01	PLATTS MILLS RD	RADNOR AVE	Odd	278	4	Mix	50% Replacement	Poor	\$6,177.78
Total Length: 556								Total Cost: \$12,355.56	
SCHOOL STREET									
SCHOOL ST-01	BRIDGE ST	ANDERSON ST	Odd	405	4	Mix	10% Replacement	Good	\$2,700.00
Total Length: 405								Total Cost: \$2,700.00	
SCOTT STREET									
SCOTT ST-01	ELM ST	GORMAN ST	Even	794	4	Mix	Defer Maintenance	Excellent	\$0.00
SCOTT ST-01	ELM ST	GORMAN ST	Odd	836	4	Mix	10% Replacement	Good	\$5,573.33
SCOTT ST-02	GORMAN ST	ARCH ST	Odd	243	4	Mix	100% Replacement	Replace	\$8,100.00
SCOTT ST-03	ARCH ST	THERESA ST	Odd	684	4	Mix	100% Replacement	Replace	\$22,800.00
SCOTT ST-04	THERESA ST	ANDREW AVE	Even	435	4	Mix	25% Replacement	Fair	\$4,833.33
SCOTT ST-04	THERESA ST	ANDREW AVE	Odd	544	4	Mix	100% Replacement	Replace	\$18,133.33
SCOTT ST-05	ANDREW AVE	MELBOURNE ST	Even	690	4	Mix	100% Replacement	Replace	\$23,000.00
SCOTT ST-05	ANDREW AVE	MELBOURNE ST	Odd	863	4	Mix	50% Replacement	Poor	\$19,177.78
Total Length: 5,089								Total Cost: \$101,617.78	
SPENCER STREET									
SPENCER ST-02	WARD ST	CHERRY ST	Odd	166	4	Mix	10% Replacement	Good	\$1,106.67
Total Length: 166								Total Cost: \$1,106.67	
SURREY DRIVE									
SURREY DR	N HOADLEY ST	QUINN ST	Even	303	4	Mix	50% Replacement	Poor	\$6,733.33
SURREY DR	N HOADLEY ST	QUINN ST	Odd	303	4	Mix	50% Replacement	Poor	\$6,733.33
Total Length: 606								Total Cost: \$13,466.67	
TERRACE AVENUE									
TERRACE AVE-01	HILLSIDE AVE	MILLVILLE AVE	Even	1130	4	Mix	50% Replacement	Poor	\$25,111.11
TERRACE AVE-01	HILLSIDE AVE	MILLVILLE AVE	Odd	283	4	Mix	Defer Maintenance	Excellent	\$0.00
TERRACE AVE-02	MILLVILLE AVE	SALEM ST	Odd	478	4	Mix	10% Replacement	Good	\$3,186.67
Total Length: 1,891								Total Cost: \$28,297.78	
WARD STREET									
WARD ST-01	ELM ST	NEVILLE ST	Odd	537	4	Mix	10% Replacement	Good	\$3,580.00
WARD ST-02	NEVILLE ST	SPENCER ST	Even	1408	4	Mix	50% Replacement	Poor	\$31,288.89

	From	To	Side	Length	Width	Material	Repair Method	Condition	Cost
Total Length: 1,945								Total Cost: \$34,868.89	
WATER STREET									
WATER ST-01	NORTH CHURCH ST	MILLVILLE AVE	Odd	347	4	Mix	10% Replacement	Good	\$2,313.33
WATER ST-03	CEDAR ST	MAPLE ST	Even	776	4	Mix	25% Replacement	Fair	\$8,622.22
Total Length: 1,123								Total Cost: \$10,935.56	
WOOD STREET									
WOOD ST	N MAIN ST	DEAD END	Even	200	4	Mix	50% Replacement	Poor	\$4,444.44
Total Length: 200								Total Cost: \$4,444.44	
WOODLAWN AVENUE									
WOODLAWN AVE	GROVE ST	MILLVILLE AVE	Odd	795	4	Mix	25% Replacement	Fair	\$8,833.33
Total Length: 795								Total Cost: \$8,833.33	